

GOVERNMENT OF INDIA

ARCHAEOLOGICAL SURVEY OF INDIA


CENTRAL  
ARCHAEOLOGICAL  
LIBRARY

ACCESSION NO. 23356

CALL No. 737.470934/Gar/Poo

D.G.A. 79.





CATALOGUE

OF

INDIAN COINS

IS

THE BRITISH MUSEUM.


GREEK AND SCYTHIC KINGS OF BACTRIA  
AND INDIA.

LONDON:

PRINTED BY ORDER OF THE TRUSTEES.

LONGMANS & CO., PUBLISHERS, 15, ALBEMARLE STREET;  
H. QUARITCH, 15, FLEET STREET; & R. S. & CO., 12, BANCING STREET,  
COURT SQUARE, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100.

FROM J. HOLLIS & F. C. L. & CO., 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100.



# THE COINS

OF THE

GREEK AND SCYTHIC KINGS OF BACTRIA  
AND INDIA

IS

THE BRITISH MUSEUM.

23356

BY PERCY GARDNER, LITT. D.

CLARE PROFESSOR OF ARCHAEOLOGY IN THE UNIVERSITY OF CAMBRIDGE.


737-470934

Gar/Poo

EDITED BY

REGINALD STUART POOLE, LL.D.

CORRESPONDENCE OF THE BRITISH MUSEUM



PRINTED BY ORDER OF THE TRUSTEES.

1886.

LONDON  
PRINTED BY GIBBERT AND RIVINGTON, LIMITED,  
ST. JOHN'S SQUARE, CLARKENWELL, E.C.

CENTRAL ARCHAEOLOGICAL  
LIBRARY, NEW DELHI.

Acc. No. 23356

Date. 29. 3. 56

Call No. 737. 470 934 / Prof Gar

Gar/100

EDITOR'S PREFACE.

THE present volume contains all the coins which were issued by the Greek and Scythic kings who ruled in India and the neighbouring lands between the time of Alexander the Great and the third century A.D.

The work has been long and laborious, alike to compiler, editor, and printer. The number of unusual characters which it contains has greatly hindered its progress; but the typographical difficulties have not been the only ones. The history of the kings is very obscure, and the types employed on their coins often of a mixed and uncertain character. On the other hand, few fields of numismatics offer richer material, historical, archaeological, and even philological; though philological theories are necessarily excluded from these pages.

Special thanks are due to General Cunningham, R.E., who has allowed the compiler free use of his plates published in recent volumes of the Numismatic Chronicle, and has thus enabled the present work to be rendered far more complete than it could otherwise be: also to Professor Cecil Bendall, who has given valuable philological aid.

The system of transliteration adopted for Prakrit words is that used by Professor Aufrecht in the Sanskrit Catalogue of the Bodleian Library; also in the Catalogue of Books in the British Museum.

I have carefully revised the manuscript of this work, comparing each coin with the corresponding description.

REGINALD STUART POOLE.

# CONTENTS.

## INTRODUCTION:—

PAGE

### I. HISTORICAL OUTLINES:—

Alexander the Great . . . . .	xviii
Andragoras, Sophytes . . . . .	xix
Diodotus; Bactrian revolt . . . . .	xx
Euthydemus I.; invasion of Antiochus III. . . . .	xxi
Demetrius and Eucratides; conquest of India . . . . .	xxii
Plato, Pantaleon, Agathocles, Euthydemus II. . . . .	xxvi
Medals of Agathocles and Antinachus . . . . .	xxviii
Heliocles . . . . .	xxix
Chinese account of the Yuch-Chi . . . . .	xxx
Chart of Greek and Scythic dominions . . . . .	xxxiii
Successors of Heliocles . . . . .	xxxiv
Antalcidas and Lysias . . . . .	xxxiv
The Sonipat find . . . . .	xxxvi
Menander, Apollodotus . . . . .	xxxvii
Geographical data . . . . .	xxxviii
Ranjabala . . . . .	xxxix
Scythic Kings: Maues . . . . .	xl
Azes, Azilises . . . . .	xli
Parthian Kings: Gondophares, &c. . . . .	xliii
Sanabares . . . . .	xlvi
Saka Kings: Heraüs . . . . .	xlvii
Yuch-Chi Kings: Kadphises I. . . . .	xlviii
Kadaphes, Kadphises II. . . . .	xlix
Kanerkes and Hooetkes: their era . . . . .	l
Vasu Deva . . . . .	li

	PAGE
II. INSCRIPTIONS: GREEK, INDIAN, AND SCYTHIC . . . . .	liii
III. MONOGRAMS . . . . .	lv
IV. TYPES:—	
Greek types . . . . .	lvi
Semi-Hellenic types . . . . .	lvii
Hindu types . . . . .	lviii
Parthian types . . . . .	lix
Types of Yueh-Chi Kings . . . . .	lx
V. WEIGHTS . . . . .	lxvii
Normal weights of coins . . . . .	lxix
VI. THE ARIAN PALI ALPHABET . . . . .	lxx
VII. TABLE OF TRANSLITERATIONS AND RENDERINGS OF PRAKRIT LEGENDS . . . . .	lxxii

# COIN CATALOGUE:—

Andragoras . . . . .	1
Sophytes . . . . .	2
Diodotus I. . . . .	3
Euthydemus I. . . . .	4
Demetrius . . . . .	6
Euthydemus II. . . . .	8
Pantaleon . . . . .	9
Agathocles . . . . .	10
Antimachus I. . . . .	12
Eueratides . . . . .	13
Eueratides with Heliocles and Laodice . . . . .	19
Plato . . . . .	20
Heliocles . . . . .	21
Antialeidas . . . . .	25
Lysius . . . . .	29
Diomedes . . . . .	31
Archebius . . . . .	32
Apollodotus I. . . . .	34
Apollodotus II. . . . .	37
Strato I. . . . .	40
Agathocleia with Strato . . . . .	43

	PAGE
Menander . . . . .	44
Epander . . . . .	51
Dionysius . . . . .	51
Zoilus . . . . .	52
Apollophanes . . . . .	54
Artemidorus . . . . .	54
Antimachus II. . . . .	55
Philoxenus . . . . .	56
Nicias . . . . .	58
Hippostratus . . . . .	59
Amyntus . . . . .	61
Hermæus . . . . .	62
Hermæus and Calliope . . . . .	66
Ranjabala . . . . .	67
Manes . . . . .	68
Azes . . . . .	73
Azes and Azilises . . . . .	92
Azilises . . . . .	93
Spalahores with Vonones . . . . .	98
Spalagadames with Vonones . . . . .	99
Spalagadames with Spalyris . . . . .	100
Spalirises as King's brother . . . . .	100
Spalirises as King . . . . .	101
Spalirises with Azes . . . . .	102
Gondophares . . . . .	103
Abdagases . . . . .	107
Orthagnes . . . . .	109
Pacores . . . . .	110
Zeionises . . . . .	110
Uncertain Kings . . . . .	111
Sanabares . . . . .	113
Soter Magas . . . . .	114
Heraüs . . . . .	116
Hyrcodes . . . . .	117
Kings of uncertain name . . . . .	119
Hermæus and Kalphises I. . . . .	120
Kalphises I. . . . .	122

	PAGE
Kadaphes . . . . .	123
Kalphilises II. . . . .	124
Kauerkas . . . . .	129
Hooerkas . . . . .	136
Bazodeo (Vasu Deva) . . . . .	159
Indo-Scythic, Uncertain . . . . .	162

SUPPLEMENT (*Important types not in the British Museum*):—

Demetrius . . . . .	163
Pantaleon . . . . .	164
Agathocles . . . . .	164
Antimachus I. . . . .	164
Eueratides . . . . .	165
Heliocles . . . . .	166
Antialeidas . . . . .	166
Antialeidas and Lysias . . . . .	166
Theophilus . . . . .	167
Archebius . . . . .	167
Apolloclotus . . . . .	167
Strato I. . . . .	168
Strato II. . . . .	168
Menander . . . . .	168
Epander . . . . .	169
Dionysius . . . . .	169
Zoilus . . . . .	170
Antemidorus . . . . .	170
Philoxenus . . . . .	171
Nicias . . . . .	171
Telephus . . . . .	171
Amyntas . . . . .	171
Hermiacus . . . . .	172
Manes . . . . .	172
Azes and Azilises . . . . .	173
Azilises . . . . .	173
Vonones and Spalahores . . . . .	173
Gondophares . . . . .	174
Zeionises . . . . .	174

	PAGE
Arsaces Dikaios . . . . .	174
Arsaces Theos . . . . .	175
Kadphises II. . . . .	175
Kauerkes . . . . .	175

## INDEXES:—

I. Types . . . . .	177
II. Kings, Tyrants, &c. . . . .	184
III. Titles of Kings—	
<i>A.</i> Greek . . . . .	186
<i>B.</i> Scythic, in Greek letters . . . . .	187
<i>C.</i> Indian Titles and Words . . . . .	187
IV. Remarkable Inscriptions and Legends . . . . .	190
Table for converting English Inches into Millimètres and the Measures of Mionnet's Scale . . . . .	191
Table of the relative Weights of English Grains and French Grammes . . . . .	192



## LIST OF PLATES.

- I. Andragoras, Sophytes, Diodotus, Euthydemus I.
- II. Euthydemus I., Demetrius.
- III. Demetrius, Euthydemus II., Pantaleon.
- IV. Agathocles.
- V. Antimachus I., Eueratides.
- VI. Eueratides, Plato.
- VII. Heliccles, Antialcidas.
- VIII. Antialcidas, Lysias, Diomedes.
- IX. Archebius, Apollodotus.
- X. Apollodotus, Strato I.
- XI. Strato I., Agathocleia, Menander.
- XII. Menander, Epander, Dionysius, Zoilus.
- XIII. Apollonphanes, Artemidorus, Antimachus II., Philoxenus, Nicias.
- XIV. Hippostratus, Amyntas.
- XV. Hermaeus, Calliope, Ranjabala.
- XVI. Maues.
- XVII. Maues, Azes.
- XVIII. Azes.
- XIX. Azes.
- XX. Azes, Azilises.
- XXI. Azilises, Vonones, Spalahores, &c.
- XXII. Spalirises &c., Gondophares.
- XXIII. Abdagases, Zeionises &c., Pacores, Orthagnes, Sanabares.
- XXIV. Basilous Megas, Heraüs, Hyrooles, &c.
- XXV. Kadphises I., Kadaphes, Kadphises II.
- XXVI. Kanerkes.
- XXVII. Kanerkes, Hooerkes.
- XXVIII. Hooerkes.
- XXIX. Hooerkes, Bazodeu, &c.
- XXX. Supplementary.
- XXXI. "
- XXXII. "



THE COINS  
OF THE  
GREEK AND SCYTHIC KINGS  
OF  
BACTRIA AND INDIA.



## INTRODUCTION.

---

IN treating of the arrangement of the coins of the Greek and Scythic Kings of Bactria and India, it is necessary to enter briefly into all the known facts of their history. The Kings of the Seleucid and Ptolemaic dynasties succeeded one another in a known order, and the chief events of their reigns have been handed down to us by ancient writers. It was therefore unnecessary to give the facts of their history as an introduction to the lists of the coins issued by them. But in regard to all but two or three of the kings of the farther East, the ancient historians are quite silent; and coins and inscriptions alone save us from ignorance even of their names. Therefore it is necessary in this Introduction to trace the outlines of any history which can now be recovered, and in particular in some detail to set forth the historical facts which may fairly be established by means of the coins. In order to bring the discussion into the narrowest possible limits, it will be necessary (1) to abstain from mere conjecture, however tempting; (2) to avoid full discussion of disputed points, merely indicating where difference of opinion exists, and referring, when possible, to works already published, or monographs in various numismatic journals; (3) to treat in detail only such parts of history as have a numismatic bearing.

The writers to whom credit is due for the arrangement and decipherment of these coins are, in the first rank, James Prinsep\* and General Alexander Cunningham.†

\* *Essays on Indian Antiquities.*

† Coins of the Successors of Alexander, *Numismatic Chronicle*, 1868, &c.

Mr. E. Thomas,\* Lassen,† and Wilson,‡ have also done much important work, both historical and numismatic, in the same field. The most recent monograph on the coins is that of von Sallet,§ whose scholarly acquirements and solid numismatic judgment have enabled him to correct on many points the theories of his predecessors. Mr. James Fergusson's and Professor Cowell's researches have also been of the greatest value to the present purpose; and there is much valuable matter in von Gutschmid's article on the Græco-Parthian Empire in the ninth edition of the *Encyclopædia Britannica*, s. v. *Persia*. When a debt is due to other writers, it will be mentioned in the foot-notes.

## I. HISTORICAL OUTLINES.

The numismatics of the Greek rulers of India properly begins with Diodotus. But there are a few coins issued in India or neighbouring countries at an earlier period than his, which are, for convenience, included in this volume. Whether Alexander himself, during his sojourn in India, issued coins in his own name, may perhaps be doubted; but it is at least a plausible conjecture that certain bronze coins,|| bearing the usual types of Alexander and his name, but of square form, were issued in India, as the custom of issuing square coins already existed in India in Alexander's time, but in no other country. These pieces, then, unfortunately wanting in the British Museum, may be considered as the earliest Greek coins of India.

\* Notes to Prinsep's *Essays*.

† *Indische Alterthumskunde*.

‡ *Ariana Antiqua*.

§ *Zeitschrift für Numismatik*, Berlin 1879.

|| The conjecture is Dannenberg's, *Zeitschr. f. Num.* vi. 166 (note), who, however, gives the coins to Bactria. India is a far more reasonable attribution.

In recent years the region of Balkh (Bactria) has furnished an abundant supply of coins, issued by the immediate successors of Alexander in that district.\* Among these are double darics, with Greek letters on the obverse; gold and silver coins of the first three Antiochi, with the types of a seated Apollo and of a horse's head; silver coins of Seleucus I., with types of a chariot of elephants and a horse's head; coins issued during the joint reigns of Seleucus and Antiochus I., bearing the names of both rulers; and gold money of an early king of the Persepolitan class, with Pehlvi legend.

Among these also have come to light a few coins, in gold and silver, of a king named Andragoras, who is conjectured to have been ruler of Parthia or one of the neighbouring countries in the early part of the third century B.C. The only ancient authority who mentions this king is Justin,† who states Andragoras to have been the name of (1) a Persian noble set up as Satrap of Parthia by Alexander, (2) a Satrap of Parthia overthrown eighty years later by the first Arsaces. It is more probable that the coins published in our catalogue belong to the period of the second of these rulers. The issue of gold coin shows that the ruler who issued them claimed a complete independence; and this is a further reason for assigning him to the time of the break up of the Seleucid empire in the East, about B.C. 250.

The coins of Sophytes were first published by Cunningham.‡ They are the more interesting because their date and place of issue can be approximately fixed. We learn from several of the historians of Alexander's reign that Sopheithes, or Sophytes, ruled a district on the banks of the Acesines

\* P. Gardner, in *Nom. Chron.* 1879, p. 1; 1880, p. 181; 1881, p. 8. Cunningham, in *R. A. S. B. Journal*, 1881, p. 151. Especially has a find from the Oxus river enriched the cabinets of collectors.

† Justin, xii. 4, xli. 4. Cf. *Nom. Chron.* 1879, p. 1; 1881, p. 8.

‡ *Nom. Chron.* 1866, p. 220.

at the time of Alexander's invasion, and was confirmed by the latter in the possession of it. But Sophytes' coins are copied from the issues, not of Alexander, but of Selenens. It would appear from them that Sophytes renewed with Seleucus, very probably on the occasion of that king's eastern expedition against Sandracottus, the friendship which he had established with Alexander.

After this expedition, for the period of a century, that is to say during the third century before our era, India proper was governed altogether by native rulers; the power of the Seleucidae and Greek kings of Bactria stopping at the Indian Caucasus.

The date of the revolt of Bactria against the authority of the Seleucidae, who had inherited all the eastern parts of the empire of Alexander, cannot be accurately fixed. Justin,\* however, states that it was con-

The Bactrian  
revolt.  
Diodotus.

temporary with another revolt of one of the eastern provinces of the Seleucid empire, that of the Parthians under Arsaces; an event which took place in B.C. 248.† About that time, then, Diodotus, Satrap of Bactria, revolted against Antiochus II. of Syria, and succeeded in establishing his independence. He seems to have prepared his subjects for a change of masters by issuing coin bearing the types of Antiochus II. of Syria, but with his own portrait.‡ After his establishment in the kingdom he continued this issue unchanged, only substituting his own name, besides his portrait, for that of the Seleucid king. According to Justin,§ Diodotus soon died, and was succeeded by his son, also named Diodotus, who made a treaty of alliance with Arsaces, the first Parthian king. But it seems clear that all coins which have come down to us bearing the

\* xli. 4.

† Gardner, *The Parthian Coinage*, p. 3.

‡ *Br. Mus. Catalogue of Seleucid Coins*, p. 15. Cf. *Num. Chron.* 1881, p. 11.

§ xli. 4. Justin calls Diodotus Theodotus. But Trogus Pompeius seems to have had the name right, *Prod. lib.* xli.

name of Diodotus were issued by one king. We must therefore either suppose that Justin is wrong and has duplicated a single monarch, or that the younger Diodotus continued the issue of his father's money unchanged, or, finally, that the elder Diodotus continued during his lifetime to issue money in the name of Antiochus of Syria, and that our coins with the name of Diodotus were issued by his son, who first ventured to introduce his own name and portrait on the coin. Between these alternatives we cannot venture to decide; in favour of the last, it may be observed that the portrait of Diodotus on his coins is that of a man of not more than middle age; the coins of flat fabric, and bearing an elderly portrait, being now considered forgeries.

We learn that Diodotus was superseded in the rule of Bactria by Euthydemus, a native of Magnesia, in Ionia, possibly a Satrap of some neighbouring province, who was in full power at the time when Antiochus the Great made his eastern expedition, in or about B.C. 208. The accurate pages of Polybius\* give us a glimpse into his history which is very valuable. Euthydemus being defeated in battle by Antiochus, and unable to oppose him, appealed to his generosity, saying that he was born in Asia Minor, and was not one of those who had revolted against Antiochus II., but, on the contrary, had gained the kingdom after rooting out the descendants of those who had so revolted. He pointed out the grave danger that must arise if he were obliged to call in the aid of the Scythians, who were already hovering on the Chinese frontier of his dominions. Antiochus seems to have been open to conviction: finally, he agreed to acknowledge Euthydemus' independence; and, taking a fancy to Demetrius his son, promised him one of his own daughters in marriage.

\* *Hist. x. and following, xl. 34.*

After making terms with Euthydemus, Antiochus advanced across the Paropamisus into India, and made a treaty with the Indian king, Sophagasenus, or Subhāgasena, who seems at that time to have been in full possession of the Kabul Valley, the Greek dominion stretching little, if at all, to the south of the Indian Caucasus. Thence Antiochus returned, through Arachosia and Drangiana, to Syria.

With the beginning of the second century B.C. we find great changes taking place in the Greek regions of Central Asia. On the death of Euthydemus, his son Demetrius succeeded; and we find, as contemporary and rival of the latter, the great Eucratides, whose career of chequered victory and defeat may be partly traced in historical records. At the same time the Greeks, perhaps in consequence of the constantly increasing pressure from the north of the nomadic tribes of Central Asia, made their way across the Indian Caucasus, and began to wrest from the native Indian princes the districts of Kabul and the Panjab, which had been left under native dominion by the Selucid kings from Seleucus I. to Antiochus III., and which Diodotus does not seem to have attacked; for coins of Diodotus are not found south of the Indian Caucasus. On the other hand, those of Euthydemus are found as far south as Seistan, and as far east as the Panjab;\* and the city of Sagala, in the neighbourhood of Lahore, bore the surname of Euthydemia. Thus the sudden extension of the Greek pale would seem to have been a feature of the later years of Euthydemus. But it appears, from the statements of ancient writers, that the actual conqueror was not Euthydemus but his son Demetrius, who was probably his colleague in the kingdom as well as his successor. Thus Justin† speaks of

\* Some were found in the Indus at Attok. See Cunningham, in *Nem. Chron.*, 1809, p. 137.

† xli. 6.

Demetrius as king of India, and Strabo\* couples him with Menander as a chief agent of Greek conquest in India. What seems most likely is that Demetrius made considerable conquests during his father's lifetime.

We are, however, scarcely justified in saying, as does v. Gutschmid,† that "Demetrius himself marched down the course of the Indus, conquered Pattala and the kingdom of Saraoates (Surāshtra) and Sigierdia, probably the district of the commercial city Barygaza." The careless language of the passage of Strabo in which these places are mentioned as within the Greek pale seems only to imply that some of the Greek kings extended their conquests so far; and it is reasonable to suppose that the rule of Menander was extended farther to south and east than that of Demetrius; to Menander therefore the conquest of the Indus valley may be with more reason ascribed.

Not only did Euthydemus acquire, through his son's activity, territory in India, but he also probably ruled the widest district ever possessed by the Greeks to the north of the Paropamisus, from Margiana to Chinese Tartary. Even into the Celestial Empire the influence and the trade of the Greeks seems at this time to have penetrated. Of this a proof is furnished by a coin brought by Sir D. Forsyth from Kashgur,‡ bearing a Chinese legend and inscribed with the name and titles of a Greek king, possibly Hermaeus. After Euthydemus' death his dominions were broken up by the rivalry between Demetrius and Eucratides, as well as by the rise and usurpations of fresh kings of uncertain origin, such as the first Antimachus.

\* *Geog.* xl. 11, 1. Most of Strabo's statements as to early Bactrian history are loose and incorrect. For instance, he speaks of the revolt of Araces as subsequent to the rise of Euthydemus.

† In *Encycl. Brit.*, Persia, p. 590.

‡ *Nouvel. Chron.* 1879, p. 274. That this coin is of iron, is now, I am informed, denied.

Of Eucratides also the origin is obscure. We know, however, by a fortunate chance, the names of his father and mother.

Coins of  
Eucratides  
with his father  
and mother.

These are furnished to us by the remarkable coins\* which bear on one side the head of Eucratides, and the inscription *Βασιλεὺς Εὐκρατίδης*; on the other

the portraits of his father and mother, Heliocles and Laodice. The very collocation of the inscriptions which appear on the two sides of these coins, *Βασιλεὺς Εὐκρατίδης* — *Ἡλιοκλέους καὶ Λαοδίκης*, where we seem almost compelled to understand the word *υἱός*, shows that in them Eucratides intends to proclaim his parentage. Heliocles does not seem to have been a king at all, for his portrait wears no diadema, but Laodice's head does seem to be bound with the diadema, in the Greek East the invariable sign of royalty. And indeed her appearance on coins in such a connexion would scarcely be explicable unless she were of royal parentage. But we must remain in ignorance whose daughter she was. Von Sallet has proposed an entirely different interpretation of the coins in question. He thinks that they were issued by Eucratides, not in honour of his parents, but on the occasion of the marriage of his son Heliocles (who afterwards succeeded him) with a Laodice, whom Sallet conjectures to have been daughter of Demetrius by the daughter of Antiochus III., whom that monarch betrothed to Demetrius in the course of his Indian campaign. On this hypothesis some recent writers have tried to build further structures of theory. But it is unfitted to bear such a weight. In its favour is the one fact that the name Laodice was usual in (not peculiar to) the Seleucid dynasty of Syria. On the other side are reasons of more weight. The portraits of Heliocles and Laodice on the coins are of elderly, not young persons; and it is not easy to see how Sallet would interpret in the inscriptions which accompany

\* See page 19, pl. vi. 9, 10.

the portraits the genitive case in the names of Heliocles and Laodice, unless he understands before them the word *υἱός*. If any one carefully compares the head of the elder Heliocles (pl. vi. 9), with that of Eucratides (pl. v. 5), and that of the younger Heliocles (pl. vii. 1, 2), he must allow that it resembles Eucratides far more nearly than his son; which may be best accounted for by supposing that the artist constructed the head of the elder Heliocles after his death, on the analogy of that of his son Eucratides.

The wars between Demetrius and Eucratides are mentioned by Justin;\* but the statements of this writer must be received with great caution, nor can we believe his assertions that the Indian conquests of Eucratides belong to the end of his reign, or that Demetrius ruled until nearly the same time. For the coins seem to contradict them. The coins of Demetrius come in almost all cases from Bactria, those of Eucratides are very commonly found in the Kabul Valley. The coins of Demetrius bear Greek legends only, with rare exception, while the bronze coins of Eucratides are nearly all bilingual, an indication alike of their later date than the money of Demetrius and that they were issued in India. We therefore, must still retain the opinion that Demetrius ruled only during the early part of the reign of Eucratides in Bactria as well as in India, and that Eucratides was for a great part of his reign lord of India as well as of Bactria and Arachosia. Eucratides founded the city of Eucratidia in Bactria; Demetrius, Demetrias in Arachosia, and Euthydemia in India.

Cunningham places the commencement of the career of Eucratides

\* " Multa tamen Eucratides bella magna virtute gessit, quibus adritus cum obsidione Demetrii regis Indorum pateretur, cum eo. militibus lx. milia hominum adsidula eruptionibus vielit. Quinto itaque mense liberatus Indiam in potestatem redegit. Unde eum se recepisse a filio quem socium regni fecerat, in itinere interficere."—Justin, lib. 6.

Reign of Eucratides. about B.C. 190, and this date must be approximately right.\* His reign began brilliantly, and was continued with chequered fortune; but the wide field over which his coins are found,† and their commonness, seems to testify to his great power. We may also remark his assumption of the title *Βασιλεὺς μέγας* as a clear indication of extensive dominions, and the fact that his types and titles are copied by the kings of Parthia,‡ and by Timarchus, king of Babylon,§ as showing how widely his money circulated. But it appears that towards the end of his reign certain provinces|| were wrested from him by the Parthians, probably in the time of their great king Mithradates, who came to the throne about B.C. 170. The reign of Eucratides appears to have lasted until the times of two kings, who certainly imitate his money, Plato, whom the date on his unique and remarkable coin shows to have ruled in B.C. 165, and Timarchus of Babylon B.C. 162. Plato would seem to have been a mere ephemeral rival, or a revolted satrap of Eucratides.

We must assign to the period of the reign of Eucratides, that is, to the first half of the second century B.C., the coins of the kings Euthydemus II., Pantaleon, Agathocles, Antimachus I. This assignment, which was first made by von Sallet, is on grounds of style quite incontestable. It is impossible, in view of the art

\* There does not seem to be any conclusive evidence on the point. v. Sallet quotes the imitation of Eucratides' types by certain early Arsacid kings as a proof that Eucratides' reign began early; but the attribution of the early coins of the Arsacidae is a matter of dispute.

† According to Cunningham, they are found at Balkh, in Bokhara, Seistan, the Kabul Valley, &c., and a few in the Panjab.

‡ For instance, Arsaces VI., Mithradates I. See Gardner, *The Parthian Coinage*, p. 31. Other writers attribute these coins to others of the Arsacidae.

§ *H. M. Cat. Seleucidæ*, pl. xv. 2, p. 50.

|| The re 'Αρχιδέου επί της Ταρσούσης ἀφίστηται Βάσιλινος οὐ Βασιλεὺς οὐ Παρθεναί: Strabo lib. II. pl. Krause. The names seem corrupt, and have been variously amended.

and fabric of the coins of those kings, to give them, as previous writers, and even Cunningham did, to the earliest days of Bactrian independence. And the evidence of style is further confirmed by the consideration that as all these kings reigned on the south side of the Paropamisus, they cannot be assigned to an earlier period than that of the Indian conquests of Demetrius.

This new light is of the utmost importance in the classification of the earlier Greek kings of India: it entirely destroys an order which was full of difficulties, and puts in its place one which is thoroughly intelligible and satisfactory.

The coins of the younger Euthydemus are certainly subsequent to those of Demetrius, whose types they borrow. There can, therefore, be no reasonable doubt that this king was either the younger son of Euthydemus I., or else the son of Demetrius and grandson of Euthydemus I. As the coins of the younger Euthydemus are not by most writers distinguished from those of the elder, it is not possible to ascertain their find-spots, or to determine the locality of his reign; its date would seem to be about a.c. 170. From the rarity of his coins it may be judged that his reign was soon brought to an end.

Pantaleon and Agathocles strike with almost identical types. They both adopt the metal nickel\* for their coins, and they alone use in their legends the square Indian alphabet. They seem, therefore, to have been closely connected, either brothers, or father and son. Coins of both are found in the Kabul Valley and the western Panjab, and those of Agathocles as far south as Kandahar. Pantaleon seems from his portrait to have been the elder of the two, and the rarity of his coins shows his reign to have been ephemeral. Agathocles seems to have ruled more widely and longer, and he has

\* See Dr. Fildt's analysis in *Nouv. Chron.* 1868, p. 305.

left us in some of his coins valuable materials for the determination of points in his history.

Of the greatest importance is a series of coins,\* which indeed we may rather term medals, of the weight of Attic tetradrachms, issued by Agathocles in commemoration of his predecessors in the Greek rule of Bactria. These medals reproduce alike the portraits of these predecessors, and, what is still more unusual, their coin-types, so that only by their style and their inscriptions do they differ from the ordinary coins of those monarchs. The inscriptions run thus:—

ΜΕΔΑΛΙΑΣ	ΑΛΕΞΑΝΔΡΟΥ ΤΟΥ ΦΙΛΙΠΠΟΥ	ΒΑΣΙΛΕΥΟΝΤΟΣ
		ΑΓΑΘΟΚΛΕΟΥΣ ΔΙΚΑΙΟΥ
ΑΝΤΙΟΧΟΥ ΝΙΚΑΤΟΡΟΣ		"
ΔΙΟΔΟΤΟΥ ΣΩΤΗΡΟΣ		"
ΕΥΘΥΔΗΜΟΥ ΘΕΟΥ		"

To these we must add the parallel coin of King Antimachus:

ΔΙΟΔΟΤΟΥ ΣΩΤΗΡΟΣ	ΒΑΣΙΛΕΥΟΝΤΟΣ
	ΘΕΟΥ ΑΝΤΙΜΑΧΟΥ

I have elsewhere† discussed these medals, the true character of which v. Sallet was the first to establish. They prove that Pantaleon and Agathocles, like the younger Euthydemus, belonged to the faction of Euthydemus I. and Demetrius, and were presumably opposed to Eucratides. Agathocles traces his political pedigree through Euthydemus I., Diodotus, and an Antiochus,‡ to

\* Pl. iv. 1, 3, xix. 5, 6.

† *Nouv. Chron.* 1881, p. 184.

‡ It is disputed which of the three first Antiochi of Syria is the Antiochus Nicator of these coins. None of them seems really to have borne the title: the first was Soter, the second Theos, the third Megas. In favour of Antiochus I., it may be urged that he was the only Antiochus who held undisputed sway in Bactria, and might well be regarded by the Eastern Greeks as full successor of Alexander the Great; also his father Seleucus was called Nicator. In favour of Antiochus II., we have the strong argument that the type of the seated Herakles which is repeated on the Bactrian coin is copied from coins of Syria given by

Alexander the Great himself. Antimachus claims Diodotus as his predecessor. These facts seem to suggest, what is by no means improbable in itself, that Euthydemus II., Pantaleon, and Agathocles were all sons of Demetrius. And possibly, though this is more speculative, Antimachus, as to whose connexions we have no information, was the representative by descent or otherwise of the house of Diodotus.

The types of Antimachus' coins add one more to the few known facts of Greek-Indian history. They are, on the silver coins, Poseidon holding trident and palm; and on the bronze, Victory standing on a ship. There is no mistaking the meaning of these types, which clearly allude to a naval victory won by the king. It might seem at first sight that this victory must have been won on the open sea. But Antimachus' rule never extended to the sea: his coins are found both on the north and the south of the Caucasus, but never south of the Panjab. We must therefore suppose that the naval victory was won on the Indus, or one of its great tributaries; and, indeed, it may easily be understood that the Greeks would place so large a river as the Indus under the sway of Poseidon.

Eucratides was succeeded by his son Heliocles. The coins of this king are found mostly in Bactria, but also in the Kabul Valley. He is, as Cunningham remarks, the last king who struck to the north of the Indian Caucasus. We may therefore be almost sure that in his reign the nomadic tribes conquered the whole country as far south as the Bamian Pass. The silver coins of Heliocles fall into two classes. The first class consists of coins of the Attic standard of weight, bearing Greek

general consent to Antiochus II. In favour of Antiochus III., the only argument is a passage of Malala (p. 261), where the term *Nicator* seems to be applied to this king. But this passage is deprived of all weight by the numerous mistakes which it contains. The balance of evidence is greatly in favour of Antiochus I. or II.

legends only. The second class consists of coins of a different weight, which I call the Persian,\* which bear bilingual inscriptions and a different portrait of the king. The theory is obvious that the first class was issued by the king while he ruled in Bactria, and the second class at a later period, when he was king only of a corner of India. And it is greatly in favour of this view that the coins of the Bactrian class were largely copied by the barbarous tribes of central Asia, just as the coins of Philip and Alexander were by the Gauls who invaded Macedon about B.C. 290, while those of the Indian class are closely like coins of subsequent Greek kings of the Kabul Valley and India.

Down to the reign of Heliocles, which must be assigned to about  
 Successors of      B.C. 160—120, we are able to trace with certainty,  
 Heliocles,      or little less than certainty, the order of succession  
 of the Greek kings of India. But we now arrive on the verge of a  
 period of uncertainty, where the data are very scanty. In fact, our  
 task would become almost hopeless, were it not that the annals of  
 Principal infor-      China preserve a general outline of the history of  
 mation from      Bactria and India in the account which they give  
 Chinese sources.      of the wanderings of the nomad nations on the  
 western borders of China, during the second and first centuries B.C.  
 To identify the names of kings and of places as recorded by the  
 Chinese with those which we find on the coins is no easy task, but  
 it is a task which has been attempted, and with some measure of  
 success in the opinion of those best qualified to judge.

The most recent authority who has examined the Chinese evidence  
 Chinese account      as to the migrations of the Yueh-chi, M. E. Spœcht,†  
 of the Yue-chi.      thus sums it up:—The Yueh-chi were conquered in  
 201 and 165 B.C. by the Huns, and fled westward, subjugating the  
 Tachia of Bactria, and fixing their seat to the north of the Oxus,

\* See below, p. lviii.

† *Journal Asiatique*, 5th Ser., vol. ii, p. 342.

where a Chinese ambassador found them in 126 B.C. After that visit they captured Lan-chi, the capital of the Ta-hia. A hundred years later, Kbiu-tsiu-kio [Kadphises I.], ruler of the Kushans, one of the Yueh-chi tribes, conquered all the other tribes, invaded the kingdom of the Arsacidæ,\* seized Kabul and Ki-pin [Cophene], and formed a great kingdom. His son conquered India, and the empire thus founded lasted from the middle of the first to the end of the fourth century.

Who the Ta-hia may be is not clear: they have been identified with the Scythian tribe of the Dahæ, but the Chinese description of them—"each town was governed by its magistrate, the population was weak and feared war,"—would not apply to any Scythic race, but would very well apply to the native Bactrians under Greek dominion; and the date at which the Greeks were driven across the Paropamisus, in the reign of Heliocles, would fall not far from B.C. 126.

In the Kabul Valley the Hellenic race held out for a century later, until Kadphises I. led the united tribes of Yueh-chi against them, and, after vanquishing them, ruled the country, at first in conjunction with the last king, Hermaeus, and finally in his place.

The Chinese authorities thus give us two dates of the utmost value for the reconstruction of the history of India and Bactria: the nomad tribes conquered Bactria (Heliocles) about B.C. 126, and India (Hermaeus) about B.C. 25. These dates both suit the numismatic evidence very well. Gen. Cunningham gives Hermaeus to a far earlier period than B.C. 25, assigning him indeed to so early a time as 138—120. But not only does this conflict with historical records, but it is also in collision with numismatic testimony. For Hermaeus was, as all writers agree, the last of the

\* About B.C. 31, Phraates, with the help of a Scythian army, expelled Tiberius from the government of Parthia.

Greek kings of Kabul. We are therefore obliged to place between Heliocles and him the reigns of all the twenty Greek kings whose coins have come down to us. To cramp all these reigns into the space of thirty years, B.C. 160—130, is an unreasonable proceeding. Moreover the forms of letters on some of the coins, those of Zoilus, Nicias, and Hermaeus, entirely preclude us from assigning them to so early a period as B.C. 130; they must be quite a century later.

The Chinese writers also authorize the supposition that the Scythian race which wrought the ruin of the Greeks was that of the Yueh-chi, who have been identified with the Tochari of Strabo. And the coins, in this confirming Chinese testimony, show that the tribe of Yueh-chi to which Kadphises belonged was the tribe of Kushan, already mentioned on the last page.

This knowledge is valuable; but it leaves us in ignorance on many points. We are still unaware to what tribes belonged the barbarous rulers of India in this age who did not come in with Kadphises. Manes, Azes, and their successors, who established a kingdom in India, as we shall hereafter see, before the days of Hermaeus, do not appear to have been Yueh-chi; and we are quite in doubt as to the connexions of Gondophares and other rulers.

Before proceeding to speak more in detail of the various groups of kings, we will set forth in the form of a chart the general outlines of our historical and geographical knowledge in regard to them:—

# CHART TO SHOW EXTENT OF DOMINIONS AND DATES OF GREEK AND SCYTHIC KINGS.



Leaving out of account the predecessors of Heliocles, we know already of upwards of twenty kings and of two queens who ruled in the Kabul Valley and the Panjab after about a.c. 160, and before the Indo-Scythic conquest of those regions. The orderly

Greek  
Successors of  
Heliocles;—  
arrangement.

arrangement of these rulers is a matter of the utmost difficulty and even of impossibility. The classification of General Cunningham is based on indications so slight that it cannot resist serious criticism: and indeed its validity depends in a great degree on his arrangement of the early kings, which must now be given up in consequence of the readjustment of Pantaleon and Agathocles. Von Sallet so entirely despairs of any reasonable arrangement that he adopts one which is merely alphabetical. All that has been attempted in the present catalogue is to group the kings roughly in something like chronological order, keeping similar types of coin as far as possible together. By means of the Index any king can easily be found, and that is the chief necessity.

It will however be well to set forth briefly what certain data we possess for the chronological and geographical assignment of the kings. We will begin with the chronological.

Chronological  
data.

possess for the chronological and geographical assignment of the kings. We will begin with the

The only one of these later kings who strikes money on the Attic standard is Antialeidas, who must therefore be either a contemporary or an immediate successor of Heliocles. And as Antialeidas and Lysias strike some coins in common they also must be contemporaries. A common type of Antialeidas is the pilei of the Dioscuri, which seems to connect him with Eueratides; his portrait also resembles that of Heliocles: he would seem therefore not improbably to belong to the Eueratidian dynasty. The connexion of Lysias is obscure. There are also a few restriking which help us in the assign-

Date of  
Antialeidas  
and Lysias.

Evidence of  
restrickings.

ment of dates to some of the Greek kings of India.  
Heliocles restricks some of the coins of Strato I,\*

and the name and types of Eucratides are stamped on a piece of Antialcidas,† as well as on some coins which I have assigned to Apollodotus I;‡ but it has been doubted whether these coins of Eucratides were really issued during his lifetime.

Types and  
legends of coins  
offer few  
indications.

Any attempt finally to arrange the kings in dynastic lists by means of the types and legends which they use is destined to failure. The kings did not inherit these things, but adopted them according to fancy or convenience. One or two instances will be sufficient to establish this. That Heliocles was son and successor of Eucratides is perhaps the most certain fact in Bactrian history. Yet he does not resemble Eucratides in his title (*δίκαιος* for *μέγας*), he does not wear the same helmet, nor use the same types. In the two last respects Demetrius differs from his father Euthydemus. On the other hand, Diodotus, who revolted against Antiochus II., retained the types of the Syrian king. These instances are sufficient to prove that identity of types between two kings is no proof of their relation to one another, nor is divergence of types any proof that they were not related. Still less can we draw any conclusions from the form of a helmet or the adoption of a title.

Perhaps the most suggestive approximation of types is that which appears when we compare the rare coins of Agathocleia, wife of Strato, with those of Euthydemus. They bear on the reverse the same type, Herakles seated, which is not usual in the Bactrian series. It is almost certain that Agathocleia must have been a king's daughter and heiress; otherwise, as we know from the coins

\* Strato also restricks coins of Heliocles.

† Sallet, p. 298.

‡ Cunningham, in *Nam. Chron.* 1869, p. 226.

of Greek kings, her name would scarcely have appeared on the coin. That she was descended from Euthydemus is therefore very likely. We have already seen that king Agathocles was probably son of Euthydemus; Agathocleia may well have been his grand-daughter, or otherwise related to him. But in this kind of argument there are obviously the greatest risks; and we will attempt it in no second instance.

A large find of coins of the kings from Heliocles to Hermacus was discovered some years ago at Sonipat;\* and no less than 703 specimens have been weighed by Gen. Cunningham, who has acutely suggested that the order of the reigns may be gathered by a consideration of the amount of weight lost in circulation by the coins of different kings, those kings whose coins are most worn being naturally supposed to be the earliest. The loss is as follows:—

Heliocles, 5·43 gr.	Philoxenus, 3·77 gr.
Apollodotus, 4·57 gr.	Menander, 3·72 gr.
Strato, 4·56 gr.	Diomedes, 3·39 gr.
Antimachus II., 4·48 gr.	Amyntas, 3·30 gr.
Antialcidas, 4·10 gr.	Hermacus, 3·20 gr.
Lysias, 3·73 gr.	

In this calculation it is assumed that the normal standard for hemidrachms is 37 grains, and that all kings minted up to that standard. This is, of course, not certain; nevertheless, the results of the test so nearly agree with the testimony of style, that we can scarcely be wrong in regarding the above order as approximately correct; only Antialcidas and Lysias should not be placed so late.

Among all these kings, two only, Apollodotus and Menander, are known to us from other sources. Menander is identified with the Milinda of the Buddhist work

\* *Num. Chron.* 1872, p. 161.

"Milinda-prasna," which records not only that he was born at the sub-Caucasian Alexandria, but that he was a just and powerful ruler, and a convert to the Buddhist religion. Strabo\* says that he was reported to have crossed the river Hypanis eastward and penetrated as far as the Isamus, but as we are ignorant where the Isamus was, this does not greatly add to our knowledge. Plutarch† records that as a ruler he was noted for justice; and that when he died many cities were anxious to possess his ashes—a curious tale, which is considered by Prinsep to indicate a Buddhist source. The extraordinary abundance and wide distribution of his silver coins is well known. They were current, with those of Apollodotus, at Barygaza, many years after his death,‡ and are still abundantly found over a wide region, including Kabul, Jalalabad, Peshawar, Mathura, and Rampur. They are not brought from Kandahar or Seistan. "From this evidence," says Cunningham,§ "it is certain that Menander could not have possessed any part of Arachosia or Drangiana, and that his dominions to the west of the Indus must have been confined to the Kabul Valley and Eastern Afghanistan."

The coins which bear the name of Apollodotus fall into two classes: these are distinguished in the Catalogue.

Apollodotus.

The second class are of later and poorer style; and on them the king usually bears the title of Philopator. General Cunningham says|| that the Philopator coins are found only in the Panjab and N.-W. India, while the others are found over a much wider area, including the "Upper Kabul Valley in the north, Kandahar and Roh in the west and east, and Sindh in the south." The evidence, on the whole, indicates that there were two kings of the name of Apollodotus, of whom the later, Philopator, was

\* xi. 11. 1.

+ *De Repub. Ger.*, p. 821.

‡ *Periplus maris Erythraei*, c. 47, ed. Müller.

§ *Nam. Caron.* 1870, p. 221.

|| *Ibid.*, 1870, p. 77.

colleague of his father, the earlier, and his successor in some part of his dominions. And this probability will be raised almost to a certainty if we suppose that the restriking of Apollodotus' coins with the name of Eucratides took place in the life-time of the latter; since the coins which bear the legend Philopator cannot be brought within a considerable distance of the reign of Eucratides.

We have thus but slight indications, beside those of art and fabric, to help us in determining the dates of the kings from Heliocles to Hermæus. Nor have we Geographical data; find-spots, and monograms. safer data for their geographical assignment. The find-spots of their coins have never been recorded with completeness or accuracy. And the monograms which have been supposed to contain the names of mints have not been satisfactorily read, in spite of the diligent efforts of General Cunningham, whose want of success\* in the matter seems to prove that success is not possible, at least in the present state of knowledge on the subject. And the details of the types adopted by various kings help us no more in determining the locality of their rule than in assigning their line of descent.

We can, however, make a few rough divisions of territory. Heliocles and his predecessors minted, as we have seen, in Bactria, his successors only on the south of the Indian Caucasus. And further, it would seem that the Panjab and the Kabul Valley were frequently in different hands. Thus the coins of Archelæus and Amyntas seem to be found in Kabul, and not to the east of the Indus; and those of Hermæus are far commoner in the same district than in the Panjab. On the other hand, the coins of kings Philoxenus, Strato, and

\* Gen. Cunningham's readings have not been accepted by the best numismatists. Von Sallet remarks, "Such interpretations and experiments have too weak a basis to serve for historical investigations." See also the remarks of M. Chabouillet in the *Revue Numism.*, 1867, p. 403.

Hippostratus are chiefly found to the east of Jalalabad. A more exact statement could only be made after many years' study on the spot.

The recorded find-spots of coins are however sufficient to give us an idea of the extent of the Greek kingdom in India. Cunningham states that coins of Apollodotus are found as far south as Kandahar and Sindh, and those of Menander as far east as Mathura on the Jamna. And there appear to be proofs in Sanskrit literature\* that a Greek ruler (perhaps Menander) besieged Ayodhya and Patali-putra (Oudh and Patna). But these expansions were temporary, and there is no doubt that the only districts which were really Hellenized were the Kabul Valley and the western Panjab.

Coins of Antialcidas, Apollodotus, Menander, Lysias, Antimachus II., Diomedes, Archebius, and Hermaeus, were found by Masson† in the course of a few years at Beghram; and since his time coins of Epander, Dionysius, Zoilus, Amyntas, and other kings have been found in the same region, if not on the same site. The kings mentioned, and probably others of Greek race, must all have reigned in the Kabul Valley.

With the Greek kings we have placed one of Indian name, **Ranjabala**, whose coins resemble those of Strato, and show him to have been nearly contemporary with that king. He may have been a satrap of Strato, who asserted his independence. His coins have been found in the eastern Panjab and at Mathura‡ in company with some of Strato.

\* Cunningham, in *Num. Chron.* 1870, p. 224.

† See his important list of coins found at Beghram, in the *Journ. As. Soc. Bengal*, 1836, p. 537.

‡ Cunningham, *J. A. S. B.* 1854, p. 691. In this paper it is suggested that Ranjabala may be identical with Rajapala, a king of the lunar race of Delhi, and that Zeionises may be Jivana Raja of the same dynasty. The reasons against these identifications are, however, very strong.

The barbarous kings who make their appearance in India after the destruction of the Greek kingdoms present even greater difficulties of arrangement than do the Greek kings themselves. Between the eastern expedition of Antiochus III., in B.C. 208, and the era of Kanerkes, which may be taken as fixed\* to A.D. 78, there is no absolutely fixed point, and we are reduced to arguments of mere probability.

Of all the coins of the barbarous rulers, those of Maues are the earliest in style. Von Sallet remarks that the copper coins of this king are like those of Demetrius and Apollodotus, and belong to a period not much later than that of those kings. In the forms of Greek letters, and the style of art, his coins are superior not only to those of Hermaeus, but also to those of kings such as Zoilus and Nicias. It is impossible to place King Maues at a later date than the middle of the first century B.C. And it is an interesting fact, vouched for by Cunningham, that his coins are found in the Panjab only, especially the N.W. part of it, and not in Afghanistan. We must suppose that he ruled over some Scythic invaders, who had entered India not through the Kabul Valley, but through Kashmir or Nepal, while the country to the west of Peshawar was ruled by contemporary Greek kings. At present the Passes between Kashmir and Yarkand are but little used, but it is stated that the Karakoram Pass is open all the year round; and the trade between India and Yarkand by that route has of late years greatly increased. And we know that in old times Kashgar was far more thickly peopled than at present. It is also a matter of history that Nepal has more than once been invaded by Chinese armies. It would appear likely that at the time of the conquest of Bactria by the

\* See below, p. li.

Yueh-chi, as to which something has been said already, about B.C. 130, some tribe of that race or some other Scythic horde passed southward through Kashmir or Nepal; and after imbibing something of Greek civilization, and learning the Greek language, succeeded during the decline of the Greek power after Menander in establishing a kingdom to the east of the Indus, of which Maues was the first ruler.

Azes was, according to general consent, the successor of Maues.

Von Sallet suggests that he was his son, and reads  
 Azes, Azilises.

on coins of Azes, with hesitation, the legend **YMAVO**, which may stand for *υἱὸς Μαύου*. Azes was certainly of later date than Maues, as the forms of his inscriptions and the art of his coins testify. His money also is not found to the west of Jalalabad; it is therefore likely that he did not greatly extend the dominions of Maues, though the extraordinary number of his coins testifies to his wealth and power. Azes strikes in conjunction with Aspavarma, Azilises, Vonones, and Spalirises, and Vonones in conjunction with Spalahores and Spalagadames. This shows that Azes, Azilises, Vonones, and the Spalirises group, of whom we shall speak presently, all belong to one time and to a single group of kings. But Vonones and Spalirises seem, from the find-spots of their coins, certainly to have reigned in Kabul: they may have ruled there and been tributary to Azes; but how they coexisted with the latest Greek kings and the invaders from Bactria, the kings of the Kadphises line, we are unable to determine.

Of the relations between themselves of the kings composing this  
 Vonones,  
 Spalirises,  
 &c.  
 group the legends of their coins enable us to judge  
 in some measure:—

1. *Βασιλέως βασιλέων μεγάλου Ἀζου* = name and titles of the Strategos Aspavarma.

2. Βασιλέως βασιλέων μεγάλου Ἀζου = Βασιλέως βασιλέων μεγάλου Ἀζιλίσου.\*
3. Βασιλέως βασιλέων μεγάλου Ὀνώνου = Βασιλέως ἀδελφου δικαίου Σπαλαόρου.
4. Βασιλέως βασιλέων μεγάλου Ὀνώνου = Σπαλαόρου υἱοῦ δικαίου Σπαλαγαδάμου.
5. Βασιλέως βασιλέων μεγάλου Σπαλιρίσου = Βασιλέως μεγάλου Σπαλιρίσου.
6. Βασιλέως μεγάλου Σπαλιρίσου = Βασιλέως μεγάλου Ἀζου.†
7. Βασιλέως ἀδελφου Σπαλιρίσου = Βασιλέως ἀδελφου δικαίου Σπαλιρίσου.
8. Σπαλῦριος δικαίου ἀδελφου τοῦ βασιλέως = Σπαλαόρου υἱοῦ δικαίου Σπαλαγαδάμου.
9. Vonones and Azes (undescribed coin, said to be in Gen. Cunningham's possession).

The evidence afforded by these legends is valuable, but not so decisive as it might at first sight appear, and capable of being variously construed. Some points, however, are clear. Four kings of the set assume the title King of Kings (Azes, Azilises, Vonones and Spalirises), but they do not do so in succession; Azes seems content to share the title in a friendly way with Azilises and Spalirises, at any rate.† Spalirises was brother of a king, but of which king does not appear. Spalahores is also brother of a king, and he and his son Spalagadames strike in conjunction with Vonones. Spalyris is another brother, and at one time Spalagadames strikes in conjunction with him. As close alliances of this kind scarcely occurred in antiquity, except between members of one family, we may regard it

\* These reverse titles are really written in Indian. I give, for convenience, the Greek equivalents.

† This is sufficient proof that the assumption of the title *Βασιλεὺς βασιλέων*, 'Maharāja adhirāja', does not imply a claim to general supremacy.

as probable, if not certain, that all the kings of the group were related one to the other. In that case it is likely that Azilises, Vonones, Spalirises, Spalahores, and Spalyris were all sons of Azes, and Spalagadames his grandson. Aspavarma was a mere general or satrap of Azes—perhaps, as his name seems to show, of Hindu descent. The kingdom of Maues lasted in the hands of these rulers from before the middle of the first century B.C. at least until A.D. 20 or 30, spreading with time over a larger and larger area. It must have been put down by the growing power of the kings of the Kushan tribe, perhaps by Kadphises II.

We have coins of several other kings in India of the same period, Kings with Parthian names. who do not appear to have been connected with either the dynasty of Kadphises or that of Azes. The only tie which connects them together is the Parthian character of their names, and in most cases of their coin-types. Some both in name and portrait, Pacores and Arsaces, for instance, are thoroughly Parthian. It is to be observed that under Mithradates and his warlike successors the Parthians had extended their empire into Bactria, and driven back the invading Scythians. Some scions of the royal Arsacid stock, or mere Parthian noblemen, may have gained a footing in India and maintained themselves in opposition to the Scythic kings.

The most important king of the Parthian class is Gondophares, Gondophares and Abdagases. with whom goes Abdagases, who on his coins calls himself the nephew of Gondophares. The names of these rulers fortunately occur in the legends dating from the third century A.D., which record the visit of S. Thomas to India,\* con-

\* Cunningham, in *Journ. As. Soc. Bengal*, vol. xxiii. Cf. also Gutschmid, *Rhein. Mus.* 1864, p. 161, and von Sallet in *Zeitschr. f. Num.*, 1880, p. 226. Gutschmid shows that Gaspari, one of the three kings of the Christian legend, is identical with Gondophares.

taining indeed much that is untrustworthy, but also a basis of fact. S. Thomas is represented as converting Gundaphorus, his brother Gad, possibly the Orthagnes mentioned below, and his sister's son Labdanus, which last name seems to be a corruption of Abdagases. Where these rulers lived is not very clear. The legend, however, may furnish some ground for assigning them to the period of S. Thomas, that is, the first century A.D. More trustworthy than an early Christian legend should be the inscription at Takht-i-Bahi, if it could be read with certainty. Professor Dowson renders thus: \* "In the 26th year of the great king Gondophares, on the third day of the month Vaiṣākha, (year) one hundred of the Samvatsara." Unfortunately, doubt hangs alike over the reading of name and date, nor can the era be identified, for Samvatsara means merely era. All that we can be sure of is that Gondophares did *not* reign in the hundredth year of the Śaka era, by which Kanerkes and his successors (see p. li) date their inscriptions; for the style of his coins forbids us to place them as late as A.D. 178. If the name of the king be rightly read it will prove that Gondophares reigned in the neighbourhood of Peshawar; but even this is not certain.

A silver coin of Gondophares discovered by v. Sallet, and figured in our plate xxxiii. 2, may perhaps give us a clue to his date. It is of the types of Arsacid silver coins, and especially reminds us of a coin of Mithradates II. (B.C. 90 or 80), which has similar types on both sides†—on one the head of the king; on the other the king seated, holding an eagle, crowned by a City, who stands behind him. And this last mentioned type seems not to recur in the Arsacid coinage, so that it would seem likely that Gondophares actually copied it from the coinage of Mithradates. In the inscription of Gondophares' coin we find the epithet *αὐτοκρατὴρ*, which is found on the money of only two

\* *Journ. R. As. Soc.*, 1875, p. 379.

† Gardner, *Parthian Coinage*, pl. ii. 19.

Arsacid kings—Sinatroces, A.C. 76 to 69, and Phraates IV., A.D. 8—11. This particular coin of Gondophares then would seem to have been struck not later than the middle of the first century A.D. The period mentioned would suit the other coins of Gondophares.

That Orthagnes was a brother of Gondophares rests on a reading of his coins proposed by Gen. Cunningham. The supposition has nothing improbable in it; the type of

Orthagnes,  
Arsaces,  
Zeionises.

Victory which appears on his coins being also found on those of Gondophares and Abdagases. If it be well founded, it will clearly prove the Parthian origin of the dynasty of Gondophares, Orthagnes connecting him with other Indian kings of Parthian type such as Pacores,\* *Arsaces θεός* and *Arsaces δάκτος*. All these rulers must have been contemporary with the great time of the Parthian empire. To the same period will be assigned also Zeionises, who on his coins calls himself by the modest title of Satrap.

With regard to the seat of the power of these Indo-Parthian kings we have a little information. The coins of

Domitions  
of these kings.

Gondophares were found in plenty at Beghram by

Masson, and his small rude silver coins in the Panjab; while those of Orthagnes are said by Gen. Cunningham to come from Scistan and Kandahar, and those of Abdagases (with legend Sasasa) from Western Panjab. These facts seem to point to an extensive dominion, and confirm the testimony of the anonymous Egyptian merchant,† who informs us of the existence of a Parthian realm in the neighbourhood of the mouth of the Indus, in the reign of Vespasian.

The silver coins of Sanabares, of which there is a specimen in the

\* Not Pacorus. Almost all the names of the kings of this class end in —es; I have therefore kept that ending in doubtful cases, such as Maues and Spalirises.

† *Periplus maris Erythr.* c. 38. Cf. Mommsen, *Röm. Geschichte*, vol. v., p. 352.

## Sanabares.

British Museum (pl. xxiii. 10), have been given by v. Sallet to about the year A.D. 80, and have been compared as contemporary with money of the Arsacid king Vologeses III.\* of that period. But the portrait of Sanabares, though it resembles that of Vologeses, is still more like that of Mithradates II., the helmet having cheek-pieces like the helmet of the latter monarch, while the style of work is very superior to anything known in Parthia in the days of Vologeses. Mr. Thomas had read on the Museum specimen the date  $\Gamma\text{TT}$ , which he interpreted as implying the 313th year of the Seleucid, and first of the Christian era. But this reading is now disputed,† and cannot be insisted on. But if it is given up we should be still inclined to place Sanabares at about the beginning of the Christian era. Sanabares does not use Indian characters in his legends, but either Greek or Pehlvi, and four of the five coins of his in the British Museum came from Persia. It is therefore likely that this king ruled exclusively or principally to the north of the Indian Caucasus.

On referring to the coins of the Arsacidae, we find that in that series the square  $\square$  and  $\sqsubset$  come in some twenty years B.C. On the other hand, the square  $\sqcup$ ‡ does not take the place of  $\Omega$  until 8 A.D. It is quite in keeping with these facts that Manes uses round letters only; Azes, Azilises, Spalirises and their contemporaries, use the square  $\square$  with  $\Omega$ ; Gondophares and Abdagases use the forms  $\square$  and  $\sqcup$ . We have thus a series of kings covering the period B.C. 50 to A.D. 50. The date of Pacores

\* *Zeitschrift f. Num.*, 1879, p. 356. The text reads 'Vologeses I.'; following the erroneous numbering of Prokesch-Osten.

† On other specimens the letters take the form  $\text{T}\text{T}\text{T}$  &c. They may have no meaning.

‡ In the text this form is used in the legend of King Nivias, who certainly reigned earlier than 8 A.D. But on the actual coins of that king the letter is rounder, and of earlier type.

and Arsaces is not easy to fix, but must fall during this period. It is, however, noteworthy, as von Sallet points out, that the coin of Arsaces θεός bears precisely the same types as one of Maues.

The nameless king, who calls himself merely Soter Megas, naturally gives us no clue in his inscription to decide his affinities. Some of his coins are in type and style closely like those of Abdagases; and as he also makes use of the form Ω, he must be of about the same period as that king, A.D. 30-50. His coins are found in great numbers in the Kabul Valley. He may possibly have been a member of the Kadphises dynasty.

After the kings of Parthian character we must mention some others whose types are not dissimilar, yet who appear to be of Scythian race. Among these the most important is **Heraüs and the Sakas.** Heraüs, whose remarkable coin (pl. xxiv. 7) throws some light over the history of this troubled time. Of late the reading of the legend *Τυρραιοῦρος Ἡραίου Σάκα κοράρου* has been disputed, but without solid reason, except as regards the last word. This may with equal exactness and probability be read *κορράρου*; but even if we do thus read it, the presence of the *τυρραιοῦρος*, which is quite undisputed, proves that unusual Greek words may be expected at this time, and suggests that *κορράρου* may be a corruption of *κοράρου*. The reading **ΗΡΑΟΥ** is allowed by Mr. Thomas; but he now disputes the important word *Saka*, reading instead of it the unintelligible words **ΣΑΝ ΑΒ**.\* But we must point out that on the Brit. Mus. coin the third letter of the word is not formed like the N's, of which there are four in the inscription, but like a retrograde **И**, which is on late Parthian and Bactrian coins an ordinary shape of **K**: see pls. xxv, vi. *passim*. Thus there seems to

\* A similar coin in the possession of M. Tiesenhausen seems to read **ΣΛΙΑΒ ΚΟΡΓΑΙΟΥ**. See Thomas, *R. A. S. Journal*, 1883, p. 75.

be at present no sufficient reason for doubting that Heraüs calls himself a Saka king; and we thus gain a confirmation of the statement of ancient historians, that that race was prominent in the conquest of India from the Greeks. But Heraüs probably ruled, like other kings of the class, to the north of the Caucasus.

Similar in type of head to Heraüs is Hyrcodes, one of whose ordinary types, that of the half-horse, is taken from silver coins of the early Antiochi of Syria, which circulated in Bactria. Wilson states that most of his coins come from the Bactrian side of the Caucasus; Mr. Thomas,\* that they belong to Kerman. At page 119 of the Catalogue will be found a few coins of the same class which seem to bear the names of other kings; but these legends may be more blundered attempts to produce some more intelligible name.

Finally, we have to speak of a well-defined group of kings which takes its rise with that Kozulo Kadphises who and successors. appears on coins as colleague and successor of Hermaeus. His date must be the last quarter of the first century a.c.

We do not know to what branch of the widely extended race of Sakas, or nomads, Maues and his successors belonged. But we have reason to think that the group at present discussed were kings of the Yueh-chi, who are identified by Cunningham with the Tochnri, and that they belonged to the Kushan branch of that tribe.

We have already seen how Kadphises led the Yueh-chi, about a.c. 25, southward across the Paropamisus and conquered Hermaeus, whom he reduced to a state of vassalage. Under his successors the dominions of the Yueh-chi went on increasing. Probably he was succeeded by the king who bears the very similar name of Kozula

\* On a coin probably similar to our pl. xxiv. 13. Mr. Thomas reads Gañth in Pehlvi characters (*Sassaniana Inscriptions*, p. 10). Our coin is not sufficiently complete for me to be sure of the reading.

Kadaphes, who on his money calls himself the ruler of the Kushana. The portrait of this ruler on the coins bears so strong a resemblance

**Kadaphes.** to that of Augustus that it seems all but certain that  
**Kadphises II.** he must have reigned at the very beginning of the Christian era. That he succeeded the first Kadphises is very probable, and it is equally probable that he was succeeded by the second, who on his coins calls himself Oeomo Kadphises, and whose reign brings us down to the accession of Kanerkes in A.D. 78. We thus have a succession of princes of the same or nearly the same name extending over 100 years, and it is hard to believe that they do not represent a dynasty which reigned in the Kabul Valley.

We have on a copper-plate from Manikyala (Taxila) a record, wherein

**Inscription** a satrap called Lako Kusuluko dates from the 78th  
**from Taxila.** year of the great king Moga. It seems not unlikely

that the satrap in question may be Kozola Kadaphes, and perhaps still more probable that the great king Moga is Maues. Kadaphes, who probably reigned at the very beginning of the Christian era, may well be placed seventy-eight years later than the accession of Maues, which must be placed not so late as the middle of the first century A.C. But of course it is all but impossible that Maues can have himself reigned seventy-eight years. The reference must be not to the year of his reign, but to an era established by him.

The evidence derived from the style and epigraphy of coins seems

**Spread of** to show that Kadphises I. and Kadaphes ruled but  
**Yueh-ehi in**  
**India.** a part of N.-W. India. When Kadphises came in

as an invader from the north, he found Hermaeus ruling in the Kabul Valley, and reduced him to a state of dependence. At the same time Azes was probably ruler of the Panjab; and perhaps some of the later Greek rulers, such as Hippostratus, still held rule on the lower Indus. When Hermaeus died no Greek succeeded him, but Kadphises occupied his place. Kadaphes, or the nameless

king, must have succeeded Kadphises: their contemporaries must have been Azilises, Spalirises and Gendophares. That the coins of

They become  
dominant under  
Kadphises II.

Gendophares and of the nameless king are alike found in abundance at Beghram, while those of

Kadaphes are not abundant, seems to show that the Yueh-chi did not rapidly extend their dominion in India, but met at first with formidable rivals in the descendants of Azes. Only on the accession of the second Kadphises did the power of the invaders become altogether predominant. It appears that under him and his successors it was supreme in all N.-W. India; and Greeks, Parthians, and the race of Azes alike disappear from history as reflected in the coins.

Kadphises II, Ooemo Kadphises, was a wealthy monarch, and the founder of a powerful line of Scythic kings, as to whom inscriptions give us some information. His date is about the middle of the first century A.D.

Successors of  
Kadphises II.,  
Kanerkes  
and Hoerkes.

His successors are the kings called on their coins

Kanerkes and Hoerkes, and in the records Kanishka and Huvishka. Their rule comprised the whole of N.-W. India and the Kabul Valley.

The date of these kings was a matter of uncertainty until the

Their date. brilliant conjecture of Mr. Fergusson\* as to the origin and use of the Śaka era settled the matter.

Mr. Fergusson's theory is accepted by most Sanskrit scholars, and the numismatic evidence in its favour is so overwhelming, that the numismatist cannot hesitate to join them; in fact, v. Sallet had before the publication of Mr. Fergusson's paper assigned Kanerkes to the same period into which he falls on the theory proposed in that paper, and that on numismatic evidence only. The new theory is that the Śaka era starts from the date not of the destruction of the Sakas,

\* *On the Śaka, Samvat and Gupta Eras*, J. R. A. S. 1880, p. 259. Cf. Max Müller, *India—What can it teach us?* p. 291.

but of the establishment of their empire in India under Kanerkes.\* It is fixed to A.D. 78. The dates at Mathura and elsewhere are said to be as follows (Thomas: *Ancient Indian Weights*, p. 46, and *Jainism*, p. 10):—

KING.	SIKA YEAR.	YEAR A.D.
Kanerkes,	9, 11, 18, 28	87—106.
Hooerkes,	33, 39, 47, 48, 51	111—129.
Vasu Deva,	44, 83, 87, 98	122—176.

The evidence of finds confirms this assignment of dates. In a tope at Ahin Posh near Jalalabad, Mr. Simpson found together the following gold coins:—

10 coins of Kanerkes, 6 of Kadphises, 1 of Hooerkes.

1 of Domitian, 1 of Trajan, 1 of Sabina.

The reigns of the Roman imperial persons cover the period A.D. 81-136; and this proves that the deposit cannot have been buried until about A.D. 130,† probably in the reign of Hooerkes.

It is true that in the Manikyala tope there were found with coins of Kanerkes some worn consular denarii which belong to the period before Augustus,‡ but it is more than probable that these coins were not buried till a long time after their issue.

It seems to be universally allowed that the Kanerkes and Hooerkes of the coins are the Kanishka and Havishka of inscriptions, and that these were successive kings of the Kabul Valley and the Panjab.

But the Vasu Deva of the inscriptions, who is supposed to correspond to the Bazodeo of the coins, is a more mysterious personage. He overlaps in the dates Havishka,

Vasu Deva.

\* Or, perhaps, Kadphises II.; as it is Kadphises who begins the issue of Indo-Scythic gold coins: and Kanerkes' earliest date is the year 9.

† Sabina came to the throne in 128. The coin of her issue, now preserved in the British Museum, is not as stated by previous writers "much worn," but seems to have greatly suffered, whether in ancient or modern times, by being exposed to heat. The coin of Trajan is worn. Cf. *J. R. A. Soc.* 1880, p. 266.

‡ *Journ. As. Soc. Bengal*, iii, p. 34.

and appears to have reigned for no less a period than fifty-four years. Indeed, if one inscription be rightly read, he sometimes dates from year 5 of the era, \* which will give to his reign the impossible length of 94 years. Prof. Dowson therefore suggests that Vasu Deva may have been the name given by their Indian subjects to kings of the Kauerkes dynasty. In favour of this view it may be remarked that the words Vasu Deva occur in Sanskrit letters on coins of various periods and classes; and the supposed Greek equivalent **BAZOΔHO** occurs only on Indo-Scythic coins of semi-barbarous fabric.

The coins of Vasu Deva are succeeded by a large variety of copies, some of fairly good style, others of barbarous work, neither class bearing intelligible legends. Some of these, in copper, were usually given to an imaginary king Ooer Kenorano, such being their legend. Von Sallet has, however, conjectured that as there are no gold coins with the legend Ooer Kenorano, and no copper bearing the legend Ooerke Korano, the copper coins above mentioned must have been struck by king Hooerkes. This conjecture is strongly confirmed by the discovery in the Museum series of coins † in all respects similar to those reading Ooer Kenorano but reading clearly Ooerke Korano. But in fact the difference between the two legends is almost evanescent, **N** in the one taking the place of **K** in the other; however, in the inscriptions of this class these two letters are constantly confounded.‡

The gold coins which repeat barbarously the legends and types of Vasu Deva become eventually of thin fabric and cup-like shape, like some of the issues of Byzantium of the ninth and subsequent centuries. But they must be earlier than that period, and are perhaps copied from the concave coins of the class struck at Persepolis during Parthian supremacy.

\* Cunningham, *Archæological Reports*, iii. 30. Dowson, *J.R.A.S.* vii. p. 381.

† Pages 156-8.

‡ See above, p. xlvii.

The whole class of Indo-Scythic gold coins appears as a most remarkable phenomenon amid the coins of India, especially as gold coins are entirely wanting in the Greek-Indian issues after the time of Eucratides. The line of descent of the new issue must be traced not through the gold money of Alexander, which perhaps still circulated in southern Asia, but through the Roman aurei which were first issued in abundance by Augustus, and which at the beginning of the Christian era made their way into India, where they have been found in conjunction with coins of Kadphises and Kanerkes. In weight the Indo-Scythic coins nearly correspond to the Roman.

## II. INSCRIPTIONS.

The inscriptions on the coins contained in this volume are of the following kinds:—

(1) Greek language in Greek characters. On the coins of earlier kings, from Diodotus to Demetrius, Greek legends only are employed. After that time we usually find Greek on one side of the coin only. It is, however, quite evident that the Greek letters and the Greek language were generally understood in northern India and in Kabul as late as the second century of our era. This fact, clearly established by the testimony of coins, confirms the otherwise not trustworthy testimony of Philostratus, who represents that Apollonius of Tyana, when he visited India, had no difficulty in making himself generally understood by speaking Greek. In the Hindu revival under the Guptas the Greek language was probably swept away with other traces of Greek culture. Notable is the use by some of the later rulers of poetical Greek words like *κοίραρος*, *τυραννέων* and *ἀνίκτος*.

(2) Indian language in native characters. These last are of two sorts. The square letters of the so-called Indian Pali are used by Pantaleon and Agathocles only; the

more cursive characters, called Arian Pali, are used by all the other kings down to the latest times. In the case of the edicts of Aśoka, the Arian characters are used only in the Kabul Valley, and the Indian characters elsewhere; and this fact shows, what is proved in many other ways, how completely the Greek and Seythian power in India centred in the Kabul Valley.

The language which I have called by the general name of Indian is a debased form of Sanskrit or Pali. To fix authoritatively the readings of words in this language is impossible except to a Pali scholar. I have therefore given, in nearly all cases, the readings of previous writers, unless they seemed to me to conflict with the clear testimony of the coins; in which case (a very rare one) I have ventured on innovation. In the cases where it was necessary to decide between various authorities, I have sometimes had the advantage of the advice of Mr. Cecil Bendall, who has kindly allowed me to profit by his wider knowledge of Sanskrit. Still more have I regarded any philological criticism of the forms presented by the coin-legends as lying outside my task. Such criticism might well form a supplement to M. Senart's valuable papers on the language of the Aśoka edicts in vols. xv. and xvi. of the *Journal Asiatique*, but in a numismatic work it would be altogether out of place. And this is clearly a task which could only be attempted with advantage by a highly-trained Sanskritist.

The system here adopted in transliteration of Pali inscriptions is the same as is used in other Museum Catalogues, and nearly identical with that used by Prof. M. Williams in his *Lexicon and Grammar*.

To the letters in which these inscriptions are written I have paid closer attention, palæography being perhaps more nearly related to archæology than to philology. To determine their forms requires care and a practised eye rather than wide linguistic knowledge. I have drawn up a table of Arian Pali

Forms of  
Indian letters.

letters used on the coins, after careful comparison of the authoritative tables drawn up by Gen. Cunningham (see p. lxx). All the letters in the table have been cut upon types; so that printing in this alphabet will in future be comparatively easy. With the square or Indian Pali characters I have not concerned myself, as they occur on so few coins.

(3) Scythic language in Greek characters. These are the inscrip-

Scythic  
language.

tions on coins of the late kings of the Kanerkes group, such as **PAO, NANO, KOZOYAO, KOPANO,**

and more especially the names of deities on the reverses. These words, so far as at present identified, are of non-Scythic origin, borrowed from the languages of India, Persia, and Greece, and only bearing the Scythian stamp in their termination **O**, and in modifications of the forms of words.

Lists of Greek, Scythic and Indian words will be found in the *Index of Inscriptions*; and renderings of the last-mentioned in the table at p. lxxii.

### III.—MONOGRAMS.

In the field of coins of all periods is a prodigious number of monograms and detached letters, sometimes Greek and sometimes of the Arian Pali class. If these could be read and interpreted, there can be no doubt that they would afford us most valuable information. But they present the greatest difficulties.

Gen. Cunningham has well remarked, in regard to some of the  
 Difficulties  
 of interpretation. Greek monograms, that their constant recurrence during successive reigns proves that they cannot denote monetary magistrates, but must stand for mints. There is reason in this; but when the writer goes further, and tries to identify the various mints which they respectively represent, we, like most students of these coins both in England and abroad, are unable to follow him. While therefore we must acknowledge the

possibility that many of the Greek monograms may stand for the names of mints, we must stop short at that point. Nor does there seem any probability that we shall advance further, until the find-spots of Bactrian and Indian coins are far more exactly recorded than they have hitherto been. The monograms and letters of the Pali alphabet do not recur in the same way as the Greek, but vary far more; and it does not seem probable that they stand for mints. They may stand for the names of magistrates, for the date or number of the issue, or they may have been used for some other purpose which has not yet been guessed. Perhaps, in these circumstances, it may seem superfluous to record them, as has been done in this Catalogue; but it is impossible to be sure that valuable information will not some day be extracted from them.

#### IV. TYPES.

The types which appear on the coins described in the present volume are most interesting from the point of view of art and mythology; but it is to be regretted that they furnish us with but little historical information. We have already noted the fatuity of trying to determine the genealogy or the dominions of the Greek kings by means of the types of their coins; and the same holds true, in scarcely less degree, in regard to the kings of Scythic race. It is a remarkable fact that throughout the period of which we treat there seem to have been in N.-W. India artists capable of designing original types for coins, so that the necessity for a slavish copying of foreign coins, which gives valuable material to the historian, does not seem to have arisen.

In the types used by Greek kings we find great variety, and they  
Types of            open to us quite a new chapter of Greek art,  
Greek kings.        affording fresh proof of the remarkable originality

of the artists of the Hellenistic age. In regard to their style, we may note two points:—(1) The extraordinary realism of their portraiture. The portraits of Demetrius (pl. ii. 9), of Antimachus (v. 1), and of Eucratides (v. 7), are among the most remarkable which have come down to us from antiquity, and the effect of them is heightened in each case by the introduction of a peculiar and strongly-characteristic head-dress, which is rendered with scrupulous exactness of detail. (2) The decidedly Praxitelean character of the full-length figures of deities on the reverses. The figures of Herakles (pl. ii. 9, iii. 3), of Zeus (iv. 4, vii. 2), of Poseidon (v. 1), of Apollo (v. 4, ix. 10), are all in their attitudes characteristic of the school of Praxiteles. The types of Greek deities which we find are sometimes more distinctive than the style in which they are rendered. Thus, on coins of Demetrius, Artemis is sometimes radiate (pl. iii. 1), on coins of Agathocles (iv. 4) Zeus bears in his hand the three-headed Hekate, Herakles crowns himself with a wreath, Pallas appears in short skirts, and many other such strange forms of Greek deities appear.

To search out the reasons of these variations of type, reasons to be found probably in many instances in the influence of local Indian or Persian legend or belief, would be a very attractive task, and not hopeless, considering the data furnished us by the legends of the gold Indo-Scythic coins, as to which we shall presently have to speak.

The earliest of the clearly Indian types to make its appearance is  
 Semi-Hellenic types. a dancing-girl, wearing long hanging earrings and oriental trousers, on the money of Pantaleon (iii. 9) and Agathocles (iv. 9). As we come to a later period, non-Hellenic types, or types in which there is a non-Hellenic element, gradually make their way on the coins. On coins of Philoxenus (xiii. 9) and Telephus (xxxii. 7) we find a radiate figure of a sun-god

standing, holding a long sceptre. On those of Amyntas (xiv. 11) and Hermaeus (xv. 8) we find the head of a deity wearing Phrygian cap, whence issue rays. But when we reach the issues of King Maues (pls. xvi., xvii.), we find a wealth of most remarkable and original barbaro-Hellenic figures; a figure resembling Tyche (xvi. 3), holding in one hand a patera, in the other a wheel, who seems to be the original of the still more outlandish figure of Azes' coins (xviii. 10, 11); a radiate Artemis, with veil flying round her head (xvi. 4); a draped goddess, bearing a crescent on her head, and standing between two stars; and several others. Still more original is the type (xvi. 9), where a seated Zeus grasps in his extended hand, not, as usual, a Victory (vii. 9) or a thunderbolt (vii. 5), but a being who seems an impersonation of the thunderbolt, and stands in the midst of it; as well as the type (xvii. 2) where a nymph, perhaps a Maenad, stands grasping two stems of vine. Maues' successors, Azes and Azilises, use types of the same class. A careful consideration of these facts will convince us that by some means or other Maues and his race secured the services of artists who had been instructed by Greeks, but were not restricted by Greek traditions. In fact, in these coins we have the sole remaining relics of an interesting school of art, one of many which existed in Asia in the first century *a.c.*, and which have passed away almost without leaving any memorial. It would further seem that kings, who were the patrons of art, and understood the Greek language, must have been considerably softened and refined by contact with civilized neighbours.

The first of Indian deities to claim a place on the coins is *Śiva*,

*Hluda types.*

who seems to make his appearance on the coins of Gondophares (pl. xxii. 8, 9), though it must be confessed that this figure may with equal plausibility be called a Poseidon, for the characteristic marks of *Śiva* are absent. But on

coins of Kadphises II. the bull, which appears beside the deity, sufficiently proves him to be Śiva; and on the money of Kanerkes and his successor he appears in more and more native form, four-armed, and bearing the numerous symbols associated with him in local belief. It is probable that the goddess who appears on the coins of Azes as standing on a lotus, and holding a flower (xix. 5), is either Pārvatī, the dread wife of Śiva, or Lakshmi, the goddess of fortune: the supposed lion, which seems on the coin to lie under her left elbow, may be after all only a lump of oxide. These, and the dancer on the coins of Pantaleon and Agathocles, are the only strictly Hindu types to be found on coins before the time of the great Yueh-chi dynasty, when other deities come in, as will be seen by the list given below.

To speak of Parthian types on coins at all may seem a misnomer, since there are no original Parthian types in existence, if we except representations of the king himself: in these matters the Parthians were imitators of the Greeks. But there are, notwithstanding, certain types of deities, and a certain style of art, which we learn to associate with the coins of Parthia; and when we can trace these on coins issued in India, a presumption arises that the king who issued them was of Parthian stock. For example, the portraits of Parthian kings, bearded, and wearing the diadema, have quite a distinct aspect; and we find this aspect in the portraits of Gondophares, Pacores, Orthagnes, and Sanabares. The type which represents a City crowning the king, which occurs on the money of Phraates IV. and subsequent kings of Parthia, is used by Zeionises (pl. xxiii. 4); and Nike, who is continually present on Parthian coins, is quite a feature also on our pl. xxiii., which contains coins of the kings of this group. Indeed, some of their coins, such as xxiii. 10 and 11, are altogether of Parthian type.

In view of their types, the gold coins of the conquering Yueh-chi

Types on gold of  
Yueh-chi.

kings are of surpassing interest. The obverse presents us with a figure of the king clad in helmet and armour, which are closely like those borne by the first Arsaces of Parthia on his coins. The reverses are extremely varied, and present us with a multitude of types borrowed from several different mythologies. Had these coins been anepigraphous, their interpretation would have baffled all ingenuity; but fortunately the names of the various deities represented are written beside them in Greek characters, only somewhat disguised by being crushed into Scythian forms. On these types two important papers have been published, one by Mr. Thomas\* and one by Dr. Hoffmann.† Though the present writer does not pretend to the linguistic knowledge of either of these scholars, he ventures to discuss their results from the numismatic point of view and that of comparative archaeology.

On these gold coins the following types appear:—

(a.) GREEK AND SEMI-GREEK DEITIES.

*Inscriptions.*

*Types.*

ΗΑΙΟC	Radiant sun-god, holds sceptre.
CAAHNH	Male moon-deity, holds sceptre.
NANAIA	Female deity holding sceptre, which ends in the fore-part of a horse.

These types occur in the series of coins issued by king Kanerkes with Greek legends only. The names of the deities are given in Greek, not Scythic. Nevertheless, in the types there are clear signs of barbarism. The figure of Helios is identical with that on bilingual coins inscribed with the name of

\* *Jainism, or the Early Faith of Asoka*; J. R. A. S. 1877.

† *Abhandlungen f. d. Kunde des Morgenlandes*, vol. vii. (1881), no. 3, p. 139 sqq.

*Inscriptions.**Types.*

Micro, and the figure of Nanaia with that on the coins inscribed **NANA**; while the type of 'Salene' is borrowed from the coins inscribed **MAO**, and is male instead of female. Nanaia, though a deity of Persian origin,\* was clearly regarded by the die-cutter as Greek, perhaps as identical with Artemis, but there is much that is oriental in her figure.

**NANA,**  
**NANA PAO** }

Female deity holding sceptre, as above; over her forehead, crescent.

[ΟΔΙΙΟ]

The **PAO** is evidently only a suffix. The crescent of course indicates a lunar deity. **NANO** and **OKPO** are combined on a coin published by Prokesch-Osten. *Arch. Zeit.* 1849, pl. x. 8.

**ΗΡΑΚΙΔΟ**

Herakles; holds club and apple.

**ΗΡΟ**

Artemis clad in long chiton; holds bow and arrow.

The type is unmistakeable, but the legend is puzzling. Mr. Thomas reads it **ZEPO** 'Ceres' (?), but that brings us no nearer to Artemis. I venture to suggest that the word **MEIPO** (see p. lxiii) is intended, for we find in other instances that inappropriate legend sometimes accompanying types which were, as we may conjecture, unintelligible to the die-cutter.

**PAO PHOPO**

War-god, standing; holds spear and shield.

The word **PAO**, evidently meaning king or royal, may be detached from the legend. The remainder, **PHOPO**, cannot be with certainty explained, but it seems most likely that it is a mere twisting of the Greek **APHΣ**, and that the intention is to portray the Greek war-god. The type suits Ares perfectly.

\* A long dissertation on her by Hoffmann, l. c., p. 130.

*Inscriptions.**Types.***PIOM**

Pallas, or Roma; holds spear and shield.

Mr. Thomas reads **PIAH**, 'Rhea' (?). But **PIOM**, or even **POM**, is nearer to the actual legend, and the types of Pallas and Roma can scarcely be distinguished; I am therefore inclined to find here an impersonation of the great city, such impersonation being usual in contemporary Roman coins.

**ΣΑΡΑΠΟ**

Sarapis, holds sceptre; modius on head.

**ΩΡΟΝ**

Deity, wearing modius, holds sceptre.

**[ΩΡΟΗ?]**

I am disposed to identify this figure with the Greek Uranus, though he may almost as well stand for the Indian Varuna.

**(β.) PERSIAN DEITIES.**
**ΑΘΡΟ, }  
 ΑΘΟΡΟ }**

Fire-god, holding hammer and tongs.

Male figure, holding wreath and tongs.

This is the Iranian fire-god, called by Mr. Thomas Atars; but his form is copied from that of the Greek Hephaestus.

**ΑΡΑΕΙΧΡΟ**

Sun-god, with hand raised. (Persian?)

The origin of the name is obscure: it may even be a mere corruption of **ΑΡΔΟΧΡΟ**.

**ΑΡΟΟΑΣΓΟ**

Male deity, holding wreath, horse beside him.

The first letter has usually been corrected to **A**. Hoffmann, however, observes that as it stands the name is near to the Persian word *Labrasp*. It is not certain that we have here a sun-god, the horse, his only marked attribute, being not necessarily solar.

**ΜΑΝΑΟ-  
 ΒΑΓΟ**

Moon-god, four-armed, seated on throne.

*Inscriptions.**Types.*

Mr. Thomas interprets the legend 'Māonh Bago,' a particular form of the Iranian moon-deity. Hoffmann recognizes the deity as Bahman (Manō Vohū).

MAO

Moon-god, holds sceptre, wreath, ankus, &c.

Mao is a Zend name for the moon-god.

MIPO, }  
MEIPO, }  
MIOPO, }  
[ONIO]

Radiate sun-god, holds sceptre, wreath, &c.

[In one case the inscription accompanies a figure of Nanaia.]

The form **MIOPO** does not, so far as I know, occur. The deity intended seems therefore rather to be the Iranian sun-god Mihira, than his Graeco-Roman counterpart Mithras.

NANA

See above, under Greek deities.

ΘΑΝΙΝΔΑ

Victory, holding wreath and sceptre.

The Zend word *Fanaht* stands for the star of victory (Hoffmann). Mr. Thomas considers the legend to refer to Anandates, a Persian deity mentioned by Strabo.\* But he was a male deity, and of his character we know nothing.

ΘΑΔΟ

Wind-god running.

"Zend, 'wind-god,' *vātō*" (Hoffmann). The type is very characteristic, and decidedly original.

ΘΡΑΓΓΝΟ

War-god; holds spear and sword.

The legend has been read **ΘΡΔΑΓΓΝΟ**, and supposed by Mr. Thomas to refer to Agni. Hoffmann considers the deity to be the Persian war-god Varhran, or Bahram.

ΦΑΡΡΟ

Deity holding fire, sceptre, sword, &c., some-

\* *Ἑλληνικὴ καὶ Ἀραβικὴ Γεωγραφία*, page 512 (c).

*Inscriptions.**Types.*

times wears winged helmet, or stands on a fire; sometimes holds the caduceus of Hermes, and even his purse.

The Persian word *far* or *farr* signifies fire, and that the deity is a fire-god is evident. Hoffmann calls him the god of victory, *hearenahh*, "Hoheits und Sieges-glanz."

## (γ.) INDIAN DEITIES.

## ΑΡΔΟΧΡΟ

[ΔΟΧΡΟ]

Female deity, holding a cornucopiae.

The type is nearer to that of the Greek Tyche than to any other figure. The legend has been regarded as a transcription of *Ardha-ugra*, half or consort of *Śiva*, *Pārvatī*. And that **ΟΚΡΟ** stands for *Śiva* is certain, as we shall presently see: but there still remains for explanation the aspirate **Χ** for **Κ**, as well as the curious circumstance that the cruel and relentless *Pārvatī* should appear in so mild and propitious a form. Hoffmann considers the deity intended to be the Persian *Ashis*, daughter of *Ahuro*, goddess of fortune. Others suppose her to be *Lakshmi*, the Indian goddess of fortune, who closely corresponds to *Tyche*.

## ΜΑΑΧΝΟ

War-god *Skanda*, holding standard and sword.

There can be little doubt that the legend represents the Sanskrit *Mahāsena*, 'ruler of a great army,' an epithet of both *Śiva* and *Skanda*. The

*Inscriptions.**Types.*

figure so nearly resembles that of Skanda in the present series, that it is safe to identify it with him. Later, Mahāsena reappears, in somewhat different form.

**OKPO**

Śiva, standing with trident and ball; his hair in form of a shell.

Śiva having four hands, in which he holds a vase, an Indian thunderbolt,\* a trident, and a goat: sometimes a wreath or a Greek thunderbolt: he is sometimes phallic.

There has been a quite unnecessary doubt as to the identification of this figure; Hoffmann calls it Ahuro, and von Sallet "Pantheon aus Zeus, Poseidon, Herakles," &c. No doubt there is a Greek element in the type, but the attributes prove beyond any doubt that Śiva (Ugra) is intended. The thunderbolt, trident, and goat, are all attributes of that deity as he appears in Hindu pictures, and the special arrangement of the hair and the phallic nature also belong to him especially. On some of the late coins Śiva has three faces.

**CKANΔO  
KOMAPO,  
BIZAGO**

Two figures of armed deities; one holds standard and sword, one sword and spear.

These figures also can be unhesitatingly identified as Skanda, the Hindu god of war, who bears the epithet of Kumāra, the prince, and Viśākha, who is called in the Mahābhārata† a son and impersonation of Skanda.

\* On p. 132 this attribute has been called a drum. Its form is that of a drum, but the occurrence of the Greek thunderbolt in the hand of Śiva shows that it is the Indian counterpart of that weapon.

† I. 2688, iii, 14384, &c.

*Inscriptions.*

*Types.*

CKANΔO  
KOMAPO,  
MAACHNO,  
BIZAGO

Two figures, as before; between them a deity, who is apparently horned.

In this remarkable group we find again Skanda Kumāra, and Viśākha: the third figure appears to be Mahāsena, who is here differentiated from Śiva.

ΩPON

See above, under 'Greek Deities.'

(δ) *Buddha.*

BOΔΔO,  
OΔYO BOY }  
CAKAMA. }  
JΓO BOYΔΔO

Figure of Buddha, standing, preaching.

Buddha seated cross-legged (Pl. xxxii. 14).

These coins are most interesting as giving us the earliest known artistic representation of Buddha. The second and longer legend seems to be a transcript of Advaya Buddha Śākyamuni.\* On a British Museum specimen **CAKAMA** is clear; the old reading **CAMANA**, with its interpretation Śramana, must therefore be given up.

The style in which these various figures are represented is remarkable, and points clearly to a local school.

*Style of types.*

There are a few set schemes according to which all the figures are arranged. Nanaia (xxvi. 10) is in exactly the same attitude as Ardochro (xxvi. 6). The sun-god (xxvii. 9) finds his close parallel in the moon-god (xxvii. 22). Pallas, or Roma (xxviii. 10) differs from Ares (xxviii. 17) only in the length of her chiton. This being the case, it is evidently futile to seek the originals of the types of these coins, as one might be tempted to do, on the Roman aurei of the Cæsars. Thus the Roma (xxviii. 20) is closely like Pallas on an aureus of Galba, and the Victory (xxviii. 13) nearly resembles

\* The word *advaya* is due to a suggestion of Mr. Bendall; the full form would be *advaya-vādin*, 'he who speaks of the one (knowledge).'

Victory on an aureus of Otho; yet we have no right in these and similar cases to assume that the Roman coin is the prototype, and the Indian coin the copy. Rather both coin-types are copies of a conventional and widely current mode of representing the deities. Within the limits set by their conventional notions as to attitudes and drapery the artists employed by the Scythic kings move freely; they vary attributes continually, and in the case of Śiva even develop a type quite different from anything to which they can have been accustomed in a Greek school.

### V. WEIGHTS.

It is maintained by Gen. Cunningham that the earliest Greek coins of India, those of Sophytes, are struck not on the Attic standard, but on a native standard which is based on the rati or grain of *abrus precatorius*. Of these grains, 32 weigh, according to Cunningham, 58½ English gr., according to Thomas 56 gr. We thus reach a unit, the *purāṇa*, followed in the early punched silver coins of India; and that the money of Sophytes follows the same standard is likely enough, though if so it is rather over-weight.

Apart from these specimens, all the earlier coins of the kings of Greek descent which were issued in India and to the north of the Caucasus, are struck on the Attic standard (drachm, 67·5 grains) which Alexander made universal in the regions which he conquered, and which was maintained by the Seleucid kings who succeeded him in Asia.

The earliest monarch to strike on another standard is Eucratides; and in the reigns of his successors, Heliocles and Antialcidas, the Attic standard is gradually given up, the new standard advancing in conjunction with the custom of using on the coins Indian transcripts of the Greek legends.

This new standard appears to be identical with that called by metrologists the Persian, the standard on which coins were struck in all parts of the Persian Empire, notably the *sigli* stamped with the figure of the Persian king, which must have freely circulated in the northern parts of India, which paid tribute to the Persians. The standard used by the Indians for the silver coins, which they issued before the Greek conquest, is as we have already remarked different. The present standard therefore would seem not to be native to India, but an importation from Persia.

In the Persian standard the unit or drachm weighs 84-86 grains: if therefore the lower standard of the Greek kings of India be Persian, we must call the heavier pieces, which weigh as a maximum 160 grains, didrachms; and the smaller pieces, which weigh up to 40 grains, hemidrachms. Hitherto the larger pieces have usually been treated as didrachms, and the smaller as hemidrachms, of Attic standard, which is clearly wrong. But Sallet also appears to be wrong in supposing that the larger pieces are tetradrachms, and the smaller drachms of a standard reduced from the Attic. For the change from the Attic standard to that which I call the Persian takes place suddenly, and is evidently due not to any sinking of standard, but to the adoption for purposes of convenience of a different weight for coins.

All gold coins before the Indo-Scythic period follow the Attic standard, somewhat debased. The Indo-Scythic gold money, as we have already observed, p. liii, follows the standard of the aurei of Rome.

The following table gives approximately the normal or standard weights of coins in the various metals issued in India by Greek and Scythic kings.

PERCY GARDNER.

## NORMAL WEIGHTS OF COINS.

## GOLD.

	Grains.	Grammes.
Stater of Attic Standard . . . . .	132	8.55
Drachm of Attic Standard . . . . .	66	4.27
<hr/>		
Indo-Scythic distater . . . . .	248	16.07
"    stater . . . . .	124	8.03
"    quarter-stater . . . . .	31	2.01

## SILVER.

Tetradrachm of Attic Standard . . . . .	264	17.10
Drachm of Attic Standard . . . . .	66	4.27
Hemidrachm of Attic Standard . . . . .	33	2.13
Obol of Attic Standard . . . . .	11	.71
<hr/>		
Didrachm of Persian Standard . . . . .	160	10.36
Hemidrachm of Persian Standard . . . . .	40	2.59
<hr/>		
Drachm of Indian Standard . . . . .	58	3.75

## NICKEL.

Didrachm of Attic Standard . . . . .	132 ?	8.55
Drachm of Attic Standard . . . . .	66	4.27

# THE ARIAN PALI ALPHABET, ON COINS.

Value.	Form.	Value.	Form.	Value.	Form.
a	<sup>1</sup> 𑀓 <sup>2</sup> 𑀔 <sup>3</sup> 𑀕*	gāṃ	𑀕	pho	𑀧
am	<sup>1</sup> 𑀓 [ <sup>2</sup> 𑀔] <sup>3</sup> †	ga	<sup>1</sup> 𑀓 <sup>2</sup> 𑀔	ṣḍa	[𑀧]
āṃ (medial) or m	.	go	𑀕	dha	[𑀧]
i	𑀕	yha	𑀕	ta	<sup>1</sup> 𑀓 <sup>2</sup> 𑀔 <sup>3</sup> 𑀕
im	𑀕	chu	<sup>1</sup> 𑀓 <sup>2</sup> 𑀔	ti	<sup>1</sup> 𑀓 <sup>2</sup> 𑀔
u	𑀕	chha	<sup>1</sup> 𑀓 [ <sup>2</sup> 𑀔] <sup>3</sup>	to	𑀕
e	𑀕	ja	<sup>1</sup> 𑀓 <sup>2</sup> 𑀔 <sup>3</sup> 𑀕	tra	<sup>1</sup> 𑀓 <sup>2</sup> 𑀔
o	[𑀕]	jī	<sup>1</sup> 𑀓 <sup>2</sup> 𑀔	tā	[𑀧]
ka	𑀕	ju	𑀕	ta	𑀕
ki	𑀕	jñā	[𑀕]	tha	[𑀧]
ku	𑀕	jha	𑀕	ṣḍa	<sup>1</sup> 𑀓 <sup>2</sup> 𑀔 <sup>3</sup> 𑀕 <sup>4</sup> 𑀕 <sup>5</sup> 𑀕
kā	𑀕	jham	𑀕	dī	<sup>1</sup> 𑀓 <sup>2</sup> 𑀔 <sup>3</sup> 𑀕
kra	𑀕	jho	𑀕	dū	𑀕
kā	𑀕	ñā	[𑀓 <sup>2</sup> 𑀔]	dē	<sup>1</sup> 𑀓 <sup>2</sup> 𑀔
kre	<sup>1</sup> 𑀓 <sup>2</sup> 𑀔	pa	[𑀔]	do	𑀕
kha	<sup>1</sup> 𑀓 <sup>2</sup> 𑀔	pha	[𑀔]	dra	𑀕
khu	𑀕	phi	𑀕	dha	𑀕
kha	[𑀕]	phu	𑀕	dhra	𑀕
ga	<sup>1</sup> 𑀓 <sup>2</sup> 𑀔 <sup>3</sup> 𑀕			ṣṇa	<sup>1</sup> 𑀓 <sup>2</sup> 𑀔 <sup>3</sup> 𑀕

\* Bottom strokes occur in the case of many letters, such as *a*, *ga*, *ja*, *sa*, and *da*; it is therefore sometimes impossible to say whether a letter is intended to be followed by *a* or *r*, or to be only usually varied.

† Forms in square brackets are not found on coins in the British Museum, but are cited as occurring elsewhere on the authority of General Cunningham.

‡ In the *Journal Asiatique* (xv, 508), M. Sarrat maintains that this sign has no phonetic value; General Cunningham, with hesitation, assigns to it the value of a long *a*; see notes on the coins to be sometimes indistinguishable from *a* and sometimes from *a*.

§ I cannot distinguish on the coins between *sa* and *ṣa*, *da* and *ḍa*; the forms of *da*, 𑀧 and 𑀧, are used interchangeably on the coins of Alexander.

THE ARIAN PALI ALPHABET, ON COINS.

Value.	Forma.	Value.	Forma.	Value.	Forma.
ni	<sup>1</sup> 𑖦 <sup>2</sup> 𑖧	no	𑖨	ni	𑖩
pa	<sup>1</sup> 𑖪 <sup>2</sup> 𑖫	pa	𑖬	pa	𑖭
pi	<sup>1</sup> 𑖮 <sup>2</sup> 𑖯	pi	𑖰	pi	𑖱
pu	𑖲	pu	𑖳	pu	𑖴
pra	𑖶	pe	𑖷	pha	𑖸
pri	𑖺	ra	𑖻	phra	[𑖼]
pha	<sup>1</sup> 𑖽 <sup>2</sup> 𑖾	raṇṇa	𑖿	phra	[𑗀]
phi	𑗁	ri	𑗂	so	<sup>1</sup> 𑗃 <sup>2</sup> 𑗄 <sup>3</sup> 𑗅
phre	𑗇	ru	𑗈	saṇṇa	𑗉
phsa	𑗊	rkha	𑗋	sa	𑗌
ba	𑗍	rle	𑗎	so	𑗏
bi	𑗐	rma	𑗑	so	<sup>1</sup> 𑗒 <sup>2</sup> 𑗓
bu	<sup>1</sup> 𑗔 <sup>2</sup> 𑗕	rea	𑗖	sa	𑗗
bru	𑗘	rpa	[𑗙]	si	𑗚
bha	𑗛	la	𑗜	si	𑗝
bha	<sup>1</sup> 𑗞 <sup>2</sup> 𑗟	li	𑗠	spa	𑗡
ma	<sup>1</sup> 𑗢 <sup>2</sup> 𑗣 <sup>3</sup> 𑗤	lu	𑗥	su	<sup>1</sup> 𑗦 <sup>2</sup> 𑗧
mi	𑗨	lo	<sup>1</sup> 𑗩 <sup>2</sup> 𑗪	la	𑗫
maṇṇa	𑗬	ra	𑗭	ku	𑗮
mi	𑗯	si	𑗰	he	𑗱
me	𑗲	ra	𑗳	ho	𑗴

# TABLE OF TRANSLITERATIONS AND RENDERINGS OF PRAKRIT LEGENDS.

Indian.	Greek equivalent.	English rendering.
INDIAN FALL		
Akathukleyasa	ΑΓΑΘΟΚΛΕΟΥΣ	King ( <i>genitive</i> ).
Pantalevasa	ΠΑΝΤΑΛΕΟΝΤΟΣ	
Rajino	ΒΑΣΙΛΕΩΣ	
ARIAN FALL		
Akathukreyasa*	ΑΓΑΘΟΚΛΕΟΥΣ	Invincible ( <i>gen.</i> ).
Amitasa	ΑΜΥΝΤΟΥ	
Antialikidasa	ΑΝΤΙΑΛΚΙΔΟΥ	
Antimakhasa	ΑΝΤΙΜΑΧΟΥ	Invincible ( <i>gen.</i> ).
Apalikhasa	ΑΝΙΚΗΤΟΥ	
Apodolasa	ΑΠΟΛΛΟΔΟΤΟΥ	
Apamjitasā	ΑΝΙΚΗΤΟΥ	Invincible ( <i>gen.</i> ).
Apantihata		Invincible ( <i>gen.</i> ).
Apantihatachakrasa		Invincible with the discus ( <i>gen.</i> ).
Apulaphanasa	ΑΠΟΛΛΟΦΑΝΟΥ <i>vic</i>	
Arkhodiyasa	ΑΡΧΕΒΙΟΥ	
Artemidorasa	ΑΡΤΕΜΙΔΩΡΟΥ	
Ashshakasa	ΑΡΣΑΚΟΥ	
Avadagasa	ΑΒΔΑΓΑΣΟΥ	
Ayasa	ΑΖΟΥ	
Ayadhasa or Ayadhasa	ΑΖΙΔΙΣΟΥ	

\* The distinction between long and short *a* is not preserved in this table, as the two forms seem to be used almost indiscriminately.

Indian.	Greek equivalent.	English rendering.
Bhradaputrassa Bhrata	ΛΔΕΛΦΙΔΕΩΣ ΑΔΕΛΦΟΣ	Brother's son ( <i>gen.</i> ). Brother.
Cha Chhatrapasa	ΣΑΤΡΑΠΟΥ	And ( <i>enclitic</i> ). Satrap ( <i>gen.</i> ).
Devatrataaa		Protected by the gods ( <i>gen.</i> )
Dhrammthidasa		Stealthy in the law ( <i>gen.</i> ). See below, suchadhrammthidasa.
Dhramikasa	ΔΙΚΑΙΟΥ	Just ( <i>gen.</i> ), for dhramikasa
Diyamedasa	ΔΙΟΜΗΔΟΥ	
Diani-iyasa	ΔΙΟΝΥΣΙΟΥ	
Epai-rasa	ΕΠΑΝΔΡΟΥ	
Eyukratidasa or Eukratidasa	ΕΥΚΡΑΤΙΔΟΥ	
Gudapharasa or Gadapharasa	ΓΟΝΔΟΦΑΡΟΥ or ΥΝΔΟΦΕΡΡΟΥ	
Heliyakreyasa	ΗΛΙΟΚΛΕΟΥΣ	
Heramayasa	ΕΡΜΑΙΟΥ	
Hiduja same		Just to those born on the Indian. Same is Sk. <i>manah</i> ( <i>nom.</i> ) Bendall.
Himakapigasa	ΟΟΗΜΟ ΚΑΔΦΙΣΟΥ	
Hipustratasa	ΙΠΠΟΣΤΡΑΤΟΥ	
Jayadhratasa	ΝΙΚΗΦΟΡΟΥ	Victorious ( <i>gen.</i> ).
Jayantasa or Jayatasa		Conquering: a secondary formation from the participle, common in all Prakrits and vernaculars. Bendall.
Jhailasa	ΖΩΙΛΟΥ	
Jhiloniasa	ΖΕΙΩΝΙΣΟΥ	

Indian.	Greek equivalent.	English rendering.
Karīyapāya	ΚΑΛΛΙΟΠΗ	God of the city of Karisi. Cunningham.
Karīyasa	ΚΑΔΑΦΕΣ	
Karīsiye nagara deva		
Kasana	ΚΑΔΦΙΣΟΥ	Kushan (tribe).
Kujala or Kuyula	ΚΟΖΟΥΛΟ or ΚΟΖΟΛΑ	
Kushana or Khushana	ΚΟΡΟΝ or ΧΟΡΑΝ	
Lisasa or Lisikasa	ΛΥΣΙΟΥ	
Mahachakrapāya		Sarap ( <i>gen.</i> ).
Mahanajusa	ΒΑΣΙΛΕΩΣ	King ( <i>gen.</i> ).
Maharajabhūta or Maharajabhūta	ΒΑΣΙΛΕΩΣ } ΑΔΕΛΦΟΣ }	Brother of the king.
Mahatasa or Mahatakasa	ΜΕΓΑΛΟΥ	Great ( <i>gen.</i> ): Pali, mahanta.
Mahāvarasa		Great prince ( <i>gen.</i> ).
Mamotrasa	ΜΕΝΑΝΔΡΟΥ	
Mosasa	ΜΑΥΟΥ	
Nikasa	ΝΙΚΙΟΥ	
Pakurasa	ΠΑΚΟΡΟΥ	
Palamakratasa	ΕΥΕΡΓΕΤΟΥ	Perhaps for Sk. pālanakratas- masa, 'able to protect' ( <i>gen.</i> ). Kā not being a Prakrit com- bination of letters, we have not been able to find an example of it in Arian Pali. Bendall.
Phalastana or Phalastana	ΦΙΛΟΞΕΝΟΥ	
Pratichhisa	ΕΠΙΦΑΝΟΥΣ	Illustrious: — for pratikaliyasa ( <i>gen.</i> ). Bendall.
Putasa	ΥΙΟΥ	Son ( <i>gen.</i> ).

Indian.	Greek equivalent.	English rendering
Rajabalsaa, Rajja- lulasa, &c. } Rajadimjasa or Rajarajasa	ΡΑΣΥ ΒΑΣΙΛΕΩΣ } ΒΑΣΙΛΕΩΝ }	King of kings ( <i>gen.</i> )
Sachadhrunaghidasa		Steadfast to true law:—for <i>sach-</i> <i>dharmasthitasya</i> ( <i>gen.</i> ) <i>Mad-</i> <i>dall</i> .
Sagaba		Brother:—for <i>agabha</i> . <i>Cum-</i> <i>ningham</i> .
Sampriyapita		To whom his father is very dear This seems to be a rendering of the Greek <i>philetaray</i> . <i>Cum-</i> <i>ningham</i> .
Sarvaloga isvarasa		Prince of all the world ( <i>gen.</i> )
Sasasa		
Spalagadamas		
Spalahorasa		
Spalirigasa		
Stratasa	ΣΠΑΛΙΡΙΣΟΥ ΣΤΡΑΤΩΝΟΣ	
Stratogasa		General ( <i>gen.</i> ), Greek <i>στρατηγος</i>
Tallphasa	ΤΗΛΕΦΟΥ	
Theophilasa	ΘΕΟΦΙΛΟΥ	
Tindatasa	ΣΩΤΗΡΟΣ	Saviour:—perhaps for a Persian <i>tragedation</i> ( <i>gen.</i> ), cf. Skt. <i>trī-</i> <i>pakartā</i> . <i>Bendall</i> .
Vriśabha	ΤΑΥΡΟΣ	Bull
Yavugasa or Yanasa	ΖΑΟΥ	Yush + ( <i>gen.</i> ).

### CORRIGENDA.

Page 68, no. 4, & p. 69, nos. 9, 10—The object described in the text as a whip over the king's shoulder seems to be merely the falling ends of the regal diadema, greatly exaggerated. On the coins of Azes and succeeding kings this view is adopted.

Pp. 103, 105—The first letter in the name of Gondophares (𑀧𑀲𑀭𑀸𑀓𑀲𑀺𑀓𑀲𑀺𑀓) is transliterated sometimes as *ga* and sometimes as *gu*. It may stand for either, or even *gam*.

# GREEK AND SCYTHIC KINGS OF BACTRIA AND INDIA.





No.	Wt.	Metal. Size.	Obverse.	Reverse.
<p>ANDRAGORAS, KING OF PARTHIA†</p> <p>B.C. <i>cir.</i> 300.</p> <p><i>Gold.</i></p>				
			Bust of Zeus r., wearing taenia; drapery round neck.	ΑΝΔΡΑΓΟΡ[ΟΥ Warrior r., in quadriga driven by Nike, and drawn by four horned horses, galloping.
1	131.9	N 7	behind, <i>IMP.</i>	[Pl. r. 1.]
<p><i>Silver.</i></p>				
			Head of a City r., wearing turreted crown.	ΑΝΔΡΑΓΟΡΟΥ Pallas standing l., clad in chiton and peplos; holds owl in r. l. rests on shield which is adorned with Gorgon's head; behind her, spear.
2	255.8	R 1-15	behind, <i>IMP.</i>	[Pl. r. 2.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<p style="text-align: center;">SOPHYTES, KING IN INDIA.</p> <p style="text-align: center;">B.C. <i>cir.</i> 300.</p> <p style="text-align: center;"><i>Silver.</i></p> <p>Head of the king r., in close-fitting helmet, bound with wreath; wing on cheek-piece.</p> <p style="text-align: right;">ΣΝΦΥΤΟΥ Cock r.; above, caduceus.</p>	
1	58.3	R 6	on section of neck, M.	[Pl. I. 3.]








DIODOTUS I., KING OF BACTRIA.

No.	Wt.	Metal. Size.	Obverse.	Reverse.
<p>DIODOTUS I., KING OF BACTRIA.</p> <p>Revolted <i>cir.</i> B.C. 250.</p> <p>(a) <i>Gold.</i></p> <p>Head of the king r., diad. <b>ΒΑΣΙΛΕΩΣ ΔΙΟΔΟΤΟΥ</b> Zeus striding to l., hurling thunder-bolt; aegis on l. arm; at his feet, eagle l.</p>				
1	130.3	N 75		to l., wreath. [Pl. I. 4.]
2*	128.3	N 75		" " [Pl. I. 5.]
<p>(β) <i>Silver.</i></p> <p>Head of the king r., diad. <b>ΒΑΣΙΛΕΩΣ ΔΙΟΔΟΤΟΥ</b> Zeus striding to l., hurling thunder-bolt; aegis on l. arm; at his feet, eagle l.</p>				
3	257.1	AR 115		to l., wreath. [Pl. I. 6.]
4	255.7	AR 105		" crescent. [Pl. I. 7.]
5	235.2	AR 1		" mon.
6	62.3	AR 7		to l., M. [Pl. I. 8.]
<p>(γ) <i>Bronze.</i></p> <p>Head of Zeus r., laur. <b>ΒΑΣΙΛΕΩΣ ΔΙΟΔΟΤΟΥ</b> Artemis, clad in short chiton, running r.; holds torch in both hands, quiver at shoulder; beside her, hound running r.</p>				
7		AE 85		[Pl. I. 9.]

\* The gold coins bearing an elderly head of Diodotus, and on the reverse the symbols of wreath and spear-head, are regarded as forgeries. They are very common, and all from one die.

No.	Wt.	Metal. Size.	Obverse.	Reverse.
<p>EUTHYDEMUS I., KING OF BACTRIA.</p> <p>(Successor of Diodotus II., <i>cir.</i> B.C. 220.)</p> <p>(a) <i>Gold.</i></p> <p>Head of the king r., diad. <b>ΒΑΣΙΛΕΩΣ</b> Herakles, bearded,  <b>ΕΥΘΥΔΗΜΟΥ</b> naked, seated l.  on rock; in r., club, which also  rests on rock.</p> <p>1 129· N 75 to l.,  [Pl. I. 10.]</p> <p>(β) <i>Silver; middle-aged portrait.</i></p> <p>Head of the king r., diad. <b>ΒΑΣΙΛΕΩΣ</b> Herakles, bearded,  <b>ΕΥΘΥΔΗΜΟΥ</b> naked, seated l.  on rock; in r., club, which also  rests on rock.</p> <p>2 254·6 AR 1·1 to r.,  [Pl. I. 11.]</p> <p>3 256·5 AR 1· " "</p> <p>4 241·2 AR 1·1 " " ; below, <b>N.</b> [L. O. C.]</p> <p>5 258·2 AR 1· to l.,  [Pl. II. 1.]</p> <p>6 252·5 AR 1·15 "  [L. O. C. Pl. II. 2.]</p> <p>7 255· AR 1·1 " "</p> <p>8 257·7 AR 1·15 " " [Pl. II. 3.]</p> <p>9 211·2 AR 1· (barbarous.)</p>				

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			Head of the king r., diad.	<b>ΒΑΣΙΛΕΩΣ</b> Herakles, bearded, <b>ΕΥΘΥΔΗΜΟΥ</b> naked, seated l. on rock, on which is spread lion's skin; in r. hand, club, which rests on his knee.
10	252.4	AR 1.15		to r., <b>Κ</b> . (traces of rock under club.) [Pl. n. 4.]
11	249.	AR 1.		" " (semi-barbarous.)
12	186.5	AR 1.		" " "
(γ) Silver; elderly portrait.				
			Head of the king r., diad.	<b>ΒΑΣΙΛΕΩΣ</b> Herakles, bearded, <b>ΕΥΘΥΔΗΜΟΥ</b> naked, seated l. on rock, on which is spread lion's skin; in r. hand, club, which rests on his knee.
13	256.7	AR 1.1		to r., <b>Κ</b> . [Pl. n. 5.]
14	60.8	AR .65		to r., <b>Κ</b> . [Pl. n. 6.]
(δ) Bronze.				
			Head of bearded Herakles r., bare.	<b>ΒΑΣΙΛΕΩΣ</b> Free horse r., <b>ΕΥΘΥΔΗΜΟΥ</b> prancing.
15		Æ .85		
16		Æ .85		[I. O. C. Pl. n. 7.]
17		Æ .85		[I. O. C.]
			Head of Zeus r., laur.	<b>ΒΑΣΙΛΕΩΣ</b> Free horse r., <b>ΕΥΘΥΔΗΜΟΥ</b> prancing.
18		Æ .7		to r., <b>Κ</b> . [I. O. C. Pl. n. 8.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
<p style="text-align: center;">DEMETRIUS, KING OF INDIA. (Son and successor of Euthydemus I.)</p> <p style="text-align: center;">(a) <i>Silver.</i></p> <p>Bust of the king r., diad., wearing elephant's scalp.</p> <p><b>ΒΑΣΙΛΕΩΣ ΔΗΜΗΤΡΙΟΥ</b> Young Herakles, facing; holds in l. hand, club and lion's skin; with r. hand, crowns himself with ivy-wreath.</p>				
1	259.5	AR 1.3		to l.,  . [Pl. II. 9.]
2	260.7	AR 1.2		" " [I. O. C.]
3	263.	AR 1.35		"  .
4	220.2 (plated)	AR 1.15		" " [I. O. C.]
5	235.5	AR 1.25		" <b>Σ</b> ; to r., <b>A</b> . (semi-barbarous.)
6	61.	AR .85		to l.,  . [I. O. C. Pl. II. 10.]
7	55.3	AR .8		"  ; to r.,  . [I. O. C.]
8	52.8	AR .8	(countermark: <b>Σ</b> , and Herakles crowning him- self.)	" <b>Δ</b> . "
9	9.	AR .5	(head, not bust.)	to l.,  . [Pl. II. 11.]
10	9.	AR .5		" "
11	10.5	AR .5		" " [I. O. C. Pl. II. 12.]
12	10.	AR .45		"  .

No.	WL	Metal, Size.	Obverse.	Reverse.
			(β) Bronze.	
			Bust of Herakles r., bearded, crowned with ivy; lion's skin round neck, club over shoulder.	<p>ΒΑΣΙΛΕΩΣ ΔΗΜΗΤΡΙΟΥ</p> <p>Artemis, radiate, facing, wearing short chiton; holds in l. hand, bow; with r. hand, draws arrow from quiver at her shoulder.</p>
13		Æ 1		to l., $\overline{\text{O}}$ .
14		Æ 1		" " [I. O. C. Pl. m. 1.]
			Gorgon-head, on round shield.	<p>ΒΑΣΙΛΕΩΣ ΔΗΜΗΤΡΙΟΥ</p> <p>Trident.</p>
15		Æ 1-35		to l., $\overline{\text{A}}$ .
			Head of elephant r., bell hung round neck.	<p>ΒΑΣΙΛΕΩΣ ΔΗΜΗΤΡΙΟΥ</p> <p>Caduceus.</p>
16		Æ 1-15		to l., $\Phi$ . [I. O. C. Pl. m. 2.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
<b>EUTHYDEMUS II., KING OF INDIA.</b>				
(Son and successor of Demetrius.)				
(a) <i>Silver.</i>				
			Bust of the king r., diad.	<b>ΒΑΣΙΛΕΩΣ ΕΥΘΥΔΗΜΟΥ</b> Young Herakles, facing, ivy- crowned; holds in r. hand, wreath of ivy; in l. hand, club and lion's skin.
1	260.7	AR 1.35		to L, $\mathcal{R}$ . [Pl. iv. 3.]
2	65.1	AR .75		to L, $\Phi$ .
3	63.5 (plated)	AR .75		" " [Pl. iii. 4.]
(β) <i>Nickel.</i>				
			Head of Apollo r., laur.	<b>ΒΑΣΙΛΕΩΣ ΕΥΘΥΔΗΜΟΥ</b> Tripod-lebes.
4	118.2	NI .95		to L, $\Phi$ . [Pl. iii. 5.]
(γ) <i>Bronze.</i>				
			Head of Apollo r., laur.	<b>ΒΑΣΙΛΕΩΣ ΕΥΘΥΔΗΜΟΥ</b> Tripod-lebes.
5		Æ 1.1		to L, $\Phi$ . [Pl. iii. 6.]
			Head of bearded Herakles r., bare.	<b>ΒΑΣΙΛΕΩΣ ΕΥΘΥΔΗΜΟΥ</b> Free horse r., prancing.
6		Æ .9		[Pl. iii. 7.]

PANTALEON, KING OF INDIA.



No.	Wt.	Metal, Size.	Obverse.	Reverse.
			<p>PANTALEON, KING OF INDIA.</p> <p>(Son and successor † of Demetria.)</p> <p>(α) <i>Nickel.</i></p>	
1	110.2	NI-95	<p>Bust of young Dionysos r., wearing ivy-wreath; thyrsos over shoulder.</p>	<p>ΒΑΣΙΛΕΩΣ Panther to r., ΠΑΝΤΑΛΕΟΝΤΟΣ l. fore-paw raised. to l., EY 1</p>
			<p>(β) <i>Bronze, round.</i></p>	
2		Æ 25	<p>Bust of young Dionysos r., wearing ivy-wreath; thyrsos over shoulder.</p>	<p>ΒΑΣΙΛΕΩΣ Panther to r., ΠΑΝΤΑΛΕΟΝΤΟΣ l. fore-paw raised. to l., A. [Pl. m. 8.]</p>
			<p>(γ) <i>Bronze, square.</i></p>	
3		Æ 96	<p>§ 27 (Rājine Pam- talecava*). 𑀘𑀓𑀭𑀺𑀓 Female figure l. with long pen- dants from her ears, clad in oriental dress with trousers; holds in her r. hand a flower.</p>	<p>ΒΑΣΙΛΕΩΣ Maneless lion r., ΠΑΝΤΑΛΕΟΝΤΟΣ in incuse square. [Pl. m. 9.]</p>
4		Æ 85		
5		Æ 9		[I. O. C.]









\* I repeat General Cunningham's reading of this inscription and those on the coin of Agathocles. The Indian inscription in the text is a facsimile taken from the inscriptions on the coins: some of the forms of letters seem abnormal.

No.	Wt.	Metal. Size.	Obverse.	Reverse.
<b>AGATHOCLES, KING OF INDIA.</b>				
(Son and successor of Demetrius.)				
(a) <i>Silver; with portraits of his predecessors.</i>				
1	251.2	AR 1.4	<b>ΑΛΕΞΑΝΔΡΟΥ</b> <b>ΤΟΥ ΦΙΛΙΠΠΟΥ</b> Head of Alexander as Herakles r., in lion's skin.	<b>ΒΑΣΙΛΕΥΟΝΤΟΣ</b> Zeus seated <b>ΑΓΑΘΟΚΛΕΟΥΣ</b> l. on throne <b>ΔΙΚΑΙΟΥ</b> with back; holds eagle and long sceptre.
				to l., R. [Pl. iv. 1.]
2	263.5	AR 1.3	<b>ΔΙΟΔΟΤΟΥ</b> Head of <b>ΣΩΤΗΡΟΣ</b> Diodotus r., diad.	<b>ΒΑΣΙΛΕΥΟΝΤΟΣ</b> Zeus striding <b>ΑΓΑΘΟΚΛΕΟΥΣ</b> to l., hurling <b>ΔΙΚΑΙΟΥ</b> thunderbolt, aegis on l. arm; at his feet, eagle l.
				to l., wreath; to r., S. [Pl. iv. 2.]
3	261.2	AR 1.2	<b>ΕΥΘΥΔΗΜΟΥ</b> Head <b>ΘΕΟΥ</b> of Euthy- demus I. r., diad.	<b>ΒΑΣΙΛΕΥΟΝΤΟΣ</b> Herakles, <b>ΑΓΑΘΟΚΛΕΟΥΣ</b> bearded, <b>ΔΙΚΑΙΟΥ</b> naked, seated l. on rock; in r. hand, club, which rests on a rock.
				to r., Φ. [Pl. iv. 3.]
(β) <i>Silver; with his own portrait.</i>				
			Bust of the king r., diad.	<b>ΒΑΣΙΛΕΩΣ</b> Zeus, facing, clad <b>ΑΓΑΘΟΚΛΕΟΥΣ</b> in himation; holds in r. hand, three-headed Hekate who bears two torches; in his l. hand, long sceptre.
4	240.8	AR 1.2		to l., Φ. [Pl. iv. 4.]
5	63.6	AR .8		[Pl. iv. 5.]

No.	Wt.	Metal. Sino.	Obverse.	Reverse.
(7) <i>Nickel.</i>				
6	117.5	NI 1.	Bust of Dionysos r., wearing ivy-wreath, thyrsos over shoulder.	<p>ΒΑΣΙΛΕΩΣ Panther r., touching a vine with his raised paw.</p> <p>ΑΓΑΘΟΚΛΕΟΥΣ</p> <p>to 1, <math>\Phi</math>. [Pl. iv. 6.]</p>
	63.5	NI .65		<p>[below, K. [Pl. iv. 7.]</p>
(8) <i>Bronze, round.</i>				
8		Æ 9	Bust of Dionysos r., wearing ivy-wreath, thyrsos over shoulder.	<p>ΒΑΣΙΛΕΩΣ Panther r., touching a vine with his raised paw.</p> <p>ΑΓΑΘΟΚΛΕΟΥΣ</p> <p>to 1, R. [L. O. C. Pl. iv. 8.]</p>
(9) <i>Bronze; square; bilingual.</i>				
			<p>§ 1 1 (Rājine Akathu- kleyasa).</p> <p>Female figure l. with long pendants from her ears, clad in oriental drapery with trousers; holds in her r. hand a flower.</p>	<p>ΒΑΣΙΛΕΩΣ Maneless lion r., in incuse square.</p> <p>ΑΓΑΘΟΚΛΕΟΥΣ</p>
9		Æ 9		
10		Æ 1.05		
11		Æ 1.05		
12		Æ 1.		[L. O. C. Pl. iv. 3.]
13		Æ .8		
14		Æ .95		















No.	Wt.	Metal. Size.	Obverse.	Reverse.
			(Q) <i>Bronze; square; Indian legend.</i>	
15		Æ 75	𑀧𑀢𑀺𑀓𑀢𑀺𑀓𑀢𑀺𑀓𑀢𑀺𑀓 (Aka- thukreyasa). Buddhist stupa, surmounted by star.	𑀮𑀺𑀓𑀢𑀺𑀓𑀢𑀺𑀓𑀢𑀺𑀓 (Hiduja Same). Tree in a square railed enclosure.  [letters? in field. [Pl. iv. 10.]
<hr/>				
ANTIMACHUS, KING OF INDIA.				
(Descendant and successor of Diodotus I).				
(a) <i>Silver.</i>				
			Bust of the king r., diad., wearing causia.	ΒΑΣΙΛΕΥΣ ΘΕΟΥ Ποσειδων, ANTIMAXΟΥ facing, wear- ing himation and wreath; holds in r. hand, trident; in l., palm, bound with fillet.
1	262.3	AR 1.35		to r., (N). [Pl. v. 1.]
2	260.5	AR 1.15		" "
3	252.3	AR 1.2		" R.
4	59	AR 8		to r., (N).
5	31.5	AR 6		to r., (N). [Pl. v. 2.]
6	10.6	AR 45		to r., R. [I. O. C. Pl. v. 3.]



No.	Wt.	Metal Size.	Obverse.	Reverse.
<p>EUCRATIDES, KING OF BACTRIA AND INDIA.          (Contemporary of Antiochus IV. and Demetrius I. of Syria.)          (α) <i>Silver ; type, Apollo.</i></p>				
			Bust of the king r., diad.: fillet-border.	ΒΑΣΙΛΕΩΣ Apollo l., clad in ΕΥΚΡΑΤΙΔΟΥ chlamys and boots; holds arrow and bow.
1	257·2	AR 1·2		to l.,  .
2	256·5	AR 1·3		"  .
3	261·	AR 1·3		" " [L. O. C. Pl. v. 4.]
4	261·	AR 1·3		" " [L. O. C.]
5	58·5	AR ·7	(border of dots.)	to l., KI. [L. O. C. Pl. v. 5.]
<p>(β) <i>Silver ; type, The Dioscuri.</i></p>				
			Bust of the king r., diad.: fillet-border.	ΒΑΣΙΛΕΩΣ The Dioscuri ΕΥΚΡΑΤΙΔΟΥ charging r., holding long lances and palms.
6	258·5	AR1·25		below, K. [Pl. v. 6.]
7	259·	AR1·25		" W. [L. O. C.]

No.	Wt.	Metal. Sine.	Obverse.	Reverse.
			Bust of the king r., diad., and wearing helmet in the shape of a canis, adorned with ear and horn of bull, and crest: fillet-border.	ΒΑΣΙΛΕΩΣ ΜΕΓΑΛΟΥ ΕΥΚΡΑΤΙΔΟΥ The Dioscuri charging r., holding long lances and palms.
8	261.2	AR 1.35		below  .
9	258.2	AR 1.35		"  . [Pl. v. 7.]
10	259.6	AR 1.3		"  .
11	258.8	AR 1.2		"  .
12	258.7	AR 1.35		" "
13	258.2	AR 1.3		"  . [Pl. v. 8.]
14	244.5	AR 1.35		to L,  . [L. O. C.]
15	57.5	AR 8		below,  . [Pl. v. 9.]
16	62.3	AR 75	(border of dots.)	" "
17	59.5	AR 75	( " )	" N. (semi-barbarous.)
18	55.3	AR 75	( " )	to L,  . (ΒΑΣΙΛΕΩΣ written ΣΙΛΕΩΣ). [L. O. C.]

No.	Wt.	Metal. Slao.	Obverse.	Reverse.
(γ) Silver; type, Pilei of Dioseuri.				
			Bust of the king r., diad.	ΒΑΣΙΛΕΩΣ ΕΥΚΡΑΤΙΔΟΥ The pilei of surmounted by stars; and palms. Dioseuri
19	9.9	AR 45		below, R. [I. O. C.]
20	9.1	AR 45		" Φ.
21	9.9	AR 45		" ΒΡ.
22	10.8	AR 5		" ΒΡ. [I. O. C. Pl. v. 10]
23	9.5	AR 45		" " [I. O. C.]
24	10.	AR 45		" K.
25	9.2	AR 45		" W.
26 (broken)	7.3	AR 4		" Η. [I. O. C.]
<hr/>				
			Bust of the king r., diad. and helmeted.	ΒΑΣΙΛΕΩΣ ΕΥΚΡΑΤΙΔΟΥ Similar type.
27	9.9	AR 45		below, W.
28	10.1	AR 45		" " [Pl. v. 11.]
29	10.	AR 45		" "
30 (broken)	6.	AR 4		" ΠΓ. [I. O. C.]

	Wt.	Metal. Size.	Obverse.	Reverse.
(δ)	Bronze ; round ; type, Dioscurel.			
			Bust of the king r., diad. and helmeted : fillet-border.	ΒΑΣΙΛΕΩΣ ΜΕΓΑΛΟΥ ΕΥΚΡΑΤΙΔΟΥ The Dioscurel charging r., holding long lances and palms.
	Æ 95			below, ☞.
	Æ 105			" "
	Æ 9			" ☛. [L O C.]
	Æ 8			" ☞. [L O C. Pl. VI I.]
			Similar.	Same inser. One of the Dioscurel charging r., holding long lance.
	Æ 6			[Pl. VI 2.]
(ε)	Bronze ; square ; type, Dioscurel.			
			ΒΑΣΙΛΕΩΣ ΜΕΓΑ- ΛΟΥ ΕΥΚΡΑΤΙΔΟΥ Bust of the king r., diad. and helmeted.	𐤁𐤓𐤕~𐤏 (Māhārājasa Eru- krātīdusa or Eū- krātīdasa). The Dioscurel charging r., holding long lances and palms.
	Æ 85			to L, ☞; to r., E. [L O C. Pl. VI 3.]
	Æ 75			" " " " [L O C.]
	Æ 9			" " " "
	Æ 8			" ☛.

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<b>ΒΑΣΙΛΕΥΣ ΜΕΓΑ-</b> <b>ΛΟΥ ΕΥΚΡΑΤΙΔΟΥ</b> Bust of the king r., diad. and helmeted.	 (Māhārājasa Eukratīdasa) or Eukratīdasa). The Dioscuri charging r., holding long lances and palms.
40	Æ 95			to r.,  .
41	Æ 9			"  .
42	Æ 9			"  .
43	Æ 95			" "
44	Æ 85			"  .
45	Æ 85			"  [L. O. C.]
46	Æ 85			"  "
47	Æ 9			"  .
48	Æ 9			"  .
49	Æ 85			"  .
50	Æ 8			"  (J for J).
51	Æ 9			"  [L. O. C.]
52	Æ 9			"
53	Æ 7			to r.,  [L. O. C.]
54	Æ 65			"  .
55	Æ 7			[L. O. C. Pl. vi. 4.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<b>ΒΑΣΙΛΕΩΣ ΜΕΓΑ- ΛΟΥ ΕΥΚΡΑΤΙΔΟΥ</b> Head of the king r., diad., without helmet.	<b>𐎲𐎠𐎧𐎡𐎴</b> (Māharajasa Euv- <b>𐎲𐎠𐎧𐎡𐎴</b> krātīdasa). The pilei of the Dioscuri surmounted by stars, and two palms.
56		Æ 6		
57		Æ 6		[I. O. C. Pl. vi. 5.]
(ζ) Bronze; square; type, Nike.				
			<b>ΒΑΣΙΛΕΩΣ ΜΕΓΑ- ΛΟΥ ΕΥΚΡΑΤΙΔΟΥ</b> Bust of the king r., diad. and helmeted.	<b>𐎲𐎠𐎧𐎡𐎴</b> (Māharajasa Euv- <b>𐎲𐎠𐎧𐎡𐎴</b> kratīdasa). Nike l., bearing wreath and palm.
58		Æ 65		to l.  .
59		Æ 75		" " [I. O. C. Pl. vi. 6.]
60		Æ 7		" "
<hr/>				
			Similar 1 (obscure coin).	Same inscr. 1 Nike r., bearing wreath and palm.
61		Æ 65		
			<b>ΜΕΓΑΛΟΥ ΒΑΣΙΛ- ΕΩΣ ΕΥΚΡΑΤΙΔΟΥ</b> Bust of the king l., helmeted, striking with spear.	Same inscr. Nike r., bearing wreath and palm.
62		Æ 9		to r.  . [I. O. C. Pl. vi. 7.]



No.	Wt.	Metal Size.	Obverse.	Reverse.
1	249.	AR 13	<p>PLATO. B.C. 166.</p> <p>(Contemporary of Eucratides.)</p> <p>(a) <i>Silver.</i></p> <p>Bust of the king r., diad. and wearing helmet adorned with ear and horn of bull, and crest: fillet-border.</p>	<p>ΒΑΣΙΛΕΩΣ ΕΠΙΦΑΝΟΥΣ ΠΛΑΤΩΝΟΣ Helios r., radiate, clad in chiton and chlainys; in quadriga.</p> <p>to r., <b>Μ</b>; in ex., <b>PMI</b>.* [Pl. VI. 11.] (year 147 of the Seleucid era.)</p>
				<p>* The <b>P</b> can scarcely be considered a certainty, but a down stroke is visible, which seems to prove that a third letter existed.</p>

No.	Wt.	Metal. Size.	Obverse.	Reverse.
<p style="text-align: center;">HELIOCLES.</p> <p style="text-align: center;">(Son or brother of Eucratides.)</p> <p style="text-align: center;">(a) <i>Silver; Greek inscription; Attic weight.</i></p>				
			Bust of the king r., diad.: fillet-border.	<p><b>ΒΑΣΙΛΕΥΣ</b>      Zeus, laur.,  <b>ΗΛΙΟΚΛΕΟΥΣ</b>      facing, clad in  <b>ΔΙΚΑΙΟΥ</b>      himation; holds  winged thunderbolt and long  acceptre.</p>
1	261·2	AR 1·3		to l., ΚΡ.      [Pl. vii. 1.]
2	258·	AR 1·25		" "      [I. O. C.]
3	259·7	AR 1·25		" Σ.      [Pl. vii. 2.]
4	249·8	AR 1·15		" Α.
5	246·6	AR 1·4		in ex., ΠΓ.
6	240·8	AR 1·3		to l., Ε.
7	205·1	AR 1·05 (plated)		" Α.
8	58·9	AR·8		in ex., ΠΓ.      [Pl. vii. 3.]
9	56·7	AR·8		" Δ or Λ.
10	56·8	AR·8		to l., Α. (inscr. semi-barbarous.) [I. O. C.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			(β) <i>Barbarous copies in bronze.</i>	
			Rude copy of bust of Helioctes r., diad.: fillet-border.	Barbarous degradation of— <b>ΒΑΣΙΛΕΩΣ</b> Zeus, facing; <b>ΗΛΙΟΚΛΕΟΥΣ</b> holds thunder- <b>ΔΙΚΑΙΟΥ</b> bolt and long sceptre.
11		Æ 1·2		
12		Æ 1·1		[I. O. C.]
13		Æ 1·2		[I. O. C.] (restruck on type next described.)
			Similar.	<b>ΒΑΣΙΛΕΩΣ</b> Horse trotting l. <b>ΗΛΙΛΕΥΣ</b> <b>ΔΙΚΑΙΟΥ</b> (varied).
14		Æ 1·1		
15		Æ 1·1		
16		Æ 1·15		[I. O. C.]
17		Æ 1·1		[I. O. C.]
18		Æ 75		[Pl. VII. 4.]
19		Æ 7		
20		Æ 7		[I. O. C.]
21		Æ 6		

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			(ANOTHER HELIOCLÉS ?).	
			(γ) Silver; Indian inscription; Persian weight.	
			ΒΑΣΙΛΕΩΣ ΔΙΚΑΙ- ΟΥ ΗΛΙΟΚΛΕΟΥΣ Bust of the king r., diad.	𐎠𐎡𐎴𐎧𐎺𐎠𐎫𐎲𐎶𐎵𐎹 (Māhōrajasa 𐎠𐎡𐎴𐎧𐎺𐎠𐎫𐎲𐎶𐎵𐎹 dhramikasa <i>Heliakreyasa</i> ). Zeus, laur., facing, clad in himation; holds winged thunderbolt and long sceptre.
22	146·4	AR 105		to l., 𐎠𐎡. [I. O. C. Pl. VII. 5.]
23	34·5	AR 65		to l., Σ. [I. O. C. Pl. VII. 6.]
24	34·2	AR 65		" "
25	26·3	AR 65		" 𐎠𐎡.
			(δ) Bronze; square.	
			ΒΑΣΙΛΕΩΣ ΔΙΚΑΙ- ΟΥ ΗΛΙΟΚΛΕΟΥΣ Bust of the king r., diad.	𐎠𐎡𐎴𐎧𐎺𐎠𐎫𐎲𐎶𐎵𐎹 (Māhōrajasa 𐎠𐎡𐎴𐎧𐎺𐎠𐎫𐎲𐎶𐎵𐎹 dhramikasa <i>Heliakreyasa</i> ). Elephant l.
26		AE 85		below, 𐎠𐎡.
27		AE 85		" "





No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<p>ΒΑΣΙΛΕΥΣ ΝΙΚΗ- ΦΟΡΟΥ ΑΝΤΙΑΛ- ΚΙΔΟΥ Bust of the king r., diad.</p>	<p>𐎠𐎡𐎢𐎣𐎤𐎥𐎦𐎧𐎨𐎩𐎪𐎫𐎬𐎭𐎮𐎯𐎰𐎱𐎲𐎳𐎴𐎵𐎶𐎷𐎸𐎹𐎺𐎻𐎼𐎽𐎾𐎿 (Māhā- 𐎠𐎡𐎢𐎣𐎤𐎥𐎦𐎧𐎨𐎩𐎪𐎫𐎬𐎭𐎮𐎯𐎰𐎱𐎲𐎳𐎴𐎵𐎶𐎷𐎸𐎹𐎺𐎻𐎼𐎽𐎾𐎿 rajasa jayalharasa Antialikidasa). Zeus seated l. on throne; holds in r. hand, Nike; in l., sceptre; to l., forepart of elephant, who raises his trunk.</p>
6	33.3	AR 65	(king helmeted).	to r., 𐎠𐎡. (elephant r.)
7	34.5	AR 7	"	below throne, 𐎠𐎡. "
8	37.2	AR 65	"	to r., 𐎠𐎡. " [I. O. C.]
9	35.8	AR 65	"	" " (elephant facing). [Pl. VII. 12.]
10	37.8	AR 65	"	" " (elephant l.) [I. O. C.]
11	37.6	AR 65	(king wears causia).	" " "
12	37.6	AR 7	"	" " [I. O. C.] Pl. VII. 13.]
Same inser. Bust of the king r., diad.				Same inser. Zeus seated l. on throne; holds in r. hand, Nike; in l., scap- tre; to l., forepart of elephant l., who carries off the wreath of Nike.
13	36.5	AR 6	(king wears causia).	below throne, 𐎠𐎡.
14	33.9	AR 6	"	" "
15	33.1	AR 65		" 𐎠𐎡. [Pl. VII. 14.]





No.	Wt.	Metal Size.	Obverse.	Reverse.
			<p>ΒΑΣΙΛΕΩΣ ΝΙΚΗ- ΦΟΡΟΥ ΑΝΤΙΑΛ- ΚΙΔΟΥ Bust of Zeus r., laur., with hand hurl- ing thunderbolt.</p>	<p>𐎧𐎡𐎢𐎠𐎥 𐎧𐎡𐎢𐎠𐎥 (Māhō- 𐎧𐎡𐎢𐎠𐎥 (2)7 rājasa jayadharasa Antialikhidasa). Lau- reate pilei of the Dioscuri, sur- mounted by stars; between them, two palms.</p>
26		Æ 75		to l. R.
27		Æ 75		" "
28		Æ 7		" R.
29		Æ 7		" " [Pl. viii. 3.]
30		Æ 85		above, "
			Same inscr., blundered. Aegis.	Same inscr., blundered. Palm and wreath.
31		Æ 85		below, K. [I. O. C. Pl. viii. 4.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
LYSIAS.				
(a) <i>Silver.</i>				
			<p>ΒΑΣΙΛΕΩΣ ΑΝΙΚΗ- ΤΟΥ ΛΥΣΙΟΥ Bust of the king r., diad.</p>	<p>𐤁𐤕𐤁𐤕𐤁𐤕 𐤁𐤕𐤁𐤕𐤁𐤕 𐤁𐤕𐤁𐤕𐤁𐤕 (<i>Māhārāja</i> <i>apadihātasa Lisikasa</i>). Young Herakles, facing; holds in l. hand, club, palm, and lion's skin; with r. hand crowns himself with vine- leaves.</p>
1	30.8	AR 65		to l., Α; to r., Σ. [Pl. viii. 5.]
2	37.4	AR 7	(king wears elephant's scalp).	" " " " (palm not visible.)
3	37.9	AR 7	" "	" " " " [I. O. C. Pl. viii. 6.]
4	34.4	AR 7	" "	" Η. [I. O. C.]
5	36.	AR 7	" "	" Κ. "
6	33.5	AR 65	(king helmeted).	" Α; " "
7	36.4	AR 65	"	" Η. (king's name written 𐤁𐤕𐤁𐤕𐤁𐤕, <i>Lisikasa</i> .) [Pl. viii. 7.]
(β) <i>Bronze; round.</i>				
			<p>ΒΑΣΙΛΕΩΣ ΑΝΙΚΗ- ΤΟΥ ΛΥΣΙΟΥ Bust of bearded Herakles r.; club and palm over shoulder.</p>	<p>𐤁𐤕𐤁𐤕𐤁𐤕 𐤁𐤕𐤁𐤕𐤁𐤕 𐤁𐤕𐤁𐤕𐤁𐤕 (<i>Māhārāja</i> <i>apadihātasa Lisikasa</i>). Elephant r., walking.</p>
8		Æ 95		below, Η. [Pl. viii. 8.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			(γ) <i>Bronze; square.</i>	
			<b>ΒΑΣΙΛΕΩΣ ΑΝΙΚΗ-</b> <b>ΤΟΥ ΛΥΣΙΟΥ</b> Bust of bearded Herakles r.; lion's skin round neck, and club over shoulder.	<p>𐎲𐎧𐎺𐎠𐎧𐎺 𐎲𐎧𐎺𐎠𐎧𐎺  𐎲𐎧𐎺𐎠𐎧𐎺 (<i>Māhārāja</i>  <i>apadihātasa Lisikasa</i>). Elephant r.,  walking.</p>
9	Æ 75			below, Α Σ. [Pl. VIII. 9.]
10	Æ 8			" " "
11	Æ 75			" " "
12	Æ 7			above, R.
13	Æ 75			below, K.
14	Æ 85			" 𐎲𐎧𐎺. (king's name written 𐎲𐎧𐎺𐎠𐎧𐎺, <i>Lisikasa</i> .)



No.	Wt.	Metal. Size.	Obverse.	Reverse.
<p>ARCHEBIUS.</p> <p>(a) <i>Silver.</i></p>				
1	139.	AR 105.	<p>ΒΑΣΙΛΕΥΣ ΔΙΚΑΙ- ΟΥ ΝΙΚΗΦΟΡΟΥ ΑΡΧΕΒΙΟΥ Bust of the king r., diad.</p>	<p>𐎲𐎠𐎼𐎿 𐎠𐎡𐎴𐎡𐎴 𐎠𐎡𐎴𐎡𐎴 𐎠𐎡𐎴𐎡𐎴 (Māhārājasa dhramikasa jayadharasa Arkhe- biyasa). Zeus, facing, clad in hima- tion; holds long sceptre in l. hand, and hurls thunderbolt with r.</p> <p>to l., 𐎡. [I. O. C. Pl. ix. 1.]</p>
2	36.	AR 7.		to r., 𐎡. [Pl. ix. 2.]
3	36.3	AR 65.	(king helmeted).	" " [Pl. ix. 3.]
4	147.6	AR 1.	(king helmeted).	<p>𐎲𐎠𐎼𐎿 𐎠𐎡𐎴𐎡𐎴 𐎠𐎡𐎴𐎡𐎴 𐎠𐎡𐎴𐎡𐎴 (Māhārājasa dhramikasa jayadharasa Arkhe- biyasa). Zeus, facing, clad in hima- tion; holds long sceptre in l. hand, and hurls thunderbolt with r.</p> <p>to l., 𐎡. [I. O. C. Pl. ix. 4.]</p>
5	34.4	AR 7.		<p>to l., 𐎡; to r., 𐎡.</p> <p>[I. O. C. Pl. ix. 5.]</p>
<p>(β) <i>Bronze; round.</i></p>				
6		Æ 1.	<p>ΒΑΣΙΛΕΥΣ ΔΙΚΑΙ- ΟΥ ΝΙΚΗΦΟΡΟΥ ΑΡΧΕΒΙΟΥ Nike l., holding wreath and palm.</p>	<p>𐎲𐎠𐎼𐎿 𐎠𐎡𐎴𐎡𐎴 𐎠𐎡𐎴𐎡𐎴 𐎠𐎡𐎴𐎡𐎴 (Māhārājasa dhramikasa jayadharasa Arkhe- biyasa). Owl r.</p> <p>to r., 𐎡. [Pl. ix. 6.]</p>

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			(γ) <i>Bronze; square.</i>	
			<p>ΒΑΣΙΛΕΩΣ ΔΙΚΑΙ- •Υ ΝΙΚΗΦ•Ρ•Υ ΑΡΧΕΒΙ•Υ Elephant r.</p>	<p>ΥΓΖΛΥ ΥΖΨΞ ΥΥΓ~Υ ΥΛΥΓΖ (Māhārāja dhranikasa jayadharasa Arkhe- biyasa). Owl r.</p>
7		Æ 1.		below,  . [Pl. ix. 7.]
8		Æ 9		"  . [L. O. C.]



No.	Wt.	Metal Sigs.	Obverse.	Reverse.
			(γ) <i>Bronze; square.</i>	
			<p>ΒΑΣΙΛΕΩΣ ΑΠΟΛ- ΛΟΔΟΤΟΥ ΣΩΤΗ- ΡΟΣ Apollo, laur., facing; holds in r. hand, arrow; in l., bow.</p>	<p>𐀀𐀃𐀆𐀇 𐀀𐀃𐀆𐀇𐀀𐀃𐀆𐀇 𐀀𐀃𐀆𐀇𐀀𐀃𐀆𐀇 (<i>Māhūrajasa Apaladatasa trāṣa-</i> <i>tasa</i>). Tripod on stand, in square of dota.</p>
13	Æ 9			[Pl. ix. 10.]
14	Æ 95			[I. O. C.]
15	Æ 85			to r., A.
16	Æ 85		to l., 𐀀.	.. 𐀀.
17	Æ 95			.. 𐀀.
18	Æ 9			.. " [I. O. C.]
19	Æ 9			.. "
20	Æ 9			.. 𐀀.
21	Æ 9			.. 𐀀. [I. O. C.]
22	Æ 1			.. A. "
23	Æ 9			.. 𐀀. "
24	Æ 75			.. " [Pl. ix. 11.]











No.	Wt.	Metal. Size.	Obverse.	Reverse.
			STRATO I.	
			(a) <i>Silver.</i>	
			ΒΑΣΙΛΕΥΣ ΕΠΙΦΑ- ΝΟΥΣ ΣΩΤΗΡΟΣ ΣΤΡΑΤΩΝΟΣ Bust of the king r., diad.	𐎧𐎡𐎢𐎣 𐎧𐎶𐎥𐎺 𐎧𐎶𐎥𐎺 𐎧𐎶𐎥𐎺 (Māhūrajasa pratichhasa tradatasa Stratasas). Pallas l., holding with l. hand aegis, and with r. hurling thunderbolt.
1	133.3	AR 1.05	(king wears helmet.)	to l., 𐎧. [Pl. x. 10.]
2	31.3	AR 7		to l., 𐎧.
3	36.2	AR 7		" R. [Pl. x. 11.]
4	33.3	AR 65		" "
			ΒΑΣΙΛΕΥΣ ΣΩΤΗ- ΡΟΣ ΣΤΡΑΤΩΝΟΣ Bust of the king r., diad.	𐎧𐎡𐎢𐎣 𐎧𐎶𐎥𐎺 (Māhūrajasa 𐎧𐎶𐎥𐎺 tradatasa Stra- tasa). Similar type.
5	35.8	AR 7	(king helmeted.)	to l., 𐎧. [Pl. x. 12.]
6	35.3	AR 6		" 2; to r., 𐎧. (semi-barbarous.)
7	37.6	AR 65		" 𐎧; " 𐎧. [I. O. C. Pl. x. 13.]
8	35.4	AR 6		" 𐎧; " 3. "
9	† 34.4	AR 6	inscr. . . . . ΠΟΝΟΣΑ ΝΟΣ	" " 𐎧. [Pl. x. 14.] "
10	32.2	AR 65		" 𐎧; " 3. [I. O. C.] "
				(last line of inscr. padayashasa †).
			* Or 𐎧, <i>prichchhasa</i> .	
			† This is one of the coins sometimes wrongly given to an imaginary king, Rosastanon.	

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<p>ΒΑΣΙΛΕΥΣ ΣΩΤΗ- ΡΟΣ ΔΙΚΑΙΟΥ ΣΤΡΑΤΩΝΟΣ Bust of the king r., diad.</p>	<p>𐤁𐤁𐤅𐤁𐤁 𐤁𐤁𐤅𐤁𐤁 𐤁𐤁𐤅𐤁𐤁 𐤁𐤁𐤅 (Mahārājaśa tradatasa dhranīhasa Strātasa). Pallas r., holding in l. hand aegis, and with r. hurling thunderbolt.</p>
11	32.7	AR 65		to l., 𐤁𐤁. [Pl. xi. 1.]
(β) Bronze; round.				
			<p>ΒΑΣΙΛΕΥΣ ΕΠΙΦΑ- ΝΟΥΣ ΣΩΤΗΡΟΣ ΣΤΡΑΤΩΝΟΣ Bust of Apollo r., laur.; hair in queue.</p>	<p>𐤁𐤁𐤅𐤁𐤁 𐤁𐤁𐤅𐤁𐤁 𐤁𐤁𐤅𐤁𐤁 𐤁𐤁𐤅 (Mahārājaśa pratichhasa tradatasa Strātasa). Bow and quiver, with strap.</p>
12		AE 1		to l., R. [Pl. xi. 2.]
(γ) Bronze; square; type, Apollo.				
			<p>ΒΑΣΙΛΕΥΣ ΕΠΙΦΑ- ΝΟΥΣ ΣΩΤΗΡΟΣ ΣΤΡΑΤΩΝΟΣ Apollo, facing; holds in r. hand, arrow; in l., bow.</p>	<p>𐤁𐤁𐤅𐤁𐤁 𐤁𐤁𐤅𐤁𐤁 𐤁𐤁𐤅𐤁𐤁 𐤁𐤁𐤅 (Mahārājaśa pratichhasa tradatasa Strātasa). Tripod-kebas, on stand.</p>
13		AE 95		to l., 𐤁𐤁; to r., R. [L. O. C. Pl. xi. 3.]
14		AE 9		" 𐤁𐤁. [L. O. C.]
15		AE 9		" 𐤁𐤁.
16		AE 85		" 𐤁, to r., 𐤁 and mon. [L. O. C.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			(δ) <i>Bronze; square; type, Nike.</i>	
			<b>ΒΑΣΙΛΕΩΣ ΣΩΤΗ-</b> <b>ΡΟΣ ΣΤΡΑΤΩΝΟΣ</b> Bust of bearded Hera- kles r.; over shoulder, club bound with taenia.	<b>𐎧𐎡𐎴 𐎧𐎡𐎴 𐎧𐎡𐎴.~𐎶</b> <i>(Māhārājasa tradatasa Stratasa).</i> Nikē r., holds wreath and palm.
17		Æ 8		to r.,  . [I. O. C. Pl. xi. 4.]
18		Æ 85		" <b>Σ.</b> [I. O. C.]
19		Æ 8		" "
			<b>ΒΑΣΙΛΕΩΣ ΣΩΤΗ-</b> <b>ΡΟΣ ΔΙΚΑΙΟΥ</b> <b>ΣΤΡΑΤΩΝΟΣ</b> Similar type.	<b>𐎧𐎡𐎴𐎶 𐎧𐎡𐎴 𐎧𐎡𐎴.~𐎶</b> <b>𐎧𐎡𐎴</b> <i>(Muharajasa</i> <i>tradatasa dhramikasa Stratasa).</i> Similar type.
20		Æ 9		to r.,  . [Pl. xi. 5.]



No.	Wt.	Metal. Slan.	Obverse.	Reverse.
MENANDER.				
(a) <i>Silver.</i>				
			ΒΑΣΙΛΕΥΣ ΣΩΤΗ- ΡΟΣ ΜΕΝΑΝΔΡΟΥ Bust of the king r., diad.	𐇀𐇁𐇂𐇃𐇄𐇅𐇆𐇇𐇈𐇉𐇊𐇋𐇌𐇍𐇎𐇏𐇐𐇑𐇒𐇓𐇔𐇕𐇖𐇗𐇘𐇙𐇚𐇛𐇜𐇝𐇞𐇟𐇠𐇡𐇢𐇣𐇤𐇥𐇦𐇧𐇨𐇩𐇪𐇫𐇬𐇭𐇮𐇯𐇰𐇱𐇲𐇳𐇴𐇵𐇶𐇷𐇸𐇹𐇺𐇻𐇼𐇽𐇾𐇿𐈀𐈁𐈂𐈃𐈄𐈅𐈆𐈇𐈈𐈉𐈊𐈋𐈌𐈍𐈎𐈏𐈐𐈑𐈒𐈓𐈔𐈕𐈖𐈗𐈘𐈙𐈚𐈛𐈜𐈝𐈞𐈟𐈠𐈡𐈢𐈣𐈤𐈥𐈦𐈧𐈨𐈩𐈪𐈫𐈬𐈭𐈮𐈯𐈰𐈱𐈲𐈳𐈴𐈵𐈶𐈷𐈸𐈹𐈺𐈻𐈼𐈽𐈾𐈿𐉀𐉁𐉂𐉃𐉄𐉅𐉆𐉇𐉈𐉉𐉊𐉋𐉌𐉍𐉎𐉏𐉐𐉑𐉒𐉓𐉔𐉕𐉖𐉗𐉘𐉙𐉚𐉛𐉜𐉝𐉞𐉟𐉠𐉡𐉢𐉣𐉤𐉥𐉦𐉧𐉨𐉩𐉪𐉫𐉬𐉭𐉮𐉯𐉰𐉱𐉲𐉳𐉴𐉵𐉶𐉷𐉸𐉹𐉺𐉻𐉼𐉽𐉾𐉿𐊀𐊁𐊂𐊃𐊄𐊅𐊆𐊇𐊈𐊉𐊊𐊋𐊌𐊍𐊎𐊏𐊐𐊑𐊒𐊓𐊔𐊕𐊖𐊗𐊘𐊙𐊚𐊛𐊜𐊝𐊞𐊟𐊠𐊡𐊢𐊣𐊤𐊥𐊦𐊧𐊨𐊩𐊪𐊫𐊬𐊭𐊮𐊯𐊰𐊱𐊲𐊳𐊴𐊵𐊶𐊷𐊸𐊹𐊺𐊻𐊼𐊽𐊾𐊿𐋀𐋁𐋂𐋃𐋄𐋅𐋆𐋇𐋈𐋉𐋊𐋋𐋌𐋍𐋎𐋏𐋐𐋑𐋒𐋓𐋔𐋕𐋖𐋗𐋘𐋙𐋚𐋛𐋜𐋝𐋞𐋟𐋠𐋡𐋢𐋣𐋤𐋥𐋦𐋧𐋨𐋩𐋪𐋫𐋬𐋭𐋮𐋯𐋰𐋱𐋲𐋳𐋴𐋵𐋶𐋷𐋸𐋹𐋺𐋻𐋼𐋽𐋾𐋿𐌀𐌁𐌂𐌃𐌄𐌅𐌆𐌇𐌈𐌉𐌊𐌋𐌌𐌍𐌎𐌏𐌐𐌑𐌒𐌓𐌔𐌕𐌖𐌗𐌘𐌙𐌚𐌛𐌜𐌝𐌞𐌟𐌠𐌡𐌢𐌣𐌤𐌥𐌦𐌧𐌨𐌩𐌪𐌫𐌬𐌭𐌮𐌯𐌰𐌱𐌲𐌳𐌴𐌵𐌶𐌷𐌸𐌹𐌺𐌻𐌼𐌽𐌾𐌿𐍀𐍁𐍂𐍃𐍄𐍅𐍆𐍇𐍈𐍉𐍊𐍋𐍌𐍍𐍎𐍏𐍐𐍑𐍒𐍓𐍔𐍕𐍖𐍗𐍘𐍙𐍚𐍛𐍜𐍝𐍞𐍟𐍠𐍡𐍢𐍣𐍤𐍥𐍦𐍧𐍨𐍩𐍪𐍫𐍬𐍭𐍮𐍯𐍰𐍱𐍲𐍳𐍴𐍵𐍶𐍷𐍸𐍹𐍺𐍻𐍼𐍽𐍾𐍿𐎀𐎁𐎂𐎃𐎄𐎅𐎆𐎇𐎈𐎉𐎊𐎋𐎌𐎍𐎎𐎏𐎐𐎑𐎒𐎓𐎔𐎕𐎖𐎗𐎘𐎙𐎚𐎛𐎜𐎝𐎞𐎟𐎠𐎡𐎢𐎣𐎤𐎥𐎦𐎧𐎨𐎩𐎪𐎫𐎬𐎭𐎮𐎯𐎰𐎱𐎲𐎳𐎴𐎵𐎶𐎷𐎸𐎹𐎺𐎻𐎼𐎽𐎾𐎿𐏀𐏁𐏂𐏃𐏄𐏅𐏆𐏇𐏈𐏉𐏊𐏋𐏌𐏍𐏎𐏏𐏐𐏑𐏒𐏓𐏔𐏕𐏖𐏗𐏘𐏙𐏚𐏛𐏜𐏝𐏞𐏟𐏠𐏡𐏢𐏣𐏤𐏥𐏦𐏧𐏨𐏩𐏪𐏫𐏬𐏭𐏮𐏯𐏰𐏱𐏲𐏳𐏴𐏵𐏶𐏷𐏸𐏹𐏺𐏻𐏼𐏽𐏾𐏿𐐀𐐁𐐂𐐃𐐄𐐅𐐆𐐇𐐈𐐉𐐊𐐋𐐌𐐍𐐎𐐏𐐐𐐑𐐒𐐓𐐔𐐕𐐖𐐗𐐘𐐙𐐚𐐛𐐜𐐝𐐞𐐟𐐠𐐡𐐢𐐣𐐤𐐥𐐦𐐧𐐨𐐩𐐪𐐫𐐬𐐭𐐮𐐯𐐰𐐱𐐲𐐳𐐴𐐵𐐶𐐷𐐸𐐹𐐺𐐻𐐼𐐽𐐾𐐿𐑀𐑁𐑂𐑃𐑄𐑅𐑆𐑇𐑈𐑉𐑊𐑋𐑌𐑍𐑎𐑏𐑐𐑑𐑒𐑓𐑔𐑕𐑖𐑗𐑘𐑙𐑚𐑛𐑜𐑝𐑞𐑟𐑠𐑡𐑢𐑣𐑤𐑥𐑦𐑧𐑨𐑩𐑪𐑫𐑬𐑭𐑮𐑯𐑰𐑱𐑲𐑳𐑴𐑵𐑶𐑷𐑸𐑹𐑺𐑻𐑼𐑽𐑾𐑿𐒀𐒁𐒂𐒃𐒄𐒅𐒆𐒇𐒈𐒉𐒊𐒋𐒌𐒍𐒎𐒏𐒐𐒑𐒒𐒓𐒔𐒕𐒖𐒗𐒘𐒙𐒚𐒛𐒜𐒝𐒞𐒟𐒠𐒡𐒢𐒣𐒤𐒥𐒦𐒧𐒨𐒩𐒪𐒫𐒬𐒭𐒮𐒯𐒰𐒱𐒲𐒳𐒴𐒵𐒶𐒷𐒸𐒹𐒺𐒻𐒼𐒽𐒾𐒿𐓀𐓁𐓂𐓃𐓄𐓅𐓆𐓇𐓈𐓉𐓊𐓋𐓌𐓍𐓎𐓏𐓐𐓑𐓒𐓓𐓔𐓕𐓖𐓗𐓘𐓙𐓚𐓛𐓜𐓝𐓞𐓟𐓠𐓡𐓢𐓣𐓤𐓥𐓦𐓧𐓨𐓩𐓪𐓫𐓬𐓭𐓮𐓯𐓰𐓱𐓲𐓳𐓴𐓵𐓶𐓷𐓸𐓹𐓺𐓻𐓼𐓽𐓾𐓿𐔀𐔁𐔂𐔃𐔄𐔅𐔆𐔇𐔈𐔉𐔊𐔋𐔌𐔍𐔎𐔏𐔐𐔑𐔒𐔓𐔔𐔕𐔖𐔗𐔘𐔙𐔚𐔛𐔜𐔝𐔞𐔟𐔠𐔡𐔢𐔣𐔤𐔥𐔦𐔧𐔨𐔩𐔪𐔫𐔬𐔭𐔮𐔯𐔰𐔱𐔲𐔳𐔴𐔵𐔶𐔷𐔸𐔹𐔺𐔻𐔼𐔽𐔾𐔿𐕀𐕁𐕂𐕃𐕄𐕅𐕆𐕇𐕈𐕉𐕊𐕋𐕌𐕍𐕎𐕏𐕐𐕑𐕒𐕓𐕔𐕕𐕖𐕗𐕘𐕙𐕚𐕛𐕜𐕝𐕞𐕟𐕠𐕡𐕢𐕣𐕤𐕥𐕦𐕧𐕨𐕩𐕪𐕫𐕬𐕭𐕮𐕯𐕰𐕱𐕲𐕳𐕴𐕵𐕶𐕷𐕸𐕹𐕺𐕻𐕼𐕽𐕾𐕿𐖀𐖁𐖂𐖃𐖄𐖅𐖆𐖇𐖈𐖉𐖊𐖋𐖌𐖍𐖎𐖏𐖐𐖑𐖒𐖓𐖔𐖕𐖖𐖗𐖘𐖙𐖚𐖛𐖜𐖝𐖞𐖟𐖠𐖡𐖢𐖣𐖤𐖥𐖦𐖧𐖨𐖩𐖪𐖫𐖬𐖭𐖮𐖯𐖰𐖱𐖲𐖳𐖴𐖵𐖶𐖷𐖸𐖹𐖺𐖻𐖼𐖽𐖾𐖿𐗀𐗁𐗂𐗃𐗄𐗅𐗆𐗇𐗈𐗉𐗊𐗋𐗌𐗍𐗎𐗏𐗐𐗑𐗒𐗓𐗔𐗕𐗖𐗗𐗘𐗙𐗚𐗛𐗜𐗝𐗞𐗟𐗠𐗡𐗢𐗣𐗤𐗥𐗦𐗧𐗨𐗩𐗪𐗫𐗬𐗭𐗮𐗯𐗰𐗱𐗲𐗳𐗴𐗵𐗶𐗷𐗸𐗹𐗺𐗻𐗼𐗽𐗾𐗿𐘀𐘁𐘂𐘃𐘄𐘅𐘆𐘇𐘈𐘉𐘊𐘋𐘌𐘍𐘎𐘏𐘐𐘑𐘒𐘓𐘔𐘕𐘖𐘗𐘘𐘙𐘚𐘛𐘜𐘝𐘞𐘟𐘠𐘡𐘢𐘣𐘤𐘥𐘦𐘧𐘨𐘩𐘪𐘫𐘬𐘭𐘮𐘯𐘰𐘱𐘲𐘳𐘴𐘵𐘶𐘷𐘸𐘹𐘺𐘻𐘼𐘽𐘾𐘿𐙀𐙁𐙂𐙃𐙄𐙅𐙆𐙇𐙈𐙉𐙊𐙋𐙌𐙍𐙎𐙏𐙐𐙑𐙒𐙓𐙔𐙕𐙖𐙗𐙘𐙙𐙚𐙛𐙜𐙝𐙞𐙟𐙠𐙡𐙢𐙣𐙤𐙥𐙦𐙧𐙨𐙩𐙪𐙫𐙬𐙭𐙮𐙯𐙰𐙱𐙲𐙳𐙴𐙵𐙶𐙷𐙸𐙹𐙺𐙻𐙼𐙽𐙾𐙿𐚀𐚁𐚂𐚃𐚄𐚅𐚆𐚇𐚈𐚉𐚊𐚋𐚌𐚍𐚎𐚏𐚐𐚑𐚒𐚓𐚔𐚕𐚖𐚗𐚘𐚙𐚚𐚛𐚜𐚝𐚞𐚟𐚠𐚡𐚢𐚣𐚤𐚥𐚦𐚧𐚨𐚩𐚪𐚫𐚬𐚭𐚮𐚯𐚰𐚱𐚲𐚳𐚴𐚵𐚶𐚷𐚸𐚹𐚺𐚻𐚼𐚽𐚾𐚿𐛀𐛁𐛂𐛃𐛄𐛅𐛆𐛇𐛈𐛉𐛊𐛋𐛌𐛍𐛎𐛏𐛐𐛑𐛒𐛓𐛔𐛕𐛖𐛗𐛘𐛙𐛚𐛛𐛜𐛝𐛞𐛟𐛠𐛡𐛢𐛣𐛤𐛥𐛦𐛧𐛨𐛩𐛪𐛫𐛬𐛭𐛮𐛯𐛰𐛱𐛲𐛳𐛴𐛵𐛶𐛷𐛸𐛹𐛺𐛻𐛼𐛽𐛾𐛿𐜀𐜁𐜂𐜃𐜄𐜅𐜆𐜇𐜈𐜉𐜊𐜋𐜌𐜍𐜎𐜏𐜐𐜑𐜒𐜓𐜔𐜕𐜖𐜗𐜘𐜙𐜚𐜛𐜜𐜝𐜞𐜟𐜠𐜡𐜢𐜣𐜤𐜥𐜦𐜧𐜨𐜩𐜪𐜫𐜬𐜭𐜮𐜯𐜰𐜱𐜲𐜳𐜴𐜵𐜶𐜷𐜸𐜹𐜺𐜻𐜼𐜽𐜾𐜿𐝀𐝁𐝂𐝃𐝄𐝅𐝆𐝇𐝈𐝉𐝊𐝋𐝌𐝍𐝎𐝏𐝐𐝑𐝒𐝓𐝔𐝕𐝖𐝗𐝘𐝙𐝚𐝛𐝜𐝝𐝞𐝟𐝠𐝡𐝢𐝣𐝤𐝥𐝦𐝧𐝨𐝩𐝪𐝫𐝬𐝭𐝮𐝯𐝰𐝱𐝲𐝳𐝴𐝵𐝶𐝷𐝸𐝹𐝺𐝻𐝼𐝽𐝾𐝿𐞀𐞁𐞂𐞃𐞄𐞅𐞆𐞇𐞈𐞉𐞊𐞋𐞌𐞍𐞎𐞏𐞐𐞑𐞒𐞓𐞔𐞕𐞖𐞗𐞘𐞙𐞚𐞛𐞜𐞝𐞞𐞟𐞠𐞡𐞢𐞣𐞤𐞥𐞦𐞧𐞨𐞩𐞪𐞫𐞬𐞭𐞮𐞯𐞰𐞱𐞲𐞳𐞴𐞵𐞶𐞷𐞸𐞹𐞺𐞻𐞼𐞽𐞾𐞿𐟀𐟁𐟂𐟃𐟄𐟅𐟆𐟇𐟈𐟉𐟊𐟋𐟌𐟍𐟎𐟏𐟐𐟑𐟒𐟓𐟔𐟕𐟖𐟗𐟘𐟙𐟚𐟛𐟜𐟝𐟞𐟟𐟠𐟡𐟢𐟣𐟤𐟥𐟦𐟧𐟨𐟩𐟪𐟫𐟬𐟭𐟮𐟯𐟰𐟱𐟲𐟳𐟴𐟵𐟶𐟷𐟸𐟹𐟺𐟻𐟼𐟽𐟾𐟿𐠀𐠁𐠂𐠃𐠄𐠅𐠆𐠇𐠈𐠉𐠊𐠋𐠌𐠍𐠎𐠏𐠐𐠑𐠒𐠓𐠔𐠕𐠖𐠗𐠘𐠙𐠚𐠛𐠜𐠝𐠞𐠟𐠠𐠡𐠢𐠣𐠤𐠥𐠦𐠧𐠨𐠩𐠪𐠫𐠬𐠭𐠮𐠯𐠰𐠱𐠲𐠳𐠴𐠵𐠶𐠷𐠸𐠹𐠺𐠻𐠼𐠽𐠾𐠿𐡀𐡁𐡂𐡃𐡄𐡅𐡆𐡇𐡈𐡉𐡊𐡋𐡌𐡍𐡎𐡏𐡐𐡑𐡒𐡓𐡔𐡕𐡖𐡗𐡘𐡙𐡚𐡛𐡜𐡝𐡞𐡟𐡠𐡡𐡢𐡣𐡤𐡥𐡦𐡧𐡨𐡩𐡪𐡫𐡬𐡭𐡮𐡯𐡰𐡱𐡲𐡳𐡴𐡵𐡶𐡷𐡸𐡹𐡺𐡻𐡼𐡽𐡾𐡿𐢀𐢁𐢂𐢃𐢄𐢅𐢆𐢇𐢈𐢉𐢊𐢋𐢌𐢍𐢎𐢏𐢐𐢑𐢒𐢓𐢔𐢕𐢖𐢗𐢘𐢙𐢚𐢛𐢜𐢝𐢞𐢟𐢠𐢡𐢢𐢣𐢤𐢥𐢦𐢧𐢨𐢩𐢪𐢫𐢬𐢭𐢮𐢯𐢰𐢱𐢲𐢳𐢴𐢵𐢶𐢷𐢸𐢹𐢺𐢻𐢼𐢽𐢾𐢿𐣀𐣁𐣂𐣃𐣄𐣅𐣆𐣇𐣈𐣉𐣊𐣋𐣌𐣍𐣎𐣏𐣐𐣑𐣒𐣓𐣔𐣕𐣖𐣗𐣘𐣙𐣚𐣛𐣜𐣝𐣞𐣟𐣠𐣡𐣢𐣣𐣤𐣥𐣦𐣧𐣨𐣩𐣪𐣫𐣬𐣭𐣮𐣯𐣰𐣱𐣲𐣳𐣴𐣵𐣶𐣷𐣸𐣹𐣺𐣻𐣼𐣽𐣾𐣿𐤀𐤁𐤂𐤃𐤄𐤅𐤆𐤇𐤈𐤉𐤊𐤋𐤌𐤍𐤎𐤏𐤐𐤑𐤒𐤓𐤔𐤕𐤖𐤗𐤘𐤙𐤚𐤛𐤜𐤝𐤞𐤟𐤠𐤡𐤢𐤣𐤤𐤥𐤦𐤧𐤨𐤩𐤪𐤫𐤬𐤭𐤮𐤯𐤰𐤱𐤲𐤳𐤴𐤵𐤶𐤷𐤸𐤹𐤺𐤻𐤼𐤽𐤾𐤿𐥀𐥁𐥂𐥃𐥄𐥅𐥆𐥇𐥈𐥉𐥊𐥋𐥌𐥍𐥎𐥏𐥐𐥑𐥒𐥓𐥔𐥕𐥖𐥗𐥘𐥙𐥚𐥛𐥜𐥝𐥞𐥟𐥠𐥡𐥢𐥣𐥤𐥥𐥦𐥧𐥨𐥩𐥪𐥫𐥬𐥭𐥮𐥯𐥰𐥱𐥲𐥳𐥴𐥵𐥶𐥷𐥸𐥹𐥺𐥻𐥼𐥽𐥾𐥿𐦀𐦁𐦂𐦃𐦄𐦅𐦆𐦇𐦈𐦉𐦊𐦋𐦌𐦍𐦎𐦏𐦐𐦑𐦒𐦓𐦔𐦕𐦖𐦗𐦘𐦙𐦚𐦛𐦜𐦝𐦞𐦟𐦠𐦡𐦢𐦣𐦤𐦥𐦦𐦧𐦨𐦩𐦪𐦫𐦬𐦭𐦮𐦯𐦰𐦱𐦲𐦳𐦴𐦵𐦶𐦷𐦸𐦹𐦺𐦻𐦼𐦽𐦾𐦿𐧀𐧁𐧂𐧃𐧄𐧅𐧆𐧇𐧈𐧉𐧊𐧋𐧌𐧍𐧎𐧏𐧐𐧑𐧒𐧓𐧔𐧕𐧖𐧗𐧘𐧙𐧚𐧛𐧜𐧝𐧞𐧟𐧠𐧡𐧢𐧣𐧤𐧥𐧦𐧧𐧨𐧩𐧪𐧫𐧬𐧭𐧮𐧯𐧰𐧱𐧲𐧳𐧴𐧵𐧶𐧷𐧸𐧹𐧺𐧻𐧼𐧽𐧾𐧿𐨀𐨁𐨂𐨃𐨄𐨅𐨆𐨇𐨈𐨉𐨊𐨋𐨌𐨍𐨎𐨏𐨐𐨑𐨒𐨓𐨔𐨕𐨖𐨗𐨘𐨙𐨚𐨛𐨜𐨝𐨞𐨟𐨠𐨡𐨢𐨣𐨤𐨥𐨦𐨧𐨨𐨩𐨪𐨫𐨬𐨭𐨮𐨯𐨰𐨱𐨲𐨳𐨴𐨵𐨶𐨷𐨹𐨺𐨸𐨻𐨼𐨽𐨾𐨿𐩀𐩁𐩂𐩃𐩄𐩅𐩆𐩇𐩈𐩉𐩊𐩋𐩌𐩍𐩎𐩏𐩐𐩑𐩒𐩓𐩔𐩕𐩖𐩗𐩘𐩙𐩚𐩛𐩜𐩝𐩞𐩟𐩠𐩡𐩢𐩣𐩤𐩥𐩦𐩧𐩨𐩩𐩪𐩫𐩬𐩭𐩮𐩯𐩰𐩱𐩲𐩳𐩴𐩵𐩶𐩷𐩸𐩹𐩺𐩻𐩼𐩽𐩾𐩿𐪀𐪁𐪂𐪃𐪄𐪅𐪆𐪇𐪈𐪉𐪊𐪋𐪌𐪍𐪎𐪏𐪐𐪑𐪒𐪓𐪔𐪕𐪖𐪗𐪘𐪙𐪚𐪛𐪜𐪝𐪞𐪟𐪠𐪡𐪢𐪣𐪤𐪥𐪦𐪧𐪨𐪩𐪪𐪫𐪬𐪭𐪮𐪯𐪰𐪱𐪲𐪳𐪴𐪵𐪶𐪷𐪸𐪹𐪺𐪻𐪼𐪽𐪾𐪿𐫀𐫁𐫂𐫃𐫄𐫅𐫆𐫇𐫈𐫉𐫊𐫋𐫌𐫍𐫎𐫏𐫐𐫑𐫒𐫓𐫔𐫕𐫖𐫗𐫘𐫙𐫚𐫛𐫜𐫝𐫞𐫟𐫠𐫡𐫢𐫣𐫤𐫦𐫥𐫧𐫨𐫩𐫪𐫫𐫬𐫭𐫮𐫯𐫰𐫱𐫲𐫳𐫴𐫵𐫶𐫷𐫸𐫹𐫺𐫻𐫼𐫽𐫾𐫿𐬀𐬁𐬂𐬃𐬄𐬅𐬆𐬇𐬈𐬉𐬊𐬋𐬌𐬍𐬎𐬏𐬐𐬑𐬒𐬓𐬔𐬕𐬖𐬗𐬘𐬙𐬚𐬛𐬜𐬝𐬞𐬟𐬠𐬡𐬢𐬣𐬤𐬥𐬦𐬧𐬨𐬩𐬪𐬫𐬬𐬭𐬮𐬯𐬰𐬱𐬲𐬳𐬴𐬵𐬶𐬷𐬸𐬹𐬺𐬻𐬼𐬽𐬾𐬿𐭀𐭁𐭂𐭃𐭄𐭅𐭆𐭇𐭈𐭉𐭊𐭋𐭌𐭍𐭎𐭏𐭐𐭑𐭒𐭓𐭔𐭕𐭖𐭗𐭘𐭙𐭚𐭛𐭜𐭝𐭞𐭟𐭠𐭡𐭢𐭣𐭤𐭥𐭦𐭧𐭨𐭩𐭪𐭫𐭬𐭭𐭮𐭯𐭰𐭱𐭲𐭳𐭴𐭵𐭶𐭷𐭸𐭹𐭺𐭻𐭼𐭽𐭾𐭿𐮀𐮁𐮂𐮃𐮄𐮅𐮆𐮇𐮈𐮉𐮊𐮋𐮌𐮍𐮎𐮏𐮐𐮑𐮒𐮓𐮔𐮕𐮖𐮗𐮘𐮙𐮚𐮛𐮜𐮝𐮞𐮟𐮠𐮡𐮢𐮣𐮤𐮥𐮦𐮧𐮨𐮩𐮪𐮫𐮬𐮭𐮮𐮯𐮰𐮱𐮲𐮳𐮴𐮵𐮶𐮷𐮸𐮹𐮺𐮻𐮼𐮽𐮾𐮿𐯀𐯁𐯂𐯃𐯄𐯅𐯆𐯇𐯈𐯉𐯊𐯋𐯌𐯍𐯎𐯏𐯐𐯑𐯒𐯓𐯔𐯕𐯖𐯗𐯘𐯙𐯚𐯛𐯜𐯝𐯞𐯟𐯠𐯡𐯢𐯣𐯤𐯥𐯦𐯧𐯨𐯩𐯪𐯫𐯬𐯭𐯮𐯯𐯰𐯱𐯲𐯳𐯴𐯵𐯶𐯷𐯸𐯹𐯺𐯻𐯼𐯽𐯾𐯿𐰀𐰁𐰂𐰃𐰄𐰅𐰆𐰇𐰈𐰉𐰊𐰋𐰌𐰍𐰎𐰏𐰐𐰑𐰒𐰓𐰔𐰕𐰖𐰗𐰘𐰙𐰚𐰛𐰜𐰝𐰞𐰟𐰠𐰡𐰢𐰣𐰤𐰥𐰦𐰧𐰨𐰩𐰪𐰫𐰬𐰭𐰮𐰯𐰰𐰱𐰲𐰳𐰴𐰵𐰶𐰷𐰸𐰹𐰺𐰻𐰼𐰽𐰾𐰿𐱀𐱁𐱂𐱃𐱄𐱅𐱆𐱇𐱈𐱉𐱊𐱋𐱌𐱍𐱎𐱏𐱐𐱑𐱒𐱓𐱔𐱕𐱖𐱗𐱘𐱙𐱚𐱛𐱜𐱝𐱞𐱟𐱠𐱡𐱢𐱣𐱤𐱥𐱦𐱧𐱨𐱩𐱪𐱫𐱬𐱭𐱮𐱯𐱰𐱱𐱲𐱳𐱴𐱵𐱶𐱷𐱸𐱹𐱺𐱻𐱼𐱽𐱾𐱿𐲀𐲁𐲂𐲃𐲄𐲅𐲆𐲇𐲈𐲉𐲊𐲋𐲌𐲍𐲎𐲏𐲐𐲑𐲒𐲓𐲔𐲕𐲖𐲗𐲘𐲙𐲚𐲛𐲜𐲝𐲞𐲟𐲠𐲡𐲢𐲣𐲤𐲥𐲦𐲧𐲨𐲩𐲪𐲫𐲬𐲭𐲮𐲯𐲰𐲱𐲲𐲳𐲴𐲵𐲶𐲷𐲸𐲹𐲺𐲻𐲼𐲽𐲾𐲿𐳀𐳁𐳂𐳃𐳄𐳅𐳆𐳇𐳈𐳉𐳊𐳋𐳌𐳍𐳎𐳏𐳐𐳑𐳒𐳓𐳔𐳕𐳖𐳗𐳘𐳙𐳚𐳛𐳜𐳝𐳞𐳟𐳠𐳡𐳢𐳣𐳤𐳥𐳦𐳧𐳨𐳩𐳪𐳫𐳬𐳭𐳮𐳯𐳰𐳱𐳲𐳳𐳴𐳵𐳶𐳷𐳸𐳹𐳺𐳻𐳼𐳽𐳾𐳿𐴀𐴁𐴂𐴃𐴄𐴅𐴆𐴇𐴈𐴉𐴊𐴋𐴌𐴍𐴎𐴏𐴐𐴑𐴒𐴓𐴔𐴕𐴖𐴗𐴘𐴙𐴚𐴛𐴜𐴝𐴞𐴟𐴠𐴡𐴢𐴣𐴤𐴥𐴦𐴧𐴨𐴩𐴪𐴫𐴬𐴭𐴮𐴯𐴰𐴱𐴲𐴳𐴴𐴵𐴶𐴷𐴸𐴹𐴺𐴻𐴼𐴽𐴾𐴿𐵀𐵁𐵂𐵃𐵄𐵅𐵆𐵇𐵈𐵉𐵊𐵋𐵌𐵍𐵎𐵏𐵐𐵑𐵒𐵓𐵔𐵕𐵖𐵗𐵘𐵙𐵚𐵛𐵜𐵝𐵞𐵟𐵠𐵡𐵢𐵣𐵤𐵥𐵦𐵧𐵨𐵩𐵪𐵫𐵬𐵭𐵮𐵯𐵰𐵱𐵲𐵳𐵴𐵵𐵶𐵷𐵸𐵹𐵺𐵻𐵼𐵽𐵾𐵿𐶀

No.	Wt.	Metal Size.	Obverse.	Reverse.
			<b>ΒΑΣΙΛΕΩΣ ΣΩΤΗ- ΡΟΣ ΜΕΝΑΝΔΡΟΥ</b> Bust of the king r., diad.	𐤠𐤡𐤢.𐤠𐤡𐤢.𐤠𐤡𐤢 (Mākūrajasa 𐤠𐤡𐤢 trādātasa Mena- drāsa). Pallas l., holding in l. hand agēia, and with r. hurling thunderbolt.
12	37·8	AR·7	(king helmeted).	to r., ☉.
13	37·8	AR·7	"	" "
14	39·	AR·7		[L. O. C.]
15	34·8	AR·65		to l., ☉.
16	33·6	AR·7		to r., "
17	37·6	AR·7		" ☉.
18	37·4	AR·7		" ☉.
19	38·	AR·65		" ☉.
20	34·1	AR·75		to l., ☉.
21	37·5	AR·65		" " ; to r., ☉.
22	36·	AR·65		" ☉.
23	37·7	AR·65		" " [L. O. C.]
24	37·3	AR·65		" ☉.
25	37·	AR·7		to l., " [17, xi. 10.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<p>ΒΑΣΙΛΕΥΣ ΣΩΤΗ- ΡΟΣ ΜΕΝΑΝΔΡΟΥ Bust of the king r., diad.</p>	<p>𐎲𐎠𐎼𐎿.𐎲𐎡𐎴𐎡𐎹.𐎲𐎠𐎹 (Mūhūrajasa 𐎲.𐎠𐎹𐎶 trālatasa Mena- drasa). Pallas l., holding in l. hand aegis, and with r. hurling thunderbolt.</p>
26	36.3	AR 65		to l., 𐎲; to r., Γ. [L. O. C.]
27	39.	AR 7		" " " E.
28	38.3	AR 7		" Σ; " 𐎲.
29	38.	AR 75		to r., 𐎲.
30	38.7	AR 7		" "
<p>Same inser. Bust of the king l., wearing aegis and thrusting with spear.</p>				Similar.
31	36.6	AR 7		to l., 𐎲.
32	37.1	AR 65		to r., 𐎲.
33	37.3	AR 65		" 𐎲.
34	37.8	AR 7		" 𐎲.
35	38.	AR 75		" 𐎲.

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<b>ΒΑΣΙΛΕΩΣ ΣΩΤΗ- ΡΟΣ ΜΕΝΑΝΔΡΟΥ</b> Bust of the king l., wear- ing aegis and thrusting with spear.	𐤁𐤁𐤁𐤁𐤁𐤁𐤁𐤁𐤁𐤁𐤁𐤁 (Māhārājaśa 𐤁𐤁𐤁𐤁𐤁 trālatasa Men- drāsa). Pallas r., holding in l. hand aegis, and with r. hurling thunderbolt.
36	38.2	AR 7		to l., ☉.
37	38.	AR 7		" "
38	37.8	AR 65		" M.
39	37.7	AR 7		to r., ☉. [I. O. C. Pl. xi. 11.]
40	38.2	AR 65		" "
41	37.8	AR 65		to l., M.
42	37.9	AR 7		" M.
43	38.2	AR 65		" M.

(β) Bronze; square; with portrait.





**ΒΑΣΙΛΕΩΣ ΣΩΤΗ-  
ΡΟΣ ΜΕΝΑΝΔΡΟΥ**  
 Bust of the king l.,  
 diad., wearing aegis  
 and thrusting with  
 spear.

𐤁𐤁𐤁𐤁𐤁𐤁𐤁𐤁𐤁𐤁𐤁 (Māhārājaśa  
 𐤁𐤁𐤁𐤁𐤁 trālatasa Men-  
 drāsa). Pallas r., holding in l.  
 hand aegis, and with r. hurling  
 thunderbolt.

44		Æ 85		to r., ☉.
45		Æ 8		" "
46		Æ 9		" E. [I. O. C. Pl. xi. 12.]



No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<b>ΒΑΣΙΛΕΩΣ ΣΩΤΗ- ΡΟΣ ΜΕΝΑΝΔΡΟΥ</b> Bust of Pallas r., wear- ing crested helmet.	<b>Ρ.ΥΩ ΠΥΡΡΥ ΠΑΡ.~Υ</b> ( <i>Mahārajasa trādatasa Mena- drūsa</i> ). Round buckler; Gorgon- head in the midst.
59		Æ 85		below, <b>Μ</b> . [Pl. xii. 2.]
60		Æ 85		.. <b>Μ</b> .
61		Æ 85		to l., <b>Μ</b> .
62		Æ 9		.. " [I. O. C. Pl. xii. 3.]
			Similar.	Same inscr. Owl r.
63		Æ 8		to r., <b>Κ</b> . [I. O. C. Pl. xii. 4.]
			(8) Bronze; square; Apolline type.	
			<b>ΒΑΣΙΛΕΩΣ ΣΩΤΗ- ΡΟΣ ΜΕΝΑΝΔΡΟΥ</b> Ox-head, facing.	<b>Ρ.ΥΩ ΠΥΡΡΥ ΠΑΡ.~Υ</b> ( <i>Mahārajasa trādatasa Mena- drūsa</i> ). Tripod-kebas.
64		Æ 9		to l., <b>Κ</b> .
65		Æ 9		" "
66		Æ 9		.. <b>Υ</b> ; to r., <b>Κ</b> . [Pl. xii. 5.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
(ε) Bronze; square; Herakleian types.				
			ΒΑΣΙΛΕΩΣ ΣΩΤΗ- ΡΟΣ ΜΕΝΑΝΔΡΟΥ Elephant's head r., bell round neck.	Υ.Υ.ΩΩ ΥΥΥ.Υ ΥΣΥ.~Υ (Māhārājasa trūdātasa Mena- drāsa). Club upwards.
67		Æ·65		to L,  ; to r., A.
68		Æ·55		" " " " [Pl. XII. 6.]
69		Æ·6		" A; "  .
70		Æ·6		" " " " [I. O. C.]
71		Æ·55	below, A.	to r., Υ.
72		Æ·55	" O.	"  .
(ζ) Bronze; square; type, wheel.				
			ΒΑΣΙΛΕΩΣ ΣΩΤΗ- ΡΟΣ ΜΕΝΑΝΔΡΟΥ Wheel.	Υ.Υ.ΩΩ ΥΥΥ.Υ ΥΣΥ.~Υ (Māhārājasa trūdātasa Mena- drāsa). Palm.
73		Æ·5		to r., mon. [I. O. C. Pl. XII. 7.]
(η) Bronze; square; with title δεικνός.				
			ΒΑΣΙΛΕΩΣ ΔΙΚΑΙ- ΟΥ ΜΕΝΑΝΔΡΟΥ Pallas l., holds patera? and spear, against which leans shield.	Υ.Υ.ΩΩ ΥΥΨΣ ΥΣΥ.~Υ (Māhārājasa dhramikasa Mena- drāsa) Maneless Indian lion l.
74		Æ·85		below,  .

No.	Wt.	Metal. Size.	Obverse.	Reverse.
EPANDER.				
(a) Bronze.				
1		Æ 9	<p>ΒΑΣΙΛΕΩΣ ΝΙΚΗ- ΦΟΡΟΥ ΕΠΑΝΔΡΟΥ</p> <p>Nike advancing r.; holds wreath and palm.</p>	<p>𐤀.𐤆𐤏𐤕𐤕 𐤕𐤏𐤕𐤕𐤕𐤕 𐤕𐤏𐤕𐤕𐤕𐤕</p> <p>(<i>Maharajasa jagadharasa Epā-</i> <i>drāsa</i>). Indian bull r.</p> <p>below, Ⲙ Ⲛ. [L. O. C. Pl. xii 8.]</p>
DIONYSIUS.				
(a) Silver.				
1	38.	AR 7	<p>ΒΑΣΙΛΕΩΣ ΣΩΤΗ- ΡΟΣ ΔΙΟΝΥΣΙΟΥ</p> <p>Bust of the king r., diad.</p>	<p>𐤕𐤏𐤕𐤕𐤕𐤕 𐤕𐤏𐤕𐤕𐤕𐤕𐤕 (Maharajasa 𐤕𐤏𐤕𐤕𐤕𐤕𐤕 tradatasa <i>Dianisiyasa</i>). Pallas l.; holding in l. hand, aegis; and with r., hurling thunderbolt.</p> <p>to r., ⲕ. [L. O. C. Pl. xii 9.]</p>
(β) Bronze.				
2		Æ 85	<p>ΒΑΣΙΛΕΩΣ ΣΩΤΗ- ΡΟΣ ΔΙΟΝΥΣΙΟΥ</p> <p>Apollon., clad in chlamys and boots; holds in both hands an arrow; a quiver at his back.</p>	<p>𐤕𐤏𐤕𐤕𐤕𐤕𐤕 𐤕𐤏𐤕𐤕𐤕𐤕𐤕 𐤕𐤏𐤕𐤕𐤕𐤕𐤕</p> <p>(<i>Maharajasa tradatasa Dianisi-</i> <i>yasa</i>). Tripod.</p> <p>to l., 𐤕; to r., 𐤕. [L. O. C.]</p>
3		Æ 8		mons. obscure.

No.	Wt.	Metal Size.	Obverse.	Reverse.
ZOILUS.				
(a) <i>Silver; with title δικάσις.</i>				
			ΒΑΣΙΛΕΩΣ ΔΙΚΑΙ- ΟΥ ΙΩΙΛΟΥ Bust of the king r., diad.	𐎧𐎡𐎴𐎡𐎴 𐎧𐎡𐎴𐎡𐎴 𐎧𐎡𐎴𐎡𐎴 (Māhārājasa dhramikasa Jhoī- lasa). Herakles facing, crowned with ivy; holds in r. hand, wreath; in l., club and lion's skin.
1	37.4	AR.7		to l., 𐎧. [Pl. XII. 10.]
2	38.5	AR.65		" 𐎧. [I. O. C.]
(β) <i>Silver; with title σωτήρ.</i>				
			ΒΑΣΙΛΕΩΣ ΣΩΤΗ- ΡΟΣ ΙΩΙΛΟΥ Bust of the king r., diad.	𐎧𐎡𐎴𐎡𐎴 𐎧𐎡𐎴𐎡𐎴 (Maharajasa 𐎧𐎡𐎴𐎡𐎴 tradatasa Jhoīlasa). Pallas l.; holding in l. hand, aegis; and with r., hurl- ing thunderbolt.
3	34.8	AR.65		to l., 𐎧; to r., 𐎧. [I. O. C. Pl. XII. 11.]
4	37.4	AR.65	Z in inscr.	" 𐎧; " " [I. O. C.]
5	37.6	AR.8	"	" 𐎧; " " "
6	36.6	AR.6	"	" 𐎧; " 𐎧𐎡𐎴𐎡𐎴.
7	34.4	AR.7	"	" " ~.
8	38.2	AR.7	"	" 𐎧. [I. O. C.]

No.	Wt.	Metal. Sine.	Obverse.	Reverse.
(γ) <i>Bronze; round.</i>				
9	Æ 1·25		ΒΑΣΙΛΕΥΣ ΣΩΤΗ- ΡΟΣ ΙΩΙΛΟΥ Apollo r., clad in chlamys and boots; holds in both hands an arrow; a quiver at his back; in field L, small elephant.	𐌲𐌶𐌶𐌶 𐌲𐌸𐌶𐌺𐌺 (Maharajasa tradatasa Jhoilasa). Tripod.
			Elephant r.	to L, 𐌸; to r, 𐌶. [Pl. XII. 12.]
10	Æ 75			Similar.
				to L, 𐌶; to r, 𐌶. (double-struck).
(δ) <i>Bronze; square.</i>				
11	Æ 1		ΒΑΣΙΛΕΥΣ ΣΩΤΗ- ΡΟΣ ΙΩΙΛΟΥ Apollo r., clad in chlamys and boots; holds in both hands an arrow; a quiver at his back.	𐌲𐌶𐌶𐌶 𐌲𐌸𐌶𐌺𐌺 𐌲𐌸𐌶𐌺𐌺 (Maharajasa tradatasa Jhoilasa). Tripod.
			to L, 𐌸.	to L, 𐌸; to r, 𐌶. [Pl. XII. 13.]



No.	Wt.	Metal. Size.	Obverse.	Reverse.
ANTIMACHUS II., NICEPHORUS.				
(a) <i>Silver.</i>				
			ΒΑΣΙΛΕΥΣ ΝΙΚΗ- ΦΟΡΟΥ ANTIMA- ΧΟΥ Nike l.; holds palm and wreath.	ΥΣΥΗΒ ΥΓΓΛΥ ΥΣΓ.~Υ ( <i>Mūhārajasa jayadharasa Anti- mākhasa</i> ). The king, wearing causia, diadem, and chlamys, on horseback r.
1	37.6	AR 65	to l., Φ.	[Pl. xiii. 3.]
2	37.5	AR 65	" "	
3	37.8	AR 65	" Κ.	
4	38.4	AR 7	" "	[I. O. C.]
5	37.8	AR 7	" Μ.	
6	37.5	AR 6	" "	
7	37.8	AR 65	" "	[I. O. C.]
8	38.3	AR 65	" Μ.	
9	36.7	AR 7	" "	
(β) <i>Bronze; square.</i>				
			ΒΑΣΙΛΕΥΣ ΝΙΚΗ- ΦΟΡΟΥ ANTIMA- ΧΟΥ Aegis: in the midst, Gorgon-head.	ΥΣΥΗΒ ΥΓΓΛΥ ΥΣΓ.~Υ ( <i>Mūhārajasa jayadharasa Anti- mākhasa</i> ). Wreath and palm.
10		Æ 8		below, Κ. [Pl. xiii. 4.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
PHILOXENUS.				
(a) <i>Silver; round.</i>				
			ΒΑΣΙΛΕΥΣ ΑΝΙΚΗ- ΤΟΥ ΦΙΛΟΞΕΝΟΥ Bust of the king r., diad.	𐎧𐎡𐎴𐎠𐎧𐎡𐎴 𐎧𐎡𐎴𐎠𐎧𐎡𐎴 𐎧𐎡𐎴𐎠𐎧𐎡𐎴 (Māhārāja apadihata <sup>s</sup> Philoxinasa). King, helmeted and diad., on horseback r.; horse prancing.
1	151.4	AR 1.05		below, Φ. (𐎧 for 𐎡 in inser.).
2	150.8	AR 1.2		" 𐎧. [Pl. XIII. 5.]
3	149.	AR 1.05	(king helmeted).	" Σ 𐎧. [Pl. XIII. 6.]
(β) <i>Silver; square.</i>				
			ΒΑΣΙΛΕΥΣ ΑΝΙΚΗ- ΤΟΥ ΦΙΛΟΞΕΝΟΥ Bust of the king r., diad.	𐎧𐎡𐎴𐎠𐎧𐎡𐎴 𐎧𐎡𐎴𐎠𐎧𐎡𐎴 𐎧𐎡𐎴𐎠𐎧𐎡𐎴 (Māhārāja apadihata <sup>s</sup> Phila <sup>s</sup> sinasa). King, helmeted and diad., on horseback r.; horse prancing.
4	36.8	AR .65		below, 𐎧. [L. O. C. Pl. XIII. 7.]
5	33.3	AR .65		" Σ 𐎧. [L. O. C.]
6	35.	AR .7		" 𐎧.
7	27.3	AR .6	(king helmeted).	" 𐎧. [L. O. C. Pl. XIII. 8.]
8	25.	AR .7	"	" 𐎧. (plated).
9	26.	AR .6	"	" 𐎧. " [L. O. C.]

\* Sometimes *h* for *l*.





No.	Wt.	Metal, Size.	Obverse.	Reverse.
			(γ) <i>Bronze; square.</i>	
			ΒΑΣΙΛΕΥΣ ΑΝΙΚΗ ΤΟΥ ΦΙΛΟΞΕΝΟΥ Sun-god, facing, radiate, clad in chiton, himation, and boots; holds in l. hand long sceptre; r. extended.	𐤀𐤁𐤁𐤁𐤁𐤁 𐤁𐤁𐤁𐤁𐤁 𐤁𐤁𐤁𐤁𐤁 (Mūhūrajasa <i>apadibataas Phila* sinasa</i> ). Nike r. ; holds wreath and palm.
10	Æ 8			to r., 𐤀. [Pl. xiii. 9.]
			Same inser. A City l.; in l. hand cornucopiae; r. extended.	Same inser. Indian bull r.
11	Æ 85		to l., 𐤀.	below; Σ.
12	Æ 8		" "	" "
13	Æ 8		" 𐤀.	" 𐤁. [I. O. C. Pl. xiii. 10.]
14	Æ 8		" "	[I. O. C.]
15	Æ 8		" "	
16	Æ 9		" mon.	" 𐤀. "
17	Æ 8		" 𐤀.	" Σ. "











\* Sometimes *to* for *ta*.

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			NICIAS.	
			(a) <i>Bronze; square.</i>	
1	Æ 8		<p>ΒΑΣΙΛΕΥΣ ΣΩΤΗ- ΡΟΣ ΝΙΚΙΟΥ Head of the king r., diad.</p>	<p>(or ΠΑΥΛΟΣ) ΠΑΥΛΟΣ ΠΑΥΛΟΣ [Σ ΠΑΥΛΟΣ] (<i>Maharajasa</i> or <i>Maharajasa tra-</i> <i>datasa Nikiasa</i>). King, diad. and wearing chlamys, on horseback r.; horse prancing.</p> <p>[Pl. XIII. 11.]</p>
2	Æ 9		<p>ΒΑΣΙΛΕΥΣ ΣΩΤΗ- ΡΟΣ ΝΙΚΙΟΥ Similar head.</p>	<p>ΠΑΥΛΟΣ ΠΑΥΛΟΣ ΠΑΥΛΟΣ (<i>Maharajasa tradatasa Nikiasa</i>). Dolphin twined round anchor.</p> <p>[Pl. XIII. 12.]</p>



No.	Wt.	Metal. Size.	Obverse.	Reverse.
HIPPOSTRATUS.				
(a) <i>Silver; type, City.</i>				
			ΒΑΣΙΛΕΩΣ ΣΩΤΗ- ΡΟΣ ΙΠΠΟΣΤΡΑ- ΤΟΥ Bust of the king r., diad.	𐤁𐤓𐤕𐤕𐤕𐤕𐤕𐤕𐤕 (Maharajasa 𐤁𐤓𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕 tradatasa Hipe- stratasa). City l., wearing mo- dius; holds in l. hand, cornucop- iae; r. advanced.
1	146	AR 1-1		to l., 𐤁; to r., 𐤕. [Pl. xiv. 1.]
2	147-7	AR 1-15		" " " "
(β) <i>Silver; type, King on horseback.</i>				
			ΒΑΣΙΛΕΩΣ ΜΕΓΑ- ΛΟΥ ΣΩΤΗΡΟΣ ΙΠΠΟΣΤΡΑΤΟΥ Bust of the king r., diad.	𐤁𐤓𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕 (Maharajasa tradatasa mahātasa 𐤁𐤓𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕 jagantasa Hippostratasa). King, diad. and helmeted, wearing chlamys, on horseback r.; horse prancing.
3	139-5	AR 1-2		below, 𐤁.
4	147	AR 1-1		to l., 𐤕; to r., 𐤕; below, 𐤕. [Pl. xiv. 2.]
5	144	AR 1-05		" " " " " 𐤕. [I. O. C.]
6	34-6	AR 75		to l., 𐤕; to r., 𐤕; below, 𐤕. [Pl. xiv. 3.]
			Similar.	Similar, horse walking.
7	143-2	AR 1-1		to l., 𐤕; to r., 𐤕; below, 𐤕. [Pl. xiv. 4.]
8	144-8	AR 1-05		" " " " " "
9	143	AR 1-1		" " " " " 𐤕. [I. O. C.]



No.	Wt.	Metal. Siv.	Obverse.	Reverse.
AMYNTAS.				
(a) <i>Silver; type, Pallas.</i>				
			<p>ΒΑΣΙΛΕΩΣ ΝΙΚΑ- ΤΟΡΟΣ ΑΜΥΝΤΟΥ</p> <p>Bust of the king r., diad., helmeted.</p>	<p>ΥΓΨΥ ΠΥΞΛΥ ΠΥΞΛΥ</p> <p>(<i>Maharajasa jayadharasa Ami- tasa</i>). Pallas l.; holding in l. hand, aegis; and with r. hurling thunderbolt.</p>
1	127.2	AR 1		to l.  . [Pl. xiv. 9.]
(β) <i>Silver; type, Zeus.</i>				
			<p>ΒΑΣΙΛΕΩΣ ΝΙΚΑ- ΤΟΡΟΣ ΑΜΥΝΤΟΥ</p> <p>Bust of the king r., diad.</p>	<p>ΥΓΨΥ ΠΥΞΛΥ ΠΥΞΛΥ</p> <p>(<i>Maharajasa jayadharasa Ami- tasa</i>). Zeus seated l. on throne; in r. hand, Nike; in l. palm and sceptre.</p>
2	33.4	AR 65		to l.  .
3	36.2	AR 65		to r., „ [I. O. C. Pl. xiv. 10.]
(γ) <i>Bronze; square.</i>				
			<p>ΒΑΣΙΛΕΩΣ ΝΙΚΑ- ΤΟΡΟΣ ΑΜΥΝΤΟΥ</p> <p>Bearded bust r., radiate, in Phrygian cap; sceptre over shoulder.</p>	<p>ΥΓΨΥ ΠΥΞΛΥ ΠΥΞΛΥ</p> <p>(<i>Maharajasa jayadharasa Ami- tasa</i>). Pallas standing l., her r. hand advanced; in her l. spear and shield.</p>
4		Æ 8		to l.  .
5		Æ 8		„  . [I. O. C. Pl. xiv. 11.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
HERMAEUS.				
(a) <i>Silver.</i>				
			ΒΑΣΙΛΕΥΣ ΣΩΤΗ- ΡΟΣ ΕΡΜΑΙΟΥ Bust of the king r., diad.	ՄԱՆՆԻ ՄԱՆՆԻ ՄԱՆՆԻ (Māhārājasa traidatasa Herama- yasa). Zeus, Laur., seated l. on throne with back; his r. hand advanced; in his l. sceptre.
1	150.7	AR 1.		to r.,  . [L. O. C. Pl. xv. 1.]
2	148.6	AR 1.		"  .
3	144.1	AR 1.		"  .
4	143.3	AR 1.		"  . [L. O. C. Pl. xv. 2.]
5	35.4	AR 65		to r.,  .
6	34.7	AR 65		" " [L. O. C.]
7	33.8	AR 65		"  .
8	33.	AR 65		" " "
9	36.	AR 65		"  .
10	36.	AR 7		"  .
11	36.5	AR 65		"  . [Pl. xv. 3.]
12	36.3	AR 7		"  . [L. O. C.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<b>ΒΑΣΙΛΕΩΣ ΣΩΤΗ- ΡΟΣ ΕΡΜΑΙΟΥ</b> Bust of the king r., diad.	<b>ΥΛΟΥΖΥΝΥΖΥΝΥ</b> <i>(Māhārājasa tradatasa Heramā- yasa)</i> . Zeus, laur., seated l. on throne with back; his r. hand advanced; in his l. sceptre.
13	32.8	AR .65		to r., M.
14	34.5	AR .6		" " [I. O. C.]
15	37.3	AR .65		to L., K <sup>p</sup> .
16	35.	AR .65		" M; to r., Δ. [I. O. C.]
17	36.3	AR .6		" " " "
18	37.5	AR .6		" ⌘.
19	50.	AR .7 (plated)		" "
			<b>ΒΑΣΙΛΕΩΣ ΣΩΤΗ- ΡΟΣ ΕΡΜΑΙΟΥ</b> Similar type.	Similar.  to L., ⌘; to r., ⌘ ς. [Pl. xv. 4.] " ⌘; " ∪.
20	140.6	AR 1.1		
21	144.6	AR 1.		
22	34.9	AR .65		to L., Δ; to r., Δ.
23	29.4	AR .65		" Δ.
			<b>ΒΑΣΙΛΕΩΣ ΣΩΤΗ- ΡΟΣ ΕΡΜΑΙΟΥ</b> Bust of the king r., diad. and helmeted.	Similar.  to L., ⌘. [Pl. xv. 5.]
24	37.7	AR .65		





No.	Wt.	Metal Size.	Obverse.	Reverse.
(β) Bronze; round; with portrait.				
			ΒΑΣΙΛΕΥΣ ΣΩΤΗ- ΡΟΣ ΕΡΜΑΙΟΥ Bust of the king r., diad.	ΞΛΥΓΛΥΒΡΥΠΥΛΥ (Maharajasa tradutasa Herama- yasa). Zeus, laur., seated l. on throne with back; his r. hand advanced; in his l., sceptre.
25	Æ 95			to l.,  ; to r., Ζ.
26	Æ 1.			" " , uncertain Indian letter. [I. O. C. Pl. xv. 6.]
27	Æ 95			" " , uncertain Indian letter.
28	Æ 85			" " " Ψ. [I. O. C.]
29	Æ 95			" " , uncertain Indian letter.
30	Æ 9			" " " Ψ. [I. O. C.]
31	Æ 95			" " " ~.
32	Æ 105			" " " "
33	Æ 1.			" " " H.
34	Æ 95			" " " "
35	Æ 95			" " " Ψ.
36	Æ 1.			" " " Σ. [I. O. C.]
37	Æ 95			"  " ~.






No.	Wt.	Metal. Size.	Obverse.	Reverse.
			ΒΑΣΙΛΕΩΣ ΣΩΤΗ- ΡΟΣ ΕΡΜΑΙΟΥ Bust of the king r., diad.	ΥΛΥΓΛΥΓΛΥΓΛΥΓΛΥ (Maharajasa tradatasa Herama- yasa). Zeus, laur., seated l. on throne with back; his r. hand advanced; in his l., sceptre.
38	Æ 9			to l., ☒; to r., γ. [I. O. C.]
39	Æ 9			" " " Δ.
40	Æ 9			" " " Ζ.
41	Æ 6			to l., ☐; to r., Ϙ.
42	Æ 6			" " " Ζ. [I. O. C.]
43	Æ 7			" " " Υ. [Pl. xv. 7.]
44	Æ 6			" ☒; " γ. [I. O. C.]
(γ) Bronze; round; ΣΥ inserted after Σ[Ω]ΤΗΡΟΣ.*				
			ΒΑΣΙΛΕΩΣ ΣΤΗ- ΡΟΣ ΣΥ ΕΡΜΑΙΟΥ Bust of the king r., diad.	ΥΛΥΓΛΥΓΛΥΓΛΥΓΛΥ (Maharajasa mahatasa Herama- yasa). Type as last, degraded.
45	Æ 8			to l., (l); to r., ☒.
46	Æ 7			" Δ "
47	Æ 8			" " "
48	Æ 75			" " "
		Similar.		Inscr. various. Nike l.; holds wreath and palm.
49	Æ 65			inscr. ΥΥΓΥΓΥΥΓΥΓΥΓΥ to r., ☒.
50	Æ 6	(obscure).		" ~ΥΥΓΥΓΥΓΥΓΥ to l., †; to r., ☒.

\* Other coins with the same obverse inscription and type, but bearing on the reverse the name of Kadphises and the type of Herakles, are described among the coins of Kadphises I., below.










No.	Wt.	Metal. Size.	Obverse.		Reverse.
			<b>RANJABALA.</b>		
			(a) Silver.		
			BACIAEI BACIAE- WC CWTHPOC PAIY Bust of the king r., diad.		ᲙᲗᲢᲚᲘᲛᲧ ᲠᲣ᲏ᲕᲁᲑᲞᲓᲔᲥ (Apratihata- chakrasa chhatrapasa Rajabulasa). Pallas l.; holding in l. hand aegis, and with r., hurling thunderbolt.
1	38·	AR ·55			to L, ᳵ; to R, ᱦ. [Pl. xv. 11.]
			Blundered inscr. Same type.	Same	ᲙᲗᲢ...ᲟᲩᲐᲃᲡᲤᲫᲭᲮᲰᲪᲝᲨᲥᲜᲬᲷ (Chha- trapasa trapasa) <i>Apra . . . chakrasa Rajabulasa)</i> Same type.
2	36·8	AR ·55			to L, ᳶ; to R, ᳾̄. [Pl. xv. 12.]
3	36·0	AR ·55	(both sides blundered).	" "	" " " "
4	36·4	AR ·55	(inset. BA MOC-CWTHPOCRA ).	" "	" " " "
5	36·	AR ·55		" "	" " (name, ᲙᲗᲢᲚᲘᲛᲧᲉᲕᲁᲑᲞᲓᲔᲥ Ranja- bulasa).
6	30·8	AR ·55		" ~;	" ᱦᱴ.
7	35·7	AR ·5		" ᳶ; (Inscr., . . . )	" ᲙᲗᲢᲚᲘᲛᲧᲉᲕᲁᲑᲞᲓᲔᲥ mahachhatrapasa, &c.)
8	35·8	AR ·5		" ~;	" ᱦ. "









No.	Wt.	Metal. Size.	Obverse.	Reverse.
MAUES.				
(α) <i>Bronze; round; Greek legend only.</i>				
			Head of elephant r.; bell round neck.	ΒΑΣΙΛΕΩΣ ΜΑΥΟΥ Caduceus.
1	Æ 1-15			to L,  . [I. O. C. Pl. xvi. 1.]
2	Æ 1-15			" "
(β) <i>Silver; type, Zeus.</i>				
			ΒΑΣΙΛΕΩΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΜΑΥΟΥ Zeus stand- ing l., clad in himation; r. hand extended; in l., long sceptre.	𐎠𐎡𐎴𐎠 𐎠𐎡𐎴𐎠𐎡𐎴𐎠 (Rajadi- 𐎠𐎡𐎴 <i>rajasa mahatasa</i> <i>Moasa</i> ). Nike r.; holds wreath and palm bound with fillet.
3	151. AR 1-15			to r.,  . [Pl. xvi. 2.]
(γ) <i>Bronze; round; type, King on horseback.</i>				
			ΒΑΣΙΛΕΩΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ [ΜΑΥΟΥ] King r. on horseback; whip over shoulder; lance couched.	𐎠𐎡𐎴 𐎠𐎡𐎴𐎠 𐎠𐎡𐎴𐎠𐎡𐎴𐎠 (Rajaditirajasa mahatasa Moasa). Female figure, facing, diad.; holds in r. hand, patera, containing offer- ings; l. rests on wheel; on head, turreted crown. (Tyche).
4	Æ 1-2		to r.,  .	to L,  . [Pl. xvi. 3.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
(δ) Bronze; round; other types.				
5	Æ 1.		<p>ΒΑΣΙΛΕΩΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΜΑΥΟΥ Artemis running r., radiate, with veil floating round her head; clad in short chiton and boots.</p>	<p>𐤁𐤓𐤕𐤕 𐤁𐤓𐤕𐤕𐤓𐤕𐤕 (Rajadi- 𐤁𐤓𐤕𐤕 <i>rajasa mahatasa</i> <i>Moasa</i>). Indian humped bull l.</p> <p>to l., . [Pl. xvi. 4.]</p>
6	Æ 1.			" "
7	Æ 1.			"  .
Same inscr. Herakles, facing; holds in l. club and lion's skin. Same inscr. Maneless lion l.				
8	Æ 1-05			to l.,  . [Pl. xvi. 5.]
(ε) Bronze; square; type, King on horseback.				
9	Æ 9.		<p>ΒΑΣΙΛΕΩΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΜΑΥΟΥ King r. on horseback; whip over shoulder; r. hand ad- vanced.</p>	<p>𐤁𐤓𐤕𐤕 𐤁𐤓𐤕𐤕𐤓𐤕𐤕 (Rajadi- 𐤁𐤓𐤕𐤕 <i>rajasa mahatasa</i> <i>Moasa</i>). Pallas r., her garment flying; holds in l. hand, spear and shield; r. extended; before her, altar.</p> <p>to r., . [Pl. xvi. 6.]</p>
Same inscr. King r. on horseback; whip over shoulder; lance couched. Same inscr. Nike l.; holds wreath and palm.				
10	Æ 1.			to l.,  . [Pl. xvi. 7.]



No.	Wt.	Metal. Size.	Obverse.	Reverse.
17	Æ 9		<p>ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΜΑΥΟΥ Poseidon striding l., hurling thun- derbolt to r., and hold- ing in left hand aplan- tre; beside him, river- god, leaping up.</p>	<p>𐤁𐤓𐤕 𐤕𐤓.𐤓𐤕 𐤕𐤓𐤕𐤓𐤕𐤓𐤕 (Rajadivajasa mahātasa Moasa). Female figure, clad in chiton and himation, facing; stands between two vines. (Maenad I).</p> <p>to L, . [I. O. C. Pl. xvii. 2.]</p>
18	Æ 1.1		<p>Same inscr. Male figure l., chlamys flying be- hind; holds club and trident.</p> <p>to L, .</p>	<p>Same inscr. Female figure r., pep- lum flying; holds long fillet.</p> <p>to r., . [I. O. C. Pl. xvii. 3.]</p>
19	Æ 1.05			
20	Æ 9		<p>Same inscr. Female figure l.; r. hand advanced; in l., cornucopias. (Tyche I).</p>	<p>Same inscr. Male figure, facing; clad in himation; r. hand on hip; wears petasus. (Hermes I).</p> <p>A to L, . [Pl. xvii. 4.]</p>
21	Æ 9		<p>Same inscr. Elephant run- ning r., holds in trunk wreath: in square of fillet-pattern.</p>	<p>Same inscr. King, facing, seated cross-legged on cushion; sword on his knees: in square of fillet- pattern.</p> <p>to r., . [Pl. xvii. 5.]</p>
22	Æ 9			<p>" "</p>
23	Æ 9			<p>" .</p>
24	Æ 85			<p>" "</p>
25	Æ 1.05		<p>Similar.</p>	<p>Same inscr. Indian humped bull r.</p> <p>to r., . [Pl. xvii. 6.]</p>



No.	Wt.	Metal. Size.	Obverse.	Reverse.
AZES.				
(a) <i>Silver; type, Zeus.</i>				
			ΒΑΣΙΛΕΩΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΟΥ The king r., on horseback; holds lance, couched.	𐤁𐤁.~𐤁𐤁𐤁𐤁𐤁𐤁𐤁𐤁𐤁𐤁𐤁 𐤁𐤁𐤁 (Maharajasa rajarajasa mahātasa Ayasa). Zeus l., radiate; r. hand advanced; in l., long sceptre.
1	146.5	AR 1.1	below, 𐤁.	to l.,  ; to r., 𐤁. [Pl. xvii. 8.]
			Similar.	Same inscr. Zeus, facing, laur.; holds winged thunderbolt and long sceptre.
2	145.7	AR 1.15		to l.,  ; to r.,  [I. O. C. Pl. xvii. 9.]
3	150.3	AR 1.05		" " " "
4	140.6	AR 1.1	below,  .	"  ; " 𐤁. [I. O. C.]
5	35.5	AR .65		to l.,  ; to r.,  [I. O. C. Pl. xvii. 10.]
			Similar.	Same inscr. Zeus, facing, laur.; hurls with r., thunderbolt; and holds in l., long sceptre.
6	37.9	AR .7	below, 𐤁.	to l.,  ; to r., 𐤁. [Pl. xvii. 11.]
7	35.	AR .65	" "	" " " "

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<p>ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΟΥ The king r., on horseback; holds whip.</p>	<p>𐎲𐎠𐎹𐎶 𐎲𐎠𐎹𐎶 𐎲𐎠𐎹𐎶 𐎲𐎠𐎹 (Maharajasa rajarajasa mahâtasâ Ayasa). Zeus l.; holds in r. hand, wreath-bearing Nike; in l., long sceptre.</p>
8	128.	AR 95	below, 𐎲.	to l., 𐎲; to r., 𐎶.
9	146.7	AR 1.1	to r., 𐎶.	" " " 𐎶.
10	140.	AR 1.1	" 𐎶.	" " " 𐎶. 𐎶
11	136.8	AR 1.	" 𐎶.	" " " [I. O. C. Pl. xvii. 12.]
12	142.3	AR 95	" 𐎶.	" " " "
13	149.	AR 1.1	" 𐎶.	" " " "
14	136.	AR 9	" 𐎶.	" 𐎲; " 𐎶. 𐎶
15	150.4	AR 9	" 𐎶.	" " " " [I. O. C.]
16	128.7	AR 95	" 𐎶.	" 𐎲; " 𐎶. 𐎶
17	148.7	AR 95	" 𐎲.	" " " 𐎶. 𐎶
18	149.	AR 9	" 𐎶.	" 𐎲; " 𐎶. 𐎶
19	147.7	AR 95	" 𐎶.	" " " " [I. O. C.]
20	147.	AR 95	" 𐎶.	" 𐎲; " mon. 𐎶

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<p>ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΟΥ The king r., on horseback; holds whip.</p>	<p>𐤀𐤂𐤁𐤏𐤃𐤁𐤏𐤃𐤁𐤏𐤃𐤁𐤏𐤃 𐤀𐤁𐤏 (Maharajasa rajarajasa mahātasa Ayasa). Zeus l.; holds in r. hand, wreath-bearing Nike; in l., long sceptre.</p>
21	32.9	AR 6	to r., Ψ.	to l., 𐤀; to r., 𐤆. 𐤀𐤁 𐤏
22	28.5	AR 6	" "	" " " "
23	33.3	AR 55	" 𐤏.	" 𐤀; " 𐤆.
24	34.8	AR 6	" 𐤏.	" " " [I. O. C. Pl. xvii. 13.]
25	30.	AR 6	" 𐤏. (inverted).	" 𐤀; " "
26	36.5	AR 6	" 𐤏.	" " " "
27	37.	AR 6	" "	" " " "
28	35.6	AR 6	" 𐤀.	" " " 𐤆. [I. O. C.]
29	36.8	AR 6	" 𐤏.	" " " 𐤏.
30	33.5	AR 55	" 𐤆.	" 𐤀; " uncertain letter.
31	27.4	AR 6	" 𐤀.	" " " 𐤏. [I. O. C.]
32	33.9	AR 6	" 𐤏.	" 𐤆; " 𐤀 𐤀.
33	34.	AR 65	" 𐤀.	" 𐤀; " mon. 𐤆.
34	30.5	AR 6	" "	" " " " " [I. O. C.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<p>ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΟΥ The king r., on horseback; holds whip.</p>	<p>𐎧𐎡𐎹𐎶𐎠𐎧𐎡𐎹𐎶𐎠𐎧𐎡𐎹𐎶𐎠𐎧𐎡𐎹𐎶 𐎧𐎡𐎹 (Maharajasa rajarajasa mahātasa Ajasa). Zeus L.; holds in r. hand, wreath-bearing Nike; in L, long sceptre.</p>
35	31.	AR 65	to r, Ψ.	to L, ☉; to r, 𐎧𐎡𐎹.
36	36.4	AR 6	" 𐎧.	" " " " "
37	36.2	AR 6	" 𐎧.	" " " 𐎧.
38	37.2	AR 6	" 𐎧.	" " " A 𐎧.
39	32.9	AR 6	" 𐎧.	" " " " "
40	35.8	AR 6	" 𐎧.	" " " 0 "
41	30.2	AR 5	" 𐎧.	" " " " 𐎧. [I. O. C.]
42	31.	AR 55	" 𐎧.	" " " Δ M. "
43	33.	AR 6	" 𐎧.	" " " 𐎧 𐎧.
44	28.7	AR 6	" 𐎧.	" " " " "
45	22.6	AR 6	" 𐎧.	" " " " "
46	35.3	AR 6	" 𐎧.	" " " " 𐎧.
47	35.2	AR 6	" 𐎧.	" " " " 𐎧.
48	37.2	AR 6	" 𐎧.	" " " " [I. O. C.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΟΥ The king r., on horseback; holds whip.	פֶּה־שֵׁן פֶּה־שֵׁן פֶּה־שֵׁן פֶּה־שֵׁן (Maharajasa <i>rajarajasa mahātasa Ayasa</i> ). Zeus l.; holds in r. hand, wreath-bearing Nike; in l. long sceptre.
49	32	AR 55	to r., $\text{h}$ .	to l., $\text{☉}$ ; to r., $\text{ז}$ .
50	34.8	AR 55	" $\Psi$ .	" " " $\text{Υ}$ .
51	35.5	AR 55	" uncertain letter.	" " " $\text{Ε}$ . $\text{Ϝ}$
52	34.3	AR 55	" "	" " " "
53	27.5	AR 6	" $\text{Ϝ}$ .	" " " $\text{Γ}$ . [I. O. C.]
54	32	AR 6	" $\text{Ϝ}$ $\text{Ζ}$ .	" " " " "

[Most of the above coins are of base metal and very rude execution. In nos. 16 and 46 the inscr. reads *rajadirajasa*].

(β) Silver; type, Poseidon.

ΒΑΣΙΛΕΥΣ ΒΑΣΙ-  
 ΛΕΩΝ ΜΕΓΑΛΟΥ  
 ΑΖΟΥ King r., on  
 horseback; holds whip.

פֶּה־שֵׁן פֶּה־שֵׁן פֶּה־שֵׁן  
 פֶּה־שֵׁן (Maharajasa  
*rajarajasa mahātasa Ayasa*). Po-  
 seidon r.; holds in l. hand, trident.

55	138	AR 95	to r., $\text{Ϝ}$ .	to l., $\text{☉}$ ; to r., $\text{Ϝ}$ . [Pl. XVIII. 1.]
----	-----	-------	---------------------	---

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			(γ) <i>Silver; type, Pallas.</i>	
			ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΟΥ King r., on horseback; holds lance, couched.	𐎠𐎡𐎢𐎣𐎤𐎥𐎦𐎧𐎨𐎩𐎪𐎫𐎬𐎭𐎮𐎯𐎰𐎱𐎲𐎳𐎴𐎵𐎶𐎷𐎸𐎹𐎺𐎻𐎼𐎽𐎾𐎿 𐎠𐎡 (Maharajasa rajarajasa mahātasa Ayasa). Pal- las l.; in raised r. hand, thunder- bolt; l. holds shield.
56	145.8	AR 95	to r., <i>Λ</i> .	to l., <i>Α</i> ; to r., <i>Ζ</i> . [Pl. XVIII. 2.]
57	132.6	AR 1. (plated)	in ex., <i>Υ</i> .	" " " "
58	145.5	AR 1.05	to r., <i>Υ</i> .	" " " <i>Α</i> .
59	145.5	AR 95		" " " "
60	139.8	AR 1.	" <i>Υ</i> .	" " " "
61	147.	AR 1.	" <i>Λ</i> .	" " " " [I. O. C.]
62	32.8	AR 65	to r., <i>Υ</i> .	to l., <i>Α</i> ; to r., <i>Α</i> .
63	29.6	AR 7	" <i>Υ</i> .	" " " " [Pl. XVIII. 3.]
64	37.5	AR 65	" <i>Υ</i> .	" " " "
65	35.	AR 6	" <i>Υ</i> .	" " " "
66	36.5	AR 7	" <i>Λ</i> .	" " " "
67	35.	AR 7	" "	" " " "
68	36.7	AR 65	" <i>~</i> .	" " " <i>Ζ</i> .
69	34.1	AR 6	" "	" " " " [I. O. C.]

No.	Wt.	Metal Size.	Obverse.	Reverse.
			<p>ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΥ ΑΖΟΥ King r., on horseback; holds whip.</p>	<p>𐤀𐤂𐤏𐤓𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕 𐤀𐤁𐤕 (Maharajasa rajarajasa mahātasa Ayasa). Pal- las, facing; holds in l. hand, spear and shield; with r., crowns herself.</p>
70	138.5	AR 1.	to r., 𐤀.	to l., 𐤀; to r., 𐤀. [Pl. XVIII. 4.]
71	35.	AR 6	to r., 𐤀.	to l., 𐤀; to r., 𐤀.
72	34.5	AR 65	" "	" " " " [Pl. XVIII. 5.]
73	38.	AR 65	" 𐤀.	" " " "
74	38.	AR 65	" 𐤀.	" " " "
75	36.4	AR 6	" 𐤀.	" " " "
76	36.	AR 65	" 𐤀.	" " " 𐤀.
77	39.	AR 65	" "	" " " "
78	37.6	AR 65	" 𐤀.	" " " "
79	38.7	AR 65	" "	" " " "
80	36.9	AR 6	" 𐤀.	" " " "
81	36.3	AR 65	" "	" " " "
82	34.5	AR 65	" 𐤀.	" " " " [I. O. C.]









No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<p>ΒΑΣΙΛΕΩΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΟΥ King r., on horseback; holds whip.</p>	<p>𐎧𐎡𐎹𐎶𐎠𐎧𐎡𐎹𐎶𐎠𐎧𐎡𐎹𐎶𐎠𐎧𐎡𐎹𐎶 𐎧𐎡𐎹 (Maharajasa rajarajasa mahātasa Ayasa). Pal- las, facing; holds in l. hand, spear and shield; with r., crowns herself.</p>
83	30.6	AR 55	to r., letter.	to l., 𐎧; to r., 𐎡.
84	35.3	AR 65	" 𐎧.	" 𐎧; " 𐎡.
85	33.6	AR 65	" "	" " " "
86	36.8	AR 65	" 𐎧.	" " " "
			Similar.	Same inscr. Pallas, standing l.; r. hand advanced; in l., shield.
87	34.1	AR 7	to r., 𐎧.	to l., 𐎧; to r., 𐎡.
88	36.6	AR 6	" 𐎧.	" " " 𐎡. [Pl. XVIII. 6.]
			Similar.	Same inscr. Pallas, facing; holds in r. hand, spear; shield slung over back.
89	33.6	AR 6	to r., 𐎧.	to l., 𐎡; to r., 𐎧. [Pl. XVIII. 7.]



No.	Wt.	Metal Size.	Obverse.	Reverse.
			<p>ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΟΝ King r., on horseback; holds whip.</p>	<p>𐎧𐎡𐎴𐎠𐎧𐎡𐎴𐎠𐎧𐎡𐎴𐎠𐎧𐎡𐎴𐎠𐎧𐎡𐎴𐎠 𐎧𐎡𐎴 (Maharajasa rajarajasa mahatasa Ayasa). Pal- las r.; her r. hand advanced; in her l., spear and shield.</p>
105	37.6	AR 6	to r., 𐎧.	to l., 𐎧; to r., 𐎧.
106	36.7	AR 65	" 𐎧.	" " " "
107	35.6	AR 65		" " " " [Pl. xviii. 9.]
108	28.5	AR 6	" uncertain letter.	" 𐎧; " 𐎧. [L. O. C.]

## (8) Silver; type, City 1

			<p>ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΟΥ King r., on horseback; holds lance, couchant.</p>	<p>𐎧𐎡𐎴𐎠𐎧𐎡𐎴𐎠𐎧𐎡𐎴𐎠𐎧𐎡𐎴𐎠𐎧𐎡𐎴𐎠 𐎧𐎡𐎴 (Maharajasa rajarajasa mahatasa Ayasa). A City? l.; holds in r. hand, object resembling a brazier; in l., palm bound with fillet.</p>
109	136.5	AR 105	to r., 𐎧.	to l., 𐎧; to r., 𐎧. [Pl. xviii. 10.]
110	143	AR 1	" 𐎧.	" " " "
111	34.3	AR 7		[to l., 𐎧 𐎧; to r., 𐎧. [Pl. xviii. 11.]





No.	Wt.	Metal. Size.	Obverse.	Reverse.
(c) <i>Silver; without figure of King.</i>				
			ΒΑΣΙΛΕΩΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΟΥ Zeus I., laur.; r. hand advanced; in l. sceptre held trans- versely.	𐤀𐤁.~𐤁 𐤕𐤕𐤕𐤕𐤕 𐤕𐤕𐤕~ 𐤕𐤕? ( <i>Maharajasa rajarajasa mahātasa Ayasa</i> ). Nike r., winged; holds wreath and palm bound with fillet.
112	35.5	AR-7		to r.,  . [Pl. xviii. 12.]
113	35.1	AR-7		" "
114	36.7	AR-7		" " [L. O. C.]
(d) <i>Bronze; type, King, seated.</i>				
			ΒΑΣΙΛΕΩΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΟΥ King, facing, seated cross-legged on cushion; holds in r. hand, ankus; in l., sword, which rests on his knees.	𐤀𐤁~𐤁 𐤕𐤕𐤕𐤕𐤕 𐤕𐤕𐤕~ 𐤕𐤕? ( <i>Maharajasa rajarajasa mahātasa Ayasa</i> ). Her- mes l., with chlamys flying; r. hand raised; in l. caduceus.
115	Æ 1.		to l.,  .	to l.,  ; to r.,  .
116	Æ 1-05		" "	" " " " [L. O. C. Pl. xix. 1.]
117	Æ-95		"  .	" " " "
118	Æ 1-05		" "	"  .
119	Æ 1.		" "	"  ; "  .
120	Æ 1.			" " " "

No.	Wt.	Metal, Size.	Obverse.	Reverse.
			<b>ΒΑΣΙΛΕΥΣ ΒΑΣΙ-</b> <b>ΛΕΩΝ ΜΕΓΑΛΟΥ</b> <b>ΑΖΟΥ</b> King, facing, seated cross-legged on cushion; holds in r. hand, ankus; in l., sword, which rests on his knees.	𐎧𐎡𐎴𐎠𐎧𐎡𐎴𐎠𐎧𐎡𐎴𐎠 𐎧𐎡𐎴 (Maharajasa <i>rajarajasa mahatasa Ayasa</i> ). Her- mes l., with chlamys flying; r. hand raised; in l., caduceus.
121	Æ 1.05		to l., 𐎧.	to l., 𐎧; to r., 𐎧.
122	Æ .95		" uncertain letter.	" " " 𐎧𐎡𐎴. ( <i>inscr. rajadhirajasa</i> ).
123	Æ .95		" 𐎧.	" 𐎧; " 𐎧𐎡𐎴.
124	Æ .7			" " " "
125	Æ 1.		" 𐎧 (inverted).	" 𐎧; " 𐎧. ( <i>inscr. rajadhirajasa</i> ).
126	Æ .9		" 𐎧.	" 𐎧𐎡𐎴; " 𐎧𐎡𐎴.



(η) Bronze; type, *Demeter or City*.

			<b>ΒΑΣΙΛΕΥΣ ΒΑΣΙ-</b> <b>ΛΕΩΝ ΜΕΓΑΛΟΥ</b> <b>ΑΖΟΥ</b> Demeter? seated l. on throne, me- dius on head; r. hand raised; in l., cornu- copia.	𐎧𐎡𐎴𐎠𐎧𐎡𐎴𐎠𐎧𐎡𐎴𐎠 𐎧𐎡𐎴 (Maharajasa <i>rajarajasa mahatasa Ayasa</i> ). Her- mes l.; r. hand raised; in l., cadu- ceus.
127	Æ 1.05			to l., 𐎧; to r., 𐎧.
128	Æ 1.05			" " " "
129	Æ 1.05			" " " " (restruck).
130	Æ 1.			[I. O. C. Pl. XIX. 2.]
131	Æ 1.			[I. O. C.]
132	Æ 1.1			" " " "

[Restruck on a coin of Azes, cf. κ; types, elephant, humped bull].

No.	Wt.	Metal. Sign.	Obverse.	Reverse.
			<p>ΒΑΣΙΛΕΩΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΟΥ Hermes l., wears chlamys; r. hand advanced; in l., cadu- ceus.</p>	<p>𐤁𐤏𐤓𐤕𐤕𐤏𐤕𐤕𐤏𐤕 𐤁𐤏𐤓 (Maharajasa rajarajasa mahatasa Ayasa). Demeter? standing l., wears mo- dius; r. hand advanced; in l., cornucopiae.</p>
133	Æ 75		to l.,  .	to l.,  ; to r., 𐤅. [Pl. XIX. 3.]
			Same inser. Lion r.	Similar.
134	Æ 75			to l.,  ; to r., 𐤅.
135	Æ 65		above,  .	" " " € 41. [Pl. XIX. 4.]
136	Æ 65		" "	" " " o 3.

(6) Bronze; type, male deity.

137	Æ 1	<p>to l., .</p>	<p>ΒΑΣΙΛΕΩΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΟΥ Female deity, facing, clad in hima- tion; holds in raised r. hand, flower; stands on lotus; beside her, lion? (Lakshmi?).</p>	<p>𐤁𐤏𐤓𐤕𐤕𐤏𐤕𐤕𐤏𐤕 𐤁𐤏𐤓 (Maharajasa rajarajasa mahatasa Ayasa). Humped bull r.</p>	
				<p>to r., .</p>	[Pl XIX. 5.]

(i) Bronze; types, lion and bull.

			<p>ΒΑΣΙΛΕΩΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΟΥ Humped In- dian bull r.</p>	<p>𐤁𐤏𐤓𐤕𐤕𐤏𐤕𐤕𐤏𐤕 𐤁𐤏𐤓 (Maharajasa rajarajasa mahatasa Ayasa). Lion r.</p>
138	Æ 1.1	above,		above,
139	Æ 1.1	" "	" "	" "

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΣΟΥ Humped In- dian bull r.	𐎧𐎡𐎢𐎵𐎠𐎧𐎡𐎢𐎵𐎠𐎧 𐎧𐎡𐎢 (Maharajasa <i>rajalirajasa mahutasi Ayami</i> ). Lion r.
140	Æ 1-1		above, 𐎧.	above, 𐎧.
141	Æ 1.		" 𐎧.	" 𐎧.
142	Æ 1-1		" 𐎧; to r., 𐎧.	" 𐎧.
143	Æ 1-05		" 𐎧; " 𐎧.	" 𐎧.
144	Æ 1-05		" " " 𐎧.	" "
145	Æ 1.		" " " 𐎧.	" "
146	Æ 1-1		" " " 𐎧.	" 𐎧.
147	Æ 95		" "	" 𐎧. [L. O. C.]
148	Æ 1.		" 𐎧.	" 𐎧.
149	Æ 1-1		" 𐎧.	" 𐎧.
150	Æ 1-2		" " " 𐎧.	" "
151	Æ 1-1		" 𐎧; " "	" 𐎧.
152	Æ 1-2		" 𐎧; " 𐎧.	" 𐎧. [Pl. XIX. 6.]
153	Æ 1-1		" " " 𐎧.	" 𐎧.
154	Æ 85		" 𐎧.	" 𐎧.
155	Æ 85		" 𐎧; " 𐎧. (inscription barbarous).	to r., 𐎧.
156	Æ 8		" 𐎧.	above, 𐎧. [L. O. C.]





No.	Wt.	Metal. Size.	Obverse.	Reverse.
			(v) <i>Bronze; square; type, Poseidon.</i>	
			<b>ΒΑΣΙΛΕΩΣ ΒΑΣΙ-</b> <b>ΛΕΩΝ ΜΕΓΑΛΟΥ</b> <b>ΑΖΟΥ</b> Poseidon l., clad in himation; r. hand on hip; in l., tri- dent: foot placed on shoulder of river-god.	𐤁𐤌.~𐤁 𐤕𐤕𐤕𐤕𐤕 𐤕𐤕𐤕~𐤁 𐤕𐤕? ( <i>Maharajasa</i> <i>rajarajasa mahātasa Ayasa</i> ). Female figure, clad in chiton and himation, facing; holds in each hand, long vine-branch.
181	Æ 1.			to l., 𐤁. [Pl. xix. 10.]
182	Æ 1.			" "
183	Æ 1.			" " [I. O. C.]
184	Æ 1-2			" "
			<hr/> Same inset. Male figure l., chlamys flying be- hind; holds club and trident.	
185	Æ 8			Same inset. Female figure r., pep- lum flying; holds long fillet. to r., 𐤁.
			(ξ) <i>Bronze; square; animal types.</i>	
			<b>ΒΑΣΙΛΕΩΣ ΒΑΣΙ-</b> <b>ΛΕΩΝ ΜΕΓΑΛΟΥ</b> <b>ΑΖΟΥ</b> Herakles, facing; holds in l hand, club and lion's skin; and with r., crowns himself.	𐤕𐤕~𐤁 𐤕𐤕𐤕𐤕𐤕 𐤕𐤕𐤕~𐤁 𐤕𐤕? ( <i>Maharajasa</i> <i>rajarajasa mahātasa Ayasa</i> ). Horse r.
186	Æ 9			above, 𐤕.
187	Æ 95		to l., 𐤁.	" " [I. O. C. Pl. xix. 11.]
* Restruck on a coin of Hippostratus; for types see coin of Hippostratus, supra, p. 60, no. 15.				

No.	Wt.	Metal, Size.	Obverse.	Reverse.
188	Æ 1.1	above, 7.	ΒΑΣΙΛΕΩΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΟΥ Elephant r.	𐎲𐎠𐎺𐎡𐎴𐎠𐎹𐎶𐎵𐎶𐎵𐎶𐎵 𐎲𐎠𐎹 (Maharajasa rajaraajasa mahatasa Ayasa). Humped bull r.
189	Æ .45		ΒΑΣΙΛΕΩΣ ΜΕΓΑ- ΛΟΥ ΑΖΟΥ Ele- phant r.	𐎲𐎠𐎹 𐎲𐎠𐎺𐎡𐎴𐎠𐎹𐎶𐎵𐎶𐎵𐎶𐎵 (Maharajasa mahatasa Ayasa). Humped bull r.
190	Æ .65	above, 7.	ΒΑΣΙΛΕΩΣ ΒΑΣΙΛΕ ΩΝ ΜΕΓΑΛΟΥΑΣ Lion r.	𐎲𐎠𐎹 . . . . . 𐎲𐎠𐎹𐎶𐎵𐎶𐎵 (Maharaja . . . . . Ayasa). Humped bull l.
191	145.4	AR .85	Corrupt legend. King r., on horseback; holds in r. hand ankus(?); before him, symbol Y.*	𐎲𐎠𐎹𐎶𐎵𐎶𐎵𐎶𐎵𐎶𐎵𐎶𐎵 𐎲𐎠𐎹𐎶𐎵𐎶𐎵𐎶𐎵 (Maharajasa mahatasa dhrami- kusa rajadhirajasa Ayasa). City L, turreted, and clad in chiton and peplum; r. hand advanced; in L, cornucopias.
192	141.	AR .8		to L, Z; to r., 𐎲. [Pl. xx. 1.]
193	142.2	AR .8		" " " "

\* On most of these coins there is an appearance of various Indian letters in the obverse field which are not here inserted, it being doubtful whether they are not mere blunders.



No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<p>ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΟΥ King r., on horseback; holds ankus; behind him, bow on sad- dle; beneath, ☉.</p>	<p>𐎲𐎠𐎧𐎡𐎴 𐎲𐎵𐎡𐎴 𐎠𐎲𐎵𐎴 𐎲𐎧𐎡𐎴 𐎲𐎵𐎴𐎶</p> <p>(Indracarma putrasa Anjavarma- sa strategasa jayatasa). Pallas r., armed; her r. hand advanced; in her l. spear and shield; behind, star and ☉.</p>
207	157.2	AR 85	to r., β.	to r., 𐎲; to l., Ϛ. [I. O. C.]
208	159.4	AR 9	" "	" " " " "
209	150	AR 85	" "	" " " ∪.
210	155.7	AR 8	" "	" " " "
211	149	AR 8	" "	" uncertain letter. "

## AZES AND AZILISES.

(a) Silver.













ΒΑΣΙΛΕΥΣ . . HM-  
ΓΑΛΟΥ ΑΖΛΙΣΟΥ  
The king r., on horse-  
back; holds bow.

𐎲𐎧𐎡𐎴 𐎲 . . . 𐎲𐎵𐎴𐎶  
𐎲𐎡𐎴 (Maharajasa  
[rajaraja]sa mahatasa Ayasa).  
Zeus standing l., diad.; holds  
Nike and long sceptre.

1 31.7 AR 6 in front, ∪.

to l., 𐎲; to r., 𐎲.

[I. O. C. Pl. xx. 3.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
AZILISES.				
(a) <i>Silver; type, Zeus.</i>				
			<p>ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΙΛΙΣΟΥ The king r., on horseback; in r. hand, ankus; bow on saddle.</p>	<p>𐤁𐤌𐤕𐤕𐤁𐤌𐤕𐤕𐤁𐤌𐤕𐤕 𐤁𐤌𐤕𐤕𐤁𐤌𐤕𐤕𐤁𐤌𐤕𐤕 (Maharajasa rajadhirajasa mahatasa Ayilishasa). Zeus r., diad., wearing himation; holds wreath (I) and long sceptre.</p>
1	148.5	AR 1.05	to r.,  .	to l.,  ; to r.,  . [Pl. xx. 4.]
(β) <i>Silver; type, Dioscouri.</i>				
			<p>ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΙΛΙΣΟΥ The king r., on horseback; holds ankus; bow on saddle.</p>	<p>𐤁𐤌𐤕𐤕𐤁𐤌𐤕𐤕𐤁𐤌𐤕𐤕 𐤁𐤌𐤕𐤕𐤁𐤌𐤕𐤕𐤁𐤌𐤕𐤕 (Maharajasa rajadhirajasa mahatasa Ayilishasa). The Dioscouri, facing; each wears Phrygian cap and chlamys, and holds spear and sword.</p>
2	146.2	AR 1.05	to r.,  .	
3	150.4	AR 1.05	"  ; below,  .	to l.,  ; to r.,  . [Pl. xx. 5.]
4	33.3	AR .65	" "	" " " [L. O. C. Pl. xx. 6.]
			Similar.	Same inser. One of the Dioscouri, facing, as above, but bearded and wearing chiton.
5	146.8	AR 1.1	to r.,  .	to l.,  . [Pl. xx. 7.]
6	37.8	AR .6	to r.,  .	to l.,  . [Pl. xx. 8.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
(γ) Silver; type, City 1				
			ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΑΖΙΛΙΣΟΥ The king r., on horseback; holds lance couched.	𐎧𐎡𐎴𐎠 𐎧𐎡𐎴𐎠 𐎧𐎡𐎴𐎠 𐎧𐎡𐎴𐎠 (Maharajasa <i>rajarajasa mahatasa Azilishasa</i> ). City (?) l.; holds in r., uncertain object; in l., palm bound with fillet.
7	140.3	AR 105		to l., 𐎧𐎡𐎴𐎠; to r., 𐎧. [Pl. xx. 9.]
8	149.8	AR 105	to r., 𐎧.	" " " "
9	146.2	AR 1	" 𐎧𐎡𐎴𐎠.	" " " " [L. O. C.]
10	139.5	AR 1	" 𐎧 "	" " " "
11	144.9	AR 11		" 𐎡; " 𐎧. [Pl. xx. 10.]
12	148.5	AR 105		" 𐎧𐎡𐎴𐎠; " 𐎧.
13	35.8	AR 7		to l., 𐎧𐎡𐎴𐎠; to r., 𐎧.
14	35.3	AR 7		" " " "
15	32.6	AR 65		" 𐎧𐎡𐎴𐎠; " 𐎡. [Pl. xx. 11.]
16	32.9	AR 7		" " " 𐎡.
17	32.2	AR 7		" " " 𐎧.
18	34.7	AR 65		" " " 𐎧.
19	36	AR 7		" " " 𐎧. [L. O. C.]
20	35.8	AR 65		" 𐎧𐎡𐎴𐎠; " 𐎧.
21	35	AR 65	to l., 𐎧.	" " " "
22	36.9	AR 7	" 𐎧𐎡𐎴𐎠.	" " " "

No.	Wt.	Metal. Size.	Obverse.	Reverse.
(δ) Bronze; square; type, King on horseback.				
			<b>ΒΑΣΙΛΕΩΣ ΒΑΣΙ-</b> <b>ΛΕΩΝ ΜΕΓΑΛΟΥ</b> <b>ΑΖΙΛΙΣΟΥ</b> King r., on horseback; holds lance couched.	<b>ΥΤΗΑΖ ΥΓ~Υ ΥΖΥ~Υ</b> <i>(Maharajasa mahatasa Agilishasa)</i> Herakles, diad., naked, seated l.; holds in r. hand club, which rests on knee.
23	Æ 9		to r., <b>Υ Ζ.</b>	to l., <b>Υ Θ.</b> [Pl. XXI. 1.]
24	Æ 95		" "	" " "
			Similar.	Same inser. Elephant r.
25	Æ 85			above, <b>Υ Θ.</b>
26	Æ 75			" " " [L. O. C. Pl. XXI. 2.]
			Similar.	<b>ΥΓ~Υ ΥΖΥΖΥΖΥΖΥΖΥ</b> <b>ΥΤΗΑΖ</b> <i>(Maharajasa</i> <i>rajarajasa mahatasa Agilishasa)</i> Humped bull r.
27	Æ 9			above, <b>Υ Σ.</b> [Pl. XXI. 3.]
28	Æ 105			" <b>Α Ζ.</b>
29	Æ 95			" " " [L. O. C.]
30	Æ 14			" <b>Π Ψ.</b>

No.	Wt.	Metal Size.	Obverse.	Reverse.
			<b>ΒΑΣΙΛΕΩΣ ΒΑΣΙ-</b> <b>ΛΕΩΝ ΜΕΓΑΛΟΥ</b> <b>ΑΖΙΛΙΣΟΥ</b> King r., on horseback; holds lance couched.	<b>𐎲𐎠𐎹𐎶 𐎠𐎡𐎴𐎶 𐎠𐎡𐎴𐎶</b> <b>𐎲𐎠𐎡𐎴𐎶</b> ( <i>Maharajasa</i> <i>rajarajasa mahatasa Ayilishasa</i> ). Humped bull l.
31	Æ 1.05			above, <b>𐎲 𐎠𐎡</b> . (restruck coin).
32	Æ .95		to r., <b>𐎡</b> .	" <b>Σ 𐎡</b> .
33	Æ .9		(king to l.)	" " "
(c) Bronze; square; type, King (l) standing.				
			<b>ΒΑΣΙΛΕΩΣ ΒΑΣΙ-</b> <b>ΛΕΩΝ ΜΕΓΑΛΟΥ</b> <b>ΑΖΙΛΙΣΟΥ</b> The king (l) standing r., clad in helmet and cloak; holds in l. hand, shield; r. advanced.	<b>𐎲𐎠𐎹𐎶 𐎠𐎡𐎴𐎶 𐎠𐎡𐎴𐎶 𐎠𐎡𐎴𐎶</b> <b>𐎲𐎠𐎡𐎴𐎶</b> ( <i>Maharajasa</i> <i>rajarajasa mahatasa Ayilishasa</i> ). Nike (l) r., unwinged, clad in short chiton, with inflated veil over her head; holds in r. hand wreath.
34	Æ .9		to r., <b>Α</b> .	to r., <b>Σ</b> . [Pl. XXI. 4.]
35	Æ 1.			
36	Æ .85		" "	to l., <b>𐎡</b> ; to r., uncertain letter. [L. O. C.]
37	Æ .95		" "	" " " " "
(d) Bronze; square; other types.				
			<b>ΒΑΣΙΛΕΩΣ [ΒΑΣΙ-</b> <b>ΛΕΩΝ ΜΕΓΑ]ΛΟΥ</b> <b>ΑΖΙΛΙΣΟΥ</b> Herakles, facing, crowning him- self; holds in l. hand club and lion's skin.	<b>𐎲𐎠𐎹𐎶 𐎠𐎡𐎴𐎶 𐎠𐎡𐎴𐎶 𐎠𐎡𐎴𐎶</b> <b>𐎲𐎠𐎡𐎴𐎶</b> ( <i>Maharajasa</i> <i>rajarajasa mahatasa Ayilishasa</i> ). Horse standing r.
38	Æ .9		to l., <b>Β</b> .	above, <b>𐎡</b> .
39	Æ .95		" "	in field, <b>𐎡 𐎠</b> . [L. O. C. Pl. XXI. 5.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<p>ΒΑΣΙΛΕΩΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛ.Υ ΑΖΙΑΙΣ.Υ Male figure, facing, clad in himation, head turned to r.; holds in r. hand, sceptre; in l., uncertain object.</p>	<p>𐤁𐤒𐤓𐤕𐤕𐤕𐤕𐤕𐤕𐤕 𐤁𐤒𐤕𐤕𐤕𐤕𐤕 (Maharaja rajadirajasa mahatasa Ayilishasa). Lion r., looking back.</p>
40		Æ 1·05	<p>to l., 𐤁𐤕.</p> <p>Inscr. obscure. Elephant l.</p>	<p>above, 𐤁𐤕. [I. O. C. Pl. xxi. 6.]</p> <p>Inscr. obscure; ends 𐤁𐤒𐤕𐤕𐤕𐤕𐤕 (Ayilishasa). Humped bull l.</p>
41		Æ 1·05		<p>to l., mon. [I. O. C.]</p>

No.	Wt.	Metal Size.	Obverse.	Reverse.
SPALAHORES, WITH VONONES.				
(a) <i>Silver.</i>				
			<p>ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΟΝΩΝΟΥ King r., on horseback; holds lance couched.</p>	<p>𐎲𐎠𐎶𐎵 𐎲𐎡 𐎶𐎵.𐎶𐎵 𐎲𐎡𐎴𐎠𐎵 (Māhārāja bhrata dhramikasa Spalahorasa). Zeus, laur., facing, clad in hima- tion; holds thunderbolt and long sceptre.</p>
1	144.5	AR 1.05		to r., R. [I. O. C. Pl. XXI. 7.]
2	37.5	AR 6		to r., R.
3	37.3	AR 7		" " [Pl. XXI. 8.]
4	38.	AR 65		to l., ☐.
5	37.8	AR 6		" "
(β) <i>Bronze; square.</i>				
			<p>ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΟΝΩΝΟΥ Herakles, facing; holds in l. hand, club and lion's skin; and with r., crowns himself.</p>	<p>𐎲𐎠𐎶𐎵 𐎲𐎡 𐎶𐎵.𐎶𐎵 𐎲𐎡𐎴𐎠𐎵 (Māhārāja bhrata dhramikasa Spalahorasa). Pallas l., wearing helmet; holds in r. hand, wreath; in l., spear and shield bound with fillet; sword slung round waist.</p>
6		Æ 85		to l., ☐.
7		Æ 8		" " [Pl. XXI. 9.]

No.	Wt.	Metal Size.	Obverse.	Reverse.
SPALAGADAMES, WITH VONONES.				
(a) <i>Silver.</i>				
			<p>ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΟΝΩΝΟΥ King r., on horseback; holds lance couched.</p>	<p>𐤁𐤓𐤕𐤕 𐤁.𐤋𐤁 𐤕𐤕𐤁𐤁 𐤕𐤕𐤕𐤕𐤁𐤁 <i>Spalahora</i> <i>putrāsa dhramiasa Spalagada-</i> <i>masa</i>). Zeus, facing, laur., clad in himation; holds thunderbolt and long sceptre.</p>
1	36.1	AR 65		to L, (A).
2	36.5	AR 7		" " [Pl. xxi. 10.]
3	36.8	AR 6		" (B).
4	36.2	AR 65		" " [I. O. C.]
(β) <i>Brinze; square.</i>				
			<p>ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΟΝΩΝΟΥ Herakles, facing; holds in l. hand, club and lion's skin; and with r., crowns himself.</p>	<p>𐤁𐤓𐤕𐤕 𐤁.𐤋𐤁 𐤕𐤕𐤁𐤁 𐤕𐤕𐤕𐤕𐤁𐤁 <i>Spalahora</i> <i>putrāsa dhramiasa Spalagada-</i> <i>masa</i>). Pallas l., wearing hel- met; holds in r. hand, wreath (F); in l., spear and shield bound with fillet; sword slung round waist.</p>
5		AE 75		to L, (C).
6		AE 8		" " [Pl. xxi. 11.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
SPALAGADAMES, WITH SPALYRIS.				
(a) <i>Bronze; square.</i>				
			<p>ΣΠΑΛΥΡΙΩΣ ΔΙΚΑΙ- ΟΥ ΑΔΕΛΦΟΥ ΤΟΥ ΒΑΣΙΛΕΩΣ King r., on horseback.</p>	<p>ΥΓΨΖ Π.ΛΑ' ΥΝΗΑ ΥΝΗΑΥΑ Spalahora <i>putrāsa dhramāsa Spalagada- masa</i>). Herakles, diad., seated l. on rocks; holds in r. hand, club, which rests on knee.</p>
1		Æ 85		to 1., ⊗. [Pl. XXI. 12.]
2		Æ 8		" "
3		Æ 85		" ⊠.
SPALIRISES; AS KING'S BROTHER.				
(a) <i>Silver.</i>				
			<p>ΒΑΣΙΛΕΩΣ ΑΔΕΛ- ΦΟΥ ΣΠΑΛΙΡΙΣΟΥ King r., on horseback; holds lance couched.</p>	<p>ΥΓΨΖ ~Η * ΥΓ.~Υ ΥΠΥΗΑ (Māhārāja <i>brahā dhramāsa Spalirisa</i>). Zeus, facing, wearing himation; holds thunderbolt and long sceptre.</p>
1	36.6	AR 55		to 1., ⊠. [Pl. XXII. 1.]
2	26.7	AR 6		" "
<p>* Or .ΛΗ <i>bratēs</i>. V. Sallet writes (p. 352), die Form <i>brahā</i> für Bruder wird von nachkundiger Seite für berechtigt erklärt.</p>				

No.	Wt.	Metal. Size.	Obverse.	Reverse.
SPALIRISES; AS KING.				
(a) <i>Bronze; square.</i>				
			<p>ΒΑΣΙΛΕΩΝ ΒΑΣΙΛ- ΕΩΣ ΜΕΓΑΛΟΥ ΣΠΑΛΙΡΙΣΟΥ</p> <p>King, standing l.; holds battle-axe; bow at his side.</p>	<p>𐤁𐤕𐤓𐤕𐤕𐤕 𐤁𐤕𐤓𐤕𐤕𐤕 𐤕𐤓𐤕𐤕𐤕𐤕 (Maharajasa mâhâtakasa Spalirîsasa). Zeus, radiate, seated l. on throne; r. hand extended; in l., sceptre.</p>
1	Æ 9			to r., ⊕.
2	Æ 9			" " *
3	Æ 95			
4	Æ 9			" " [I. O. C. Pl. xxii. 2.]
5	Æ 9			" ⊕. [I. O. C.]

\* Restruck on copper of Venonoe with Spalaberes or Spalagadames (?).  
Club of Herakles seen on obv. (?).

No.	Wt.	Metal. Size.	Obverse.	Reverse.
SPALIRISES, WITH AZES.				
(a) <i>Silver.</i>				
			ΒΑΣΙΛΕΩΣ ΜΕΓΑ- ΛΟΥ ΠΠΑΛΙΡΙΣΟΥ King r., on horseback; holds lance couched.	𐎧𐎡𐎴.~ 𐎧𐎡𐎴 𐎧𐎡𐎴 (Maharajasa mahātakasa Ayasa). Zeus, facing, laur., clad in himation; holds thun- derbolt and long sceptre.
1	37.7	AR 6		to l., ☐; to r., 𐎧.
2	37.8	AR 6		" " " "
3	34.5	AR 65		" " " [I. O. C. Pl. xxii. 3.]
4	30.9	AR 65		" " " " [I. O. C.]
(β) <i>Bronze; round.</i>				
			ΒΑΣΙΛΕΩΣ ΜΕΓΑ- ΛΟΥ ΠΠΑΛΙΡΙΣΟΥ King r., on horseback; holds ankus.	𐎧𐎡𐎴.~ 𐎧𐎡𐎴 𐎧𐎡𐎴 (Maharajasa mahātakasa Ayasa). Strung bow and arrow l.
5	Æ 95			above, ☉. [Pl. xxii. 4.]

No.	Wt.	Metal. Slee.	Obverse.	Reverse.
GONDOPHARES.				
(a) <i>Base silver; type, Zeus.</i>				
			<b>ΒΑΣΙΛΕΩΣΙΔΕΩΝ</b> <b>ΜΕΓΑΛΙ ΝΗΔΟΦΡΟ</b> The king r., on horse- back; arm extended; in front, ☧.	𐎠𐎡𐎢𐎣𐎤𐎥𐎦𐎧𐎨𐎩𐎪𐎫𐎬𐎭𐎮𐎰𐎱𐎲𐎳𐎴𐎵 𐎶𐎷𐎸𐎹𐎺𐎻𐎼𐎽𐎾𐎿 ( <i>Maharaja rajadiraja tradata de-            vatrata* Gudapharasa</i> ). Zeus, naked to waist, standing r.; r. arm extended; in l. long sceptre.
1	144.2	AR.9		to l., ☧; to r., 𐎠𐎡. [I. O. C. Pl. xxii. 5.]
2	136.5	AR.95	inser. <b>ΒΑΣΙΛΕΩΣ</b> <b>ΒΑΣΙΛΕΩΝ</b> &c.	" " B; " 𐎠𐎡. [I. O. C.]
(β) <i>Base silver; type, Pallas.</i>				
			<b>ΒΑΣΙΛΕ .</b> <b>ΒΑΣΙ-</b> <b>ΛΕΩΝ ΜΕΓΑΛ .</b> <b>ΥΝΔΟΦΕΡΡΟ</b> The king, diad., r., on horse- back; to r., ☧.	𐎠𐎡𐎢𐎣𐎤𐎥𐎦𐎧𐎨𐎩𐎪𐎫𐎬𐎭𐎮𐎰𐎱𐎲𐎳𐎴𐎵 𐎶𐎷𐎸𐎹𐎺𐎻𐎼𐎽𐎾𐎿 ( <i>Maharaja rajadiraja tradata de-            vatrata Gudapharasa</i> ). Pallas r., armed; in her l. hand, spear and shield; her r. advanced.
3	142.	AR.95		to l., 𐎠𐎡; to r., 𐎠𐎡. [Pl. xxii. 6.]
4	143.	AR.9	inser. <b>ΒΑΣΙΛΕΩΣ</b> <b>ΟΥ ΜΕΩΝ ΝΗΔΟ</b> <b>ΟΕΡΡ</b>	" " " " "
			Inscr. barbarous. Head of the king r., diad.	𐎠𐎡𐎢𐎣𐎤𐎥𐎦𐎧𐎨𐎩𐎪𐎫𐎬𐎭𐎮𐎰𐎱𐎲𐎳𐎴𐎵 𐎶𐎷𐎸𐎹𐎺𐎻𐎼𐎽𐎾𐎿 ( <i>Maharajasa            mahatasa Gudapharasa</i> ). Pallas r., fighting; holds thunderbolt and shield.
5	37.6	AR.45		in field, 𐎠𐎡 𐎠𐎡. [Pl. xxii. 7.]
6	38.6	AR.45		" " "
7	40.6	AR.5		" " "
* <i>Devatrata</i> , protected by the Gods. This word has been read by Gen. Cunningham <i>Devakata</i> , as a rendering of <i>θεόπρωτος</i> .				

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			(γ) <i>Base silver; type, Siva.</i>	
			ΒΑΣΙΛΕΩΣ ΒΑΣΙ- ΛΕΩΝ ΜΕΓΑΛΟΥ ΥΝΔΟΦΕΡΡΟΥ The king l., on horse- back; r. hand raised; behind him, Nike flying l., holding wreath and palm; to l., ☿.	𐎧𐎡𐎢𐎣 𐎧𐎡𐎢𐎣 𐎧𐎡𐎢𐎣 𐎧𐎡𐎢𐎣 𐎧𐎡𐎢𐎣 ( <i>Maharajasa rajarajasa tradatasa</i> <i>devatrata Gudapharasa</i> ). Siva, facing; holds in r. hand, trident; in l., palm.
8	146.2	AR '95		to l., ☿; to r., ♀. [Pl. xxii. 8.] 𐎧
9	137.4	AR '95	below, 𐎧.	" " " " [I. O. C.] (Λ for 𐎧 in inscr.)
			ΒΑΣΙΛΕΩΝ ΒΑΣΙ- ΛΕΩΝ ΓΟΥΔΟΦΑ- ΡΟΥ The king r., on horseback; holds ankus in extended r. hand; to r., ☿.	𐎧𐎡𐎢𐎣 𐎧𐎡𐎢𐎣 𐎧𐎡𐎢𐎣 𐎧𐎡𐎢𐎣 𐎧𐎡𐎢𐎣 ( <i>Maharaja rajaraja mahatasa</i> <i>devatrata Gudapharasa</i> ). Siva, facing; r. extended; in l., trident.
10	145.8	AR '95	below, 𐎧.	to l., 𐎧; to r., mon. [I. O. C. Pl. xxii. 9.]
11	146.7	AR '9	" "	" " " "

(δ) *Base silver; type, Nike.*

			ΒΑ CΙΛΕ The king, diad., seated l. on throne with back; on the top of which ☿ ☿; r. hand raised.	ΑΛΟΥΝΔΟΦ Nike r.; holds wreath and palm.
† 12	108.5	AR '85		to l., 𐎧; to r., ☿. [Pl. xxii. 10.]

\* The missing letters look like 𐎧𐎡𐎢𐎣 *mita* (for *mitra*?).

† This coin, as well as some of those which precede it, is apparently wholly or almost wholly made of copper; but the nature of the types indicates that it was intended to pass among the debased silver coins of the period.

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			(a) <i>Copper; type, Nike.</i>	
			BACIAEΩΣ ΕΩΤΗ- ΡΟΣ ΥΝΔΟΦΕΡ- ΡΟΝ Bust of the king r., diad.	𐤁𐤁𐤁𐤁 𐤏𐤕𐤏𐤕𐤏 𐤏𐤕𐤏𐤕𐤏 (Maharajasa Gudaphanasa tradatasa). Nike r.; holds wreath and palm.
13		Æ 9		
14		Æ 1.		
15		Æ 95		
16		Æ 95		
17		Æ 85	(ω for Ω in inscr.).	
18		Æ 95		
19		Æ 9		
20		Æ 9		
21		Æ 9	(inscr. begins BACIA- EON).	[I. O. C. Pl. xxii. 11.]
			(b) <i>Bronze; square.</i>	
			ΦΑΓΟΝ ΕΓΑΛΟΝ ΓΟΝΔΑ sic. King l., on horseback; re- ceived by Nike, who holds wreath.	𐤏𐤕𐤏𐤕𐤏𐤕𐤏 𐤏𐤕𐤏𐤕𐤏𐤕𐤏 . . . . . 𐤏𐤕𐤏𐤕𐤏𐤕𐤏 𐤏𐤕𐤏𐤕𐤏𐤕𐤏 (. . . . . dhamikasa apratihata devatrata (devahodasa) Gada- pharasa). 𐤏.
22		Æ 85		to l., 𐤏; to r., 𐤏. [I. O. C. Pl. xxii. 12.] P



No.	Wt.	Metal. Size.	Obverse.	Reverse.
ABDAGASES.				
(α) <i>Copper; as King.</i>				
			ΒΑΣΙΛΕΩC CWTH- POC A[ΒΔΑΓ]ΑCΘV Bust of the king r., diad.	𐤁𐤓𐤕𐤕𐤕𐤕𐤕 𐤕𐤕𐤕𐤕𐤕𐤕 𐤕𐤕𐤕𐤕𐤕 (Tradatasas maharajasa Avadagasa). Nike r., holding wreath and palm.
1		Æ ·85		[Pl. xxiii. 1.]
2		Æ ·85		to l., uncertain letters.
3		Æ ·9		
4		Æ ·9	(inscr. ΒΑΣΙΛΕYC CWTHP....).	
(β) <i>Base silver; as King's nephew.</i>				
			ΒΑΣΙΛΕΥΟΝΤΟΞ ΒΑΣΙΛΕΩΝΙ ΑΒ- ΔΑΓΑΣΘY (The BA of Abdagases' name read sometimes as the first letters of ΒΑΣΙΛ- ΕΥΟΝΤΟΞ; the let- ter which follows ΒΑ- ΣΙΛΕΩΝ is uncertain [l or ξ]). The king l., on horseback; in front, ξ.	𐤕𐤕𐤕𐤕𐤕𐤕 𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕 𐤕𐤕𐤕𐤕𐤕𐤕𐤕 𐤕𐤕𐤕𐤕𐤕 (Gadapharabhradaputrasa maharajasa tradatasas Avadagasa). Zeus, standing r.; holds sceptre; r. hand advanced.
5	150	AR ·85	to l., 𐤕.	to l., 𐤕𐤕𐤕; to r., 𐤕𐤕.
6	155·5	AR ·9	" "	" 𐤕𐤕; " 𐤕𐤕. [Pl. xxiii. 2.]
7	150·1	AR ·85	" "	" " " " " "

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<p>ΒΑΣΙΛΕΥΟΝΤΟΣ ΒΑΣΙΛΕΩΝΙ ΑΒ- ΔΑΓΑΣΟΥ (The BA of Abdagases' name read sometimes as the first letters of ΒΑΣΙΛ- ΕΥΟΝΤΟΣ; the let- ter which follows ΒΑ- ΞΙΛΕΩΝ is uncertain [I or Ξ]). The king l., on horseback; in front, Ξ.</p>	<p>𐰽𐰺𐰍𐰎 𐰽𐰺𐰠𐰪𐰍𐰎𐰽𐰺𐰠𐰪𐰍𐰎 𐰽𐰺𐰠𐰪𐰍𐰎 𐰽𐰺𐰠𐰪𐰍𐰎 (<i>Gadapharabhradaputrasa maha- rajasa tradatusa Avadagajasa</i>). Zeus, standing r.; holds sceptre; r. hand advanced.</p>
8	149.3	AR.85		to l. 𐰽𐰺𐰠𐰪𐰍𐰎; to r. 𐰽𐰺𐰠𐰪𐰍𐰎. [I. O. C.]
9	149.2	AR.85	to l. 𐰽𐰺.	" " " B; " " "
10	146.4	AR.8	" 𐰽.	" 𐰽 " " " "
11	142.5	AR.9	" 𐰽.	" " " " " "
12	158.5	AR.85	" S.	" " " " " "
13	142.4	AR.95	type r.	" " " 𐰽 𐰽.
14	150.2	AR.95	"	" " " " S. [I. O. C.]
15	124.4	AR.85	"	" " " 𐰽 𐰽.
16	121.5	AR.85	inscr. ΓΥΝΑΙΦΕΡΟΑ- ΔΕΛΦΙ[ΔΕΩΣ	" 𐰽; " Α 𐰽. [Pl. xxiii. 3.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
ORTHAGNES.				
(a) Bronze.				
			<p>BACILEVC BACI- ΛΕΩΝ ΜΕΓΑΣ ΟΡΘΑΓΝHC East of the king l., diad.; wears torquis.</p>	<p>ΥΥΥΥΥΥ ΥΥΥ~ ~ΥΥΥ ΥΥΥΥ ΥΥ~ (<i>Maharajasa rajaditajasa maha- tasa Gudaphara sagaba. f.</i>)* Nike r.; holds wreath and palm.</p>
1	Æ 9			to l., Υ Υ; to r., Υ. [Pl. xxiii. 9.]
2	Æ 1.05			" " " " Υ.
3	Æ 95			" Υ Ϙ; " "
4	Æ 9			" Υ; " " (last letter of inscr. absent).
5	Æ 9			" " " " " "
6	Æ 1.05		inscr. ends ΟΡΘΑΓΝ.	to l., uncertain letter; to r., Υ.
			<p>Β ΜΕΓΑΛΟΥ ΟΡΘΑΓΝΟΥ Similar.</p>	<p>Illegible inscr. Similar type.</p>
7	Æ 95			to l., Ψ; to r., ~.

\* This is Gen. Cunningham's reading: *sagaba* he supposes to stand for *sagarika*, 'brother.' On no. 2 of the British Museum coins there is another letter at the end, which looks like ζ (*sa* or *da*), but which may be a badly formed Υ.



No.	Wt.	Metal. Size.	Obverse.	Reverse.
			(β) <i>Bronze; types, lion and bull.</i>	
			ΛΟΥΥΙΥCΑΤΡΑΠ[ Humped bull r.; above, ἑξ.	ΥΥΖΖΥ ΥΛΥΥ ΥΛΥΥΥ[ ([Mani]) * gulaputrasa chhatrapasa Jihuniasa). Lion r.
3	Æ 1.		to r., Υ.	to l., Χ; to r., Ζ; below, 2. [Pl. xxiii. 5.]
4	Æ 1.		" Ζ.	" " " 3.

## UNCERTAIN KINGS.

(α) *Bronze; square.*

Illegible Greek inscription; in which sometimes the word CΑΤΡΑΠ and sometimes ΧΑΡΑΝΩ is visible. King r., on horseback; lance couched.

Illegible Indian inscription; the words ΥΛΥΥ (chhatrapasa) and ΥΛΥ (putrasa) sometimes visible. Lion r.

1	Æ 1.		to r., Ε.	above, Η; to r., Χ.
2	Æ 1.		" "	" " " "
3	Æ 1.		" "	" " " " [Pl. xxiii. 6.]
4	Æ 85		" "	" " " " [I. O. C.]
5	Æ 8		" Η.	" " " " "
6	Æ 8		" Υ.	" Ζ " " "

\* Or mahigulasa. This is supposed to give us the name of the father of Zaloniassa. The word Jihuniasa is not clear on any British Museum specimens in bronze.





No.	Wt.	Metal. Size.	Obverse.	Reverse.
(β) Bronze; round.				
			Debased Greek legend. Humped bull r.; above, ☞.	Undetermined Indian legend. Bac- trian camel r.
7	Æ 9		to r., uncertain letter.	to r., ☞; above, h.
8	Æ 85		" "	" "
9	Æ 9		" "	" uncertain letter.
10	Æ 95		" h.	" γ. [Pl. xxiii. 7.]
11	Æ 9		" ζ.	" h.
12	Æ 95		" "	" uncertain letter. (inser. $\Upsilon \Lambda \gamma \mu \Lambda \gamma \Upsilon \Lambda \gamma \sim$ &c.)
13	Æ 9			to r., uncertain letter.
14	Æ 9		" h.	above, uncertain letter; to r., $\Xi \gamma$ .
15	Æ 75		above, BA Λ; to r., un- certain letter.	to r., uncertain letter. (inser. $\Upsilon \Upsilon \gamma \sim$ &c.)
16	Æ 65		" "	to r., uncertain letter.

[Various readings of these two classes of coins have been published by Gen. Cunningham, *J. A. S. B.* 1854, pp. 695, 698; and by von Sallet, *Zeitsch. f. Num.* 1879, 369, 370. The British Museum specimens are not sufficiently well-preserved to enable us to give any certain readings].

No.	Wt.	Metal. Size.	Obverse.	Reverse.
SANABARES.				
(a) <i>Silver.</i>				
1	58.5	AR 75	Bust of the king l., wearing tiara of late Parthian form, and torquis; behind, $\Delta \Pi$ ( <i>ath</i> ).	<p><b>ΒΑΣΙΛΕΥΣ ΜΕΓΑΣ ΣΑΝΑΒΑ</b> King dressed in Parthian style, seated r. on throne with back; holds bow.</p> <p>in front, <math>\overline{\Lambda}</math>; above, <math>\Gamma \Pi</math>. [Pl. xxiii. 10.]</p>
(β) <i>Bronze; Parthian class.</i>				
2		Æ 65	Head of the king l., diad. Inscr. (1)	<p><b>ΒΑΣΙΛΕ ΣΑΝΑΒΑΡΗΣ</b> King seated r. on stool; holds bow.</p> <p>in front, <math>\Pi</math>. [Pl. xxiii. 11.]</p>
3		Æ 65		" "
4		Æ 6		<p>" <math>\overline{\Lambda}</math> <math>\Pi</math>. (barbarous).</p>
(γ) <i>Bronze; Bactrian class.</i>				
5		Æ 85	<b>ΒΑΣΙΛΕΥΣ . . .</b> (corrupt). Bust of the king l., wearing tiara.	<p><b>ΣΑΝΑΠΑΡΟΥ</b> Nike r., holds wreath.</p> <p>[Pl. xxiii. 12.]</p>




No.	Wt.	Metal. Size.	Obverse.	Reverse.
10		Æ 85	Bust of the king r., diad. and radiate; hand holds lance, bound with fillet; behind, ☸.	<b>ΒΑΣΙΛΕΥΣ ΒΑΣΙΛΕΥΩΝ</b> <b>ΩΤΗΡ ΜΕΓΑΣ</b> (frequently blundered). The king r., on horse- back, diad.; holds ankus? to r., ☸.
11		Æ 75		(inser. ends <b>ΒΑΣΙΛΕΩΝΩΤΗ</b> ).
12		Æ 8		(inser. barbarous). [L. O. C.]
13		Æ 55	Similar.	<b>ΒΑΣΙΛΕΥΣ ΒΑΣΙΛΕΥΩΝ</b> <b>ΩΤΗΡ Μ</b> Similar.
14		Æ 55		
15		Æ 6		
16		Æ 5		
17		Æ 5		
18		Æ 55		
19		Æ 6		[L. O. C. Pl. xxiv. 3.]
20		Æ 5		
21		Æ 5		[L. O. C.]
22		Æ 55		(inser. barbarous).

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			Bust of the king r., diad.; to r.,  .	<b>ΒΑΣΙΛ[ΕΩΝ]CΩTHPM[</b> Zeus, standing l.; holds in r. hand, thunderbolt over altar; in l., scap- tre.
23		Æ 7		
24		Æ 7		
25		Æ 7		(inser. . . <b>BACIAEYΩM</b> . . . .). [Pl. xxiv. 5.]
			Bust of the king l., wear- ing crested helmet; in r. hand, lance: fillet border.	<b>BACIAEV BACIAEVΩ[N</b> <b>C]ΩTHP MEΓAC</b> King on horseback r., holding ankus; to r.,  .
26		Æ 95	to l.,  ; to r.,  .	
27		Æ 95	" " " "	[I. O. C. Pl. xxiv. 6.]
<p style="text-align: center;">HERAÏUS (ERAÏUS).</p> <p style="text-align: center;">(a) <i>Silver.</i></p>				
			Bust of the king r., diad.; fillet-border.	<b>TY/ANNOYNTOC H/ADY</b> <b>ΣΑΗ A ΝΟ//ΑΝΟΥ*</b> The king r., on horseback; bow and quiver tied to saddle; behind, Nike r., crowning him.
I 1844	AR 12			in field r., B. [Pl. xxiv. 7.]

\* As to this legend, see Introduction.


No.	Wt.	Metal Size.	Obverse.	Reverse.
HYRCODES.				
(a) <i>Silver; type, a Deity standing.</i>				
			ΥΡΚΩΔΟΥ Bust of the king with peaked beard r., diad.	ΜΑΚΑΡΟΥ ΑΡΔΗΘΟΥ Figure of a Deity(l), facing; holds spear in r. hand; flames on shoulders.
1	44·9	AR·65		[Pl. xxiv. 8.]
2	43·5	AR·7		
3	45·2	AR·65		[I. O. C.]
4	27·5	AR·7		
<hr/>				
			ΥΛΚΩΔΟΥ Similar.	ΟΔΚΑΡΟ ΟΥΗΟΡ Similar.
5	44·	AR·7		
6	42·5	AR·65		[I. O. C.]
7	39·7	AR·65		[Pl. xxiv. 9.]
8	51·5	AR·7		
			Barbarous imitation of the above.	Barbarous imitation.
9	30·	AR·55		[I. O. C.]
10	20·2	AR·55		
11	23·2	AR·6		
12	26·	AR·6		[Pl. xxiv. 10.]
13	17·5	AR·55		

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			Barbarous imitation further degraded.	Barbarous imitation.
14	34.4	AR 55		[I. O. C.]
15	12.	AR 5		
16	17.6	AR 55		
17	12.3	AR 5		
18	10.	AR 55		
19	13.8	AR 45		
20	10.1	AR 4		[Pl. xxiv. 11.]
(β) <i>Silver; type, horse.</i>				
			VPKΩΔ Bust of the king r., diad.	VPKΩΔ Forepart of bridled horse r.
21	23.3	AR 55		
22	23.8	AR 5		[Pl. xxiv. 12.]
23	22.5	AR 5		
24	14.	AR 45		[I. O. C.]
25	10.8	AR 5		
26	14.2	AR 45		
27	14.	AR 5	(barbarous legend).	(barbarous legend). [Pl. xxiv. 13.]
28	11.6	AR 5	"	"

No.	Wt.	Metal. Size.	Obverse.	Reverse.
KINGS OF UNCERTAIN NAME.				
SAPADBIZES (†).				
(a) <i>Silver.</i>				
			Bust of a king r., in helmet like that of Eucratides.	NANAIA NANAIA Lion r.
1	25.3	AR 65	behind, ΑΓΕΕΙ ΗΛ	above,  Λ.
2	26.2	AR 6	„ ΣΑΠΑΔΒΙΖ	„ „ [I. O. C. Pl. xxiv. 14.]
3	31.5	AR 6	„ ΣΑΠΑΔΒΙΖΗΕ	„ „ [I. O. C. Pl. xxiv. 15.]
PHSEIGACHARIS (†).				
(a) <i>Silver.</i>				
			Bust of Scythian king r., diad.	ΦΣΕΙΓΑ Herakles, facing; holds ΧΑΡΙΣ in r. hand, club; in l., lion's skin.
1	37.6	AR 6		[I. O. C. Pl. xxiv. 16.]
2	36.8	AR 6		



No.	Wt.	Metal Size.	Obverse.	Reverse.
			<p>ΒΑΣΙΛΕΩΣ ΣΤΗ- ΡΟΣ ΣΥ ΕΡΜΑΙΩΝ (often corrupted). Bust of Hermaeus r., diad.</p>	<p>ΥΡΖΛΣΤΑ ΥΡΖΛΣΤΑ ΥΡΖΛΣΤΑ [ΥΖ] (<i>Kujula- kasasa kushana yavv</i>) (<i>Yyasa dha- (dha)mathidasa</i>). Herakles, facing, diad.; holds in r. hand, club; in l., lion's skin.</p>
11	Æ 9		lower line of inser. ΖΑΕΩΝ	
12	Æ 9		inser. retrograde.	in ed. [Pl. xxv. 2.]
13	Æ 9		inser. retrograde and bar- barous.	" "
14	Æ 1		twice struck.	inser. varied; in field, γ.
15	Æ 8		degraded copy.	degraded copy.
16	Æ 75		"	
17	Æ 85		"	
18	Æ 7		"	
19	Æ 7		"	
20	Æ 6		"	
21	Æ 6		"	



No.	Wt.	Metal. Size.	Obverse.	Reverse.
KADPHISES I.				
(a) Copper; type, Herakles.				
			Inscr. as below. Bust of Hermaios facing dial.	<p>              ὩΡΑΛΕΤΗΡΑΥΗ (Kujula-            kassa kushana yarugasa dhra(dha)-            mathidasa). Herakles, facing, dial.;            holds in r. hand, club; in l., lion's            skin.         </p>
1	Æ 97		ΚΑΡΕΝΛΚΑΖΟΝΛΑ- ΚΑΔΦΙΖΑΝ	in field, Ζ Γ. [I. O. C. Pl. xxv. 3.]
	Æ 95		ΚΑΖΟΝΛΑΚΑΔΦΙ- ΖΑΝ	[I. O. C.] (inscr. varied).
	Æ 9		ΚΟΡΘΙΛΚΑΖΟΝΛΑ	„ Ζ Γ. [Pl. xxv. 4.]
4	Æ 85		ΙΟΚΑΔΦΙΣΗΟΝ	„ Η. (inscr. varied).
5	Æ 9		ΑΔΦΙΣ	„ uncertain letter. „ „
6	Æ 9		ΦΙΖΑΝΚΟΛΕ	„ Ζ Γ.
7	Æ 9		Κ..ΖΟΥΛΟΚΑΔ ΖΝ	„ Ζ Β. [I. O. C.]
8	Æ 85		Inscr. blundered.	„ Γ. [I. O. C.]


















No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<p>ΒΑΣΙΛΕΥΣ ΒΑΣΙ- ΛΕΩΝ ΣΩΤΗΡ ΜΕΓΑΣ ΘΘΗΜΟ ΚΑΔΦΙΧΘ The king l., sacrificing at altar; to l., trident and axe combined; to r., club and .</p>	<p>𐤀𐤁𐤁𐤃 𐤃𐤃𐤃𐤁𐤃𐤃𐤃𐤃𐤃𐤃 𐤃𐤃𐤃𐤃𐤃𐤃𐤃𐤃𐤃𐤃 𐤃𐤃𐤃𐤃𐤃𐤃𐤃𐤃𐤃𐤃 (Maha- rajasa rajasirajasa, sarvalopa is- varasa mahisvarasa himakaprasa tradata). Siva facing, holding trident; drapery hanging at his back; behind him, bull; to l., .</p>
14	Æ 1.05			[I. O. C.]
15	Æ 1.1			"
16	Æ 1.1			"
17	Æ 1.05			
18	Æ 1.25	(twice struck).		
19	Æ 1.			
20	Æ 1.05			
21	Æ 1.1			
22	Æ 1.05			
23	Æ 1.15			
24	Æ 1.15			
25	Æ 1.1			
26	Æ 1.			<p>in inser. 𐤃𐤃𐤃𐤃 between second and third words.</p>












No.	Wt.	Metal. Size.	Obverse.	Reverse.
KANERKES.				
(a) Gold; inscription, βασιλεὺς βασιλείων.				
1	121.8	A <sup>8</sup>	<p><b>BACIAEYC BACI ΛEΩN KANHP- KOY</b> The king l., wearing helmet and dia- dem, clad in coat and trousers, and cloak, sa- crificing at altar; flames rise from shoulders; holds in l. hand, spear.</p>	<p><b>CAAHNH</b> Selene * (male) l., diad., clad in chiton and himation; crescent behind shoulders; r. hand advanced; holds in l. long sceptre, bound with fillet; sword girt round waist; to l., ☾.</p> <p>[I. O. C. Pl. xxvi. 1.]</p>
(β) Bronze; inscription, βασιλεὺς βασιλείων.				
2		Æ 9	<p><b>BACIAEYC BACI ΛEΩN KANHP- KOY</b> The king as above.</p>	<p><b>HAIOC</b> Helios l., diad., clad in chiton and himation; radiate disk behind head; r. hand advanced, l. on hip; to l., ☼.</p> <p>[I. O. C. Pl. xxvi. 2.]</p>
3		Æ 9		
4		Æ 9		
			Similar.	<p><b>NANAIA</b> Nanais r., nimbate and diad.; holds in r. hand sceptre ending in forepart of horse; to r., ☼.</p> <p>[I. O. C. Pl. xxvi. 3.]</p>
5		Æ 9		"
6		Æ 9		"
7		Æ 9		"
8		Æ 85		
9		Æ 9		





\* The figure of Selene is identical with that which appears on the col  
inscribed **MAO**; it is that of a male moon-deity.







No.	Wt.	Metal. Size.	Obverse.	Reverse.
(γ) Gold; inscription, <b>PAONANO</b> &c.				
			<b>ΠΑΟΝΑΝΟΡΑΟΚΑ ΝΗΡΚΙΚΟΡΑΝΟ</b> The king standing l., wearing helmet and diadem, clad in coat and trousers, and cloak; flames rise from his shoulders; he holds in r. hand elephant-goad over altar; in his l. spear; sword at his waist.	<b>ΑΘΡΟ</b> Bearded deity, fire-god, l., diad., clad in chiton and himation; holds in r. hand, wreath; in l., which rests on hip, tongs; to l.,  .
10	122.8	N 8		[Pl. xxvi. 4.]
11	121.9	N 75		
12	27.7	N 5		[I. O. C. Pl. xxvi. 5.]
			Similar.	<b>ΑΡΔΟΧΡΟ</b> Female figure r., wearing medius and nimbate, clad in chiton and himation; holds cornucopias; to r.,  .
13	122.8	N 8		[Pl. xxvi. 6.]
			Similar.	<b>ΑΡΟΘΑΣΠΟ</b> Bearded deity r., diad., clad in sleeved tunic; holds in r. hand, wreath; beside him, horse r., saddled, trotting; to l.,  .
14	120.2	N 75		[Pl. xxvi. 7.]
15	122	N 75	(same die).	(same die). [I. O. C.]
			Similar.	<b>ΒΟΔΔΟ</b> Buddha, facing, nimbate, clad in chiton and himation; r. hand advanced; in l., wallet; to r.,  .
16	109.2	N 8		[I. O. C. Pl. xxvi. 8.]



No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<b>PAONANOPAKA NHPIKOPANO</b> The king standing l., wearing helmet and diadem, clad in coat and trousers, and cloak; flames rise from his shoulders; he holds in r. hand elephant-goad over altar; in his l. spear; sword at his waist.	<b>MAO</b> Male deity (moon-god) l., diad., clad in chiton and himation; crescent behind shoulders; r. hand advanced; holds in l. long sceptre, bound with fillet; sword girt round waist; to l.  .
17	121.9	N 75		[Pl. xxvi. 9.]
18	122.3	N 8		(no sword).
			Similar.	<b>MEIPO</b> Mithras, diad. and with radiate disk, to l.; r. hand advanced; in l. sceptre bound with fillet; sword girt round waist; to l.  .
19	118	N 8		
			Similar.	<b>MIIPO</b> Mithras, to l.; r. hand advanced; l. rests on hip; sword at waist; to l.  .
20	122.3	N 8		[Pl. xxvi. 10.]
			Similar.	<b>NANA</b> Nanaia r., nimbate and diad., head surmounted by crescent; holds sceptre ending in forepart of horse, and palera; to r.  .
21	13.2	N 8		
			Similar.	<b>NANAPAO</b> Similar figure of Nanaia; to r.  .
22	120.3	N 75		(sword at waist). [Pl. xxvi. 11.]
23	122.2	N 75		
24	30.2	N 5		" " [I. O. C. Pl. xxvi. 12.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<b>ΠΑΟΝΑΝΟΡΑΟΚΑ ΝΗΡΚΙΚΟΡΑΝΟ</b> The king standing l., wearing helmet and diadem, clad in coat and trousers, and cloak; flames rise from his shoulders; he holds in r. hand elephant-goad over altar; in his l. spear; sword at his waist.	<b>ΟΚΡΟ</b> Siva l., nimbate; hair in horn on top of head; has four arms and hands, in which he holds respectively a vase, a drum, a trident, and a goat, the last by the horns; to l.,  .
25	123	A 8		[Pl. xxvi. 13.]
26	123.4	A 75		[I. O. C.]
27	122	A 75		"
28	29	A 6		[I. O. C. Pl. xxvi. 14.]
			Similar.	<b>ΟΡΛΑΓΝΟ</b> War-god (Bahram f) r., wearing diadem, helmet surmounted by eagle, and clad like the king; holds in r. hand, spear; in l. sword; to l.,  .
29	121.3	A 85		[Pl. xxvi. 15.]
			Similar.	<b>ΦΑΡΡΟ</b> Male figure, to r., diad. and nimbate, clad in chiton and himation; holds spear in l. hand, and mountain or fire in r.; to r.,  .
30	122.8	A 8		[Pl. xxvi. 16.]
			<b>ΠΑΟΝΑΝΟΚΑΝΗΡ ΚΙ ΚΟΡΑΝΟ</b> Bust of the king l., diad. and wearing helmet; l. hand raised, holds spear; body emerges from clouds.	<b>ΑΘΡΟ</b> Bearded deity l., clad in chiton and himation; holds in r. hand wreath; in l. which rests on hip, tongs; to l.,  .
31	30.8	A 5		[I. O. C. Pl. xxvi. 17.]
			Similar.	<b>ΟΚΡΟ</b> Siva, as above, not nimbate; to l.,  .
32	30.1	A 5		[Pl. xxvi. 18.]


No.	Wt.	Metal. Size.	Obverse.	Reverse.
<i>Later period.</i>				
33	30.6	N 5	<b>PAO NANOPATO</b> <b>[KA]NHHPKOKOPANO</b> The king standing l. at altar, nimbate; holds r. hand over altar; in l. spear bound with fillet; to l., trident bound with fillet.	<b>A]PAOKPO</b> Goddess, seated facing on throne, nimbate; under feet, footstool; holds wreath and cornucopiae to l.,  .
				[I. O. C. Pl. xxvi. 19.]
(d) <i>Bronze; inscr. PAO &amp;c.</i>				
34	Æ 1.05		<b>PAOKA NHPKI</b> The king, clad as in last class, standing l. by altar; holds in l. hand spear; r. extended over altar.	<b>AΘPO</b> Bearded deity l.; holds in r. hand, wreath; in l., which rests on hip, tongs (!); to l.,  .
35	Æ 1.			[Pl. xxvii. 1.]
36	Æ 1.05		inscr. barbarous.  Similar.	<b>ΟΔΥΟΒΟΥ</b> Buddha facing, nimbate; his r. hand raised as in teaching; in l., wallet; to l.,  .
37	Æ .85			[Pl. xxvii. 2.]
38	Æ .9		Similar.	[I. O. C.]
39	Æ 1.05		king nimbate; to l.,  .	[Pl. xxvii. 3.]
40	Æ 1.05			deity does not hold sceptre.
41	Æ .85			





No.	Wt.	Metal Size.	Obverse.	Reverse.
			<b>PAOKA NHPKI</b> The king standing l. as before; holds in l. hand spear; r. extended over altar.	<b>MAO</b> Male deity l., clad as king; crescent behind shoulders; r. hand advanced; in l., long sceptre bound with fillet; sword at waist; to l.,  .
42	Æ 75		to l.,  . (inscr. retrogr.)	(inscr. retrogr.)
43	Æ 75		" "	deity does not hold sceptre.
44	Æ 75		" "	" " "
45	Æ 5		" "	" " "
			Similar.	<b>MIPO</b> Sun-god, Mithras, l., diad. with radiate disk, clad as king; r. hand advanced; in l., sword; to l.,  .
46	Æ 105			[Pl. xxvii. 4.]
47	Æ 105			
48	Æ 1			inscr. <b>MIPO</b> .
49	Æ 1.1			" "
50	Æ 8			" "
51	Æ 85			
52	Æ 65			
53	Æ 7			inscr. <b>MIPO</b> .
			Similar.	<b>NANA</b> Nanaia r., nimbate and diad.; holds sceptre, ending in forepart of horse, and patera; to r.,  .
54	Æ 105			[I. O. C. Pl. xxvii. 5.]
55	Æ 95			
56	Æ 1			

No.	Wt.	Metal Size.	Obverse.	Reverse.
			<b>PAOKA NHPKI</b> The king standing l. by altar; holds in l. hand spear; r. extended over altar.	<b>NANA</b> Nanaia r., nimbate and diad.; holds sceptre, ending in forepart of horse, and patera; to r.,  .
57	Æ 7		to l.,  .	
58	Æ 7		" "	
59	Æ 7		" "	
60	Æ 55			
61	Æ 6		Similar.	<b>oAΔO</b> Wind-god running l., his hair loose; holds in both hands ends of his garment which floats about him; to l.,  .
62	Æ 1·05			[I. O. C. Pl. xxvii. 6.]
63	Æ 1·05			[I. O. C.]
64	Æ 1·05			
65	Æ 65		Similar.	<b>OKPO</b> Siva l., nimbate; has four arms and hands, in which he holds a wreath, a drum, a trident, and a vase; to l.,  .
66	Æ 1·			[I. O. C.]
67	Æ 1·			
68	Æ 8			
69	Æ 8		Similar.	[I. O. C. Pl. xxvii. 7.]
70	Æ 75		to l.,  .	<b>OKPO</b> Siva l., nimbate; holds in r. hand, trident; to l.,  .
71	Æ 75		" "	(not nimbate).

No.	Wt.	Metal. Sloo.	Obverse.	Reverse.
HOOERKES.				
(a) <i>Gold.</i>				
1	121.5	N 8	<b>PAONANOPAOO</b> Upper part of king l., emerging from clouds; is diad. and nimbate; wears conical helmet and coat of mail; holds ear of corn and spear.*	<b>AΘOPO</b> Hephaestus standing r., flames rising from shoulders; holds hammer and tongs; to r.,  .
				[Pl. xxvii. 8.]
2	123.5	N 85	<b>PAONANOP AOOOH- PKIKO</b> Similar.	<b>AΘPO</b> Similar.
3	120.0	N 85	<b>PAONANOPAOOO HPKIKOPANO</b> Similar.	Similar; symbol to l.
			Similar.	<b>APAEIXPO</b> Sun-god l., diad. and with radiate disk; r. hand ad- vanced, and two fingers raised; l. rests on hip; to l.,  .
4	123.5	N 85		[Pl. xxvii. 9.]
5	122.8	N 9		[I. O. C.]

\* It has been judged unnecessary to describe at length the details of the king's costume in this and other coins.

No.	Wt.	Metal Size.	Obverse.	Reverse.
			<b>ΠΑΟΝΑΝΟΡΑΟ ΟΟ ΗΡΚΙΚΟΡΑΝΟ</b> Upper part of king L, emerging from clouds; diad. and nimbate; wears conical helmet and coat of mail; holds ear of corn and spear.	<b>ΑΡΔΟΧΡΟ</b> Female deity r., in Greek attire; holds in both hands cornucopias; to r.,  .
6	124.5	A .8		[Pl. xxvii. 10.]
7	122.	A .85		
8	122.5	A .8		
9	122.4	A .8		to r., fire (l).
10	58.3 (plated)	A .8		
11	122.	A .85		inscr. <b>ΑΡΔΟΧΡΑ</b> . [I. O. C.]
12	123.5	A .85		type L, and symbol to L. [I. O. C.]
13	30.6	A .55	inscr. <b>ΠΑΟΝΑΝΟ ΟΟΗ</b>	[I. O. C.]
			<b>ΠΑΟΝΑΝΟ ΡΑΟΟ ΟΗΡΚΙΚΟΡΑΝΟ</b> Upper part of king L, emerging from clouds, diad.; wears rounded helmet; holds ear of corn and elephant-goad.	Similar.
14	122.5	A .85		deity with modius and nimbus.
15	120.7	A .8	inscr. <b>ΟΥΟΗΡΚΙ</b> for <b>ΟΟΗΡΚΙ</b> .	inscr. <b>ΟΥΟΔΡΑ</b> .
16	120.6	A .8		type L, and symbol to l.
17	30.6	A .5		deity with modius and nimbus. [Pl. xxvii. 11.]
			<b>ΠΑΟΝΑΝΟΡΑΟ ΟΟΗΡΚΟΚΟΡΑΝΟ</b> The king r., riding on elephant; holds sceptre and elephant-goad.	Similar. Deity with modius and nimbus.
18	120.9	A .8		[Pl. xxvii. 12.]




No.	Wt.	Metal Size.	Obverse.	Reverse.
			Inscr. obscure. Upper part of king l., emerging from clouds, diad.; wears rounded helmet; holds ear of corn and elephant-goad.	<b>ΔΟΧΡΟ</b> Female figure l., nimbate; holds wreath and cornucopias; to l.,  .
19	122.5	A 8		[Pl. xxvii. 13.]
20	123.3	A 8		
			<b>ΠΑΟΝΑΝΟΠΑΟΟΟ</b> <b>ΗΡΚΙΚΟΠΑΝΟ</b> Upper part of the king l., emerging from clouds, diad. and nimbate; wears conical helmet and chlamys over armour; holds ear of corn and spear.	<b>ΜΙΟΡΟ</b> Female deity r., diad. and nimbate, in Greek attire; holds cornucopias in both hands; to r.,  .
21	123	A 8		[Pl. xxvii. 14.]
			<b>ΠΑΟΝΑΝΟΠΑ</b> <b>ΟΟΟΗΡΚΙ</b> The king seated cross-legged to l., diad. and nimbate; flames rising from shoulders; wears conical helmet, and holds ear of corn and spear.	<b>ΗΡΑΚΛΙΟ</b> Bearded Heracles l., naked; holds in r. hand, club; over l. arm, lion's skin; in l. hand, apple; to l.,  .
22	123.3	A 8		[Pl. xxvii. 15.]
			<b>ΠΑΟΝΑΝΟΠΑΟΟ</b> <b>ΟΗΡΚΙΚΟΠΑΝΟ</b> Upper part of the king l., emerging from clouds, diad.; wears rounded helmet; holds ear of corn and elephant-goad.	<b>ΜΑΑΧΗΝΟ</b> Male deity (Mahá-sená) facing, nimbate and diad., clad in coat and chlamys; holds in r. hand, standard surmounted by bird; in l., sword; to l.,  .
23	125.5	A 8		[I. O. C. Pl. xxvii. 15.]
24	112.7	A 7.5		


No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<b>ΠΑΝΑΝΟΡΑΟΟ</b> <b>ΟΗΡΚΙΚΟΡΑΝΟ</b> Upper part of the king l., emerging from clouds, diad.; wears rounded helmet; holds ear of corn and elephant-goad.	<b>ΜΑΝΑΟΒΑΓΟ</b> Moon-god facing, seated on throne; feet resting on footstool; wears helmet; crescent behind shoulders; has four arms and hands, in three of which he grasps sceptre, wreath? and fire?, fourth hand rests on hip; to r., 𐀭.
25	122·	N 75		[Pl. xxvii. 17.]
26	122·5	N 8		
			<b>ΠΑΝΑΝΟΡΑΟΟ</b> <b>ΟΗΡΚΙΚΟΡΑΝΟ</b> Upper part of the king l., emerging from clouds, diad. and nimbate; wears conical helmet and coat of mail; holds ear of corn and spear.	<b>ΜΑΟ</b> Moon-god l., crescent behind shoulders; clad in coat; holds wreath and sceptre; sword at waist; to l., 𐀭.
27	122·3	N 85		[Pl. xxvii. 18.]
			Similar.	
28	122·2	N 85		
29	123·2	N 8		
			Similar.	
30	122·6	N 85		<b>ΜΑΟ</b> Moon-god l.; holds sceptre in l.; r. hand advanced; to l., 𐀭. [L. O. C. Pl. xxvii. 19.]
			<b>ΠΑΝΑΝΟΡ</b> <b>ΑΟΟΟΗΡΚΟ</b> Similar type.	<b>ΜΑΟ</b> Moon-god l.; r. hand ex- tended; in l., sword; to l., 𐀭. [L. O. C. Pl. xxvii. 20.]
31	30·2	N 5		




No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<b>PAONANOPAOO</b> <b>OHPIKOPANO</b> Upper part of the king L. emerging from clouds, diad. ; wears rounded helmet, and chlamys over armour ; holds ear of corn and elephant- goad.	<b>MAO</b> Moon-god L. ; holds sceptre in l. hand ; to L., 𐎢𐎠𐎧.
32	120.4	N 9		
			Similar.	<b>MAO</b> Moon-god L. ; holds sceptre in r. hand ; to L., 𐎢𐎠𐎧. [PL. XXVII. 21.]
33	121.2	N 8		
34	122.5	N 8		
			Similar.	<b>MAO</b> Moon-god L. ; r. hand ex- tended ; in L., sceptre, held trans- versely ; to L., 𐎢𐎠𐎧. [L. O. C.]
35	122.4	N 75		
36	121.2	N 8		
37	121.2	N 8		
38	123.	N 85		
			Similar.	sceptre bound with fillet. " " [PL. XXVII. 22.] (inscr. <b>MAOO</b> ).
39	122.8	N 85		
40	121.4	N 8		
			Similar.	<b>MAO</b> Moon-god L. ; r. hand ex- tended ; sword in L. ; to L., 𐎢𐎠𐎧. (inscr. <b>MAOO</b> ).
41	122.	N 8		
				<b>MAO</b> Moon-god r., diad. ; holds in r. hand, wreath ; in L., sceptre ; to r., 𐎢𐎠𐎧. [PL. XXVII. 23.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
42	121.1	N 8	<p><b>PAONANOPAOO</b> <b>OHPIKOPANO</b> Upper part of the king l., emerging from clouds, diad.; wears rounded helmet, and chlamys over armour; holds ear of corn and elephant- god.</p>	<p>Bearded moon-god r., diad.; crescent behind shoulders; holds in r. hand, sceptre, bound with fillet; in l. elephant-god: and sun-god l., ra- diate; r. hand advanced; in l., sceptre, bound with fillet; behind the two, the names <b>MAO</b> and <b>MIPO</b> respectively; between them, 𐤀.</p> <p>[Pl. xxvii. 24.]</p>
43	123.	N 85	<p><b>PAONANOPAOOO</b> <b>HPKEKOPANO</b> Upper part of the king l., emerging from clouds, diad. and nimbate; flames rising from shoulders; wears con- ical helmet; holds ear of corn and spear.</p>	<p><b>MIPO</b> Sun-god l., nimbate; holds wreath and sceptre; sword at waist; to l., 𐤀.</p>
44	122.3	N 85	Similar; no flames.	<p><b>MOPO</b> Sun-god l., radiate; holds wreath and sceptre; sword at waist; to l., 𐤀.</p> <p>[Pl. xxviii. 1.]</p>
45	123.	N 8	Similar.	<p><b>MIPO</b> Sun-god l., radiate; holds wreath and sceptre, bound with fillet; to l., 𐤀.</p> <p>[I. O. C.]</p>
46	121.7	N 8	Similar; king holds stan- dard instead of spear.	<p><b>MIPO</b> Sun-god l., diad. and nimbate; holds wreath and sword; to l., 𐤀.</p>
47	122.8	N 8		

No.	Wt.	Metal. Size.	Obverse.	Reverse.
48	122.2	A' 9	<p><b>ΠΑΟΝΑΝΟΡΑΟΟΟ</b>  <b>ΗΡΚΙΚΟΡΑΝΟ</b>  Upper part of the king  l., emerging from clouds,  diad. and nimbate;  wears conical helmet;  holds ear of corn and  spear.</p>	<p><b>ΜΙΥΡΟ</b> Sun-god l., diad. and  radiate; holds wreath and sword;  to l., 𐎲.</p>
			Similar.	<p><b>ΜΙΙΡΟ</b> Sun-god r., radiate; holds  spear and sword; to r., 𐎲.</p> <p>[I. O. C. Pl. xxviii. 2.]</p>
49	121.3	A' 85	<p><b>ΠΑΟΟΟΗ</b> Similar.</p>	
50	30.2	A' 5	<p><b>ΠΑΟΝΑΝΟΡΑ</b>  <b>ΟΟΟΗΡΚΙ</b> Upper  part of the king l.,  emerging from clouds,  diad.; wears rounded  helmet; holds ear of  corn and elephant-good.</p>	<p><b>ΜΥΡΟ</b> Sun-god l., nimbate; r.  hand advanced; in l., sceptre;  to l., 𐎲.</p> <p>[I. O. C. Pl. xxviii. 3.]</p>
51	30.7	A' 55	<p><b>ΠΑΟΝΑΝΟΡΑ</b>  <b>ΟΟΟΗΡΚΙ</b> Upper  part of the king l.,  emerging from clouds,  diad.; wears rounded  helmet; holds ear of  corn and elephant-good.</p>	<p><b>ΜΙΟΡΟ</b> Sun-god l., radiate; holds  wreath and sceptre; to l., 𐎲.</p> <p>[I. O. C.]</p>
52	120.8	A' 8	<p><b>ΠΑΟΝΑΝΟΡΑΟΟΥ</b>  <b>ΟΗΡΚΙΚΟΡΑΝΟ</b>  Similar.</p>	<p><b>ΜΙΟΡΟ</b> Sun-god l., radiate; r.  hand holds spear; l. grasps sword;  to l., 𐎲.</p>
53	122.8	A' 8		<p>[I. O. C.]</p>
54	122.2	A' 85	<p><b>ΠΑΟΝΑΝΟΡΑΟ</b>  <b>ΟΟΗΡΚΙΚΟΡΑΝΟ</b>  Similar.</p>	<p><b>ΜΙΟΡΟ</b> Sun-god l., radiate; l.  hand holds spear; r. rests on hip;  sword at waist; to l., 𐎲.</p> <p>[Pl. xxviii. 4.]</p>






No.	Wt.	Metal, Size.	Obverse.	Reverse.
			<b>PAONANOPAO</b> <b>OOHPKIKOPANO</b> Upper part of the king L. emerging from clouds, diad. ; wears rounded helmet ; holds ear of corn and elephant-goad.	<b>MIPO</b> Sun-god L. radiate ; r. hand extended ; in L. sceptre, held transversely, bound with fillet ; to L.,  .
55	123	N 8		
56	121.4	N 75		inscr. <b>MIPO</b> .
57	120.8	N 8	(bust only of king).	
58	120	N 8	" "	[I. O. C.]
59	122.7	N 8		inscr. <b>MYPO</b> . [I. O. C.]
60	30.2	N 5		
61	29.5	N 5		
			Similar.	<b>MIPPO</b> Sun-god L. radiate ; r. hand advanced ; L. holds sword ; to L.,  .
62	120.6	N 75		
63	122.3	N 8		inscr. <b>MIPO</b> . [I. O. C.]
64	119.5	N 8		" <b>MIPO</b> . "
			Same inscr. Upper part of king as above, to r.	<b>MIPO</b> Similar.
65	118	N 8		[I. O. C.]
			Same inscr. Upper part of king as above, to L.	<b>MIPO</b> Sun-god r. diad. and ra- diate ; holds wreath and sword ; to r.,  .
66	122.3	N 85		
67	122.4	N 8		[PL XXVIII. 5.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<b>ΠΑΟΝΑΝΟΡΑΟ</b> <b>ΟΟΗΡΚΙΚΟΡΑΝΟ</b> Upper part of king l., emerging from clouds, diad. and nimbate; wears conical helmet; holds ear of corn and spear.	<b>ΟΝΙΑ</b> Sun-god advancing l., ra- diate; r. hand advanced; l. holds sword; to l., ☸.
68	26	N 5		
69	28.8	N 5		[I. O. C.]
70	30.2	N 55		[I. O. C. Pl. xxviii. 6.]
			<b>ΠΑΟΝΑΝΟΡΑΟΟΟ</b> <b>ΗΡΚΕΚΟΡΑΝΟ</b> Upper part of king l., emerging from clouds, diad. and nimbate; flames rise from shoul- ders; wears conical hel- met; holds ear of corn and spear.	<b>ΤΕΙΡΟ</b>  <b>ΗΡΟ (ΜΕΙΡΟ)</b> Artemis stand- ing r., clad in long chiton and himation; holds in l. hand, bow; and with r., draws arrow from quiver; to r., ☸.
71	122.3	N 85		[Pl. xxviii. 7.]
			<b>ΠΑΟΝΑΝΟΡΑΟΟΟ</b> <b>ΗΡΚΙΚΟΡΑΝΟ</b> Upper part of king l., emerging from clouds, diad. and nimbate; wears conical helmet; holds ear of corn and spear.	<b>NANA</b> Nanaia l., wears stephane; holds sceptre, ending in forepart of horse, and patera; to l., ☸.
72	121.7	N 8		[Pl. xxviii. 8.]
			Similar.	<b>NANO</b> Nanaia r., diad. and nim- bate; crescent on head; holds sceptre and patera; to r., ☸.
73	124	N 85		[I. O. C.]
74	123	N 85	king's name <b>ΟΟΗΡΚΟ</b> .	inscr. <b>NANA</b> . [I. O. C.]
75	121.3	N 85	" <b>ΟΗΡΚΟ</b> .	" "





No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<b>PAONANOPAOOO HPKIKOPANO</b> Upper part of king L, emerging from clouds, diad. and nimbate; wears conical helmet; holds ear of corn and spear.	<b>NANO</b> Nanaia r., diad. and nim- bate; crescent on head; holds sceptre and patera; to r.,  .
76	122.9	A <sup>7</sup> 8	king holds double ear of corn.*	[Pl. xxviii. 9.]
77	122.5	A <sup>7</sup> 85	king's name <b>OOHPKO</b> .	[I. O. C.]
78	121.2	A <sup>7</sup> 85	" <b>OOHPKE</b> .	inscr. barbarous.
79	122.5	A <sup>7</sup> 8	" "	" "
80	122.6	A <sup>7</sup> 85	" "	" " [I. O. C.]
			<b>PAONANOPAOO OHPKOKOPANOPAO</b> King seated cross-legged on clouds, head r., diad. and helmeted; holds in L, standard, surmounted by bird.	<b>NANA</b> Nanaia r., diad. and nim- bate; crescent on head; sword at waist; holds sceptre and patera; to r.,  .
81	120.8	A <sup>7</sup> 85		
82	119.5	A <sup>7</sup> 8		[I. O. C. Pl. xxviii. 10.]
			<b>PAONANOPAOO OHPKIKOPANO</b> Upper part of the king L, emerging from clouds, diad.; wears rounded helmet; holds ear of corn and elephant-goad.	<b>NANAPAO</b> Nanaia r., diad. and nimbate; crescent on head; sword at waist; holds sceptre and patera; to r.,  .
83	118.8	A <sup>7</sup> 8		
84	121.3	A <sup>7</sup> 8		[I. O. C.]

\* This specimen proves that the object in the king's r. hand is an ear of corn, and not a club as it has usually been supposed to be.

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<b>ΠΑΟΝΑΝΟΠΑΟΟ</b> <b>ΟΗΡΚΙΚΟΠΑΝΟ</b> Upper part of the king L, emerging from clouds, diad.: wears rounded helmet; holds ear of corn and elephant-goad.	<b>NANA</b> Nanaia r., diad. and nim- bate; crescent on head; sword at waist; holds sceptre and patera; to r., 𐎲.
85	122.4	N 8		[L. O. C.]
86	122	N 8		
87	119.7	N 8		
88	121.4	N 8		inser. <b>NANO</b> .
			Similar.	<b>NANA</b> Nanaia L, diad. and nim- bate; crescent on head; holds sceptre in outstretched r. hand; in L, patera; to L, 𐎲.
89	121.6	N 85		[L. O. C.]
90	120	N 8		inser. <b>NANO</b> . [L. O. C. Pl. xxviii. 11.]
91	122.4	N 8		" "
92	121.2	N 8		" "
93	121.1	N 85	inser. barbarous.	inser. barbarous.
			Similar.	<b>ΟΔΙΙΟ</b> Nanaia r., diad. and nim- bate; holds sceptre, bound with fillet, and patera; to r., 𐎲.
94	119.6	N 85		[Pl. xxviii. 12.]







No.	Wt.	Metal Size.	Obverse.	Reverse.
			<b>ΠΑΟΝΑΝΟΡΑΟΟΟ ΗΡΚΕΚΟΡΑΝΟ</b> Upper part of king I., emerging from clouds, diad. and nimbate; wears conical helmet; flames rising from shoulders; holds ear of corn and spear.	<b>ΟΑΝΙΝΔΑ</b> Nike standing l.; holds wreath and trophy-stand, as on coins of Alexander; to r.,  .
95	122·	N·85		[Pl. XXVIII. 13.]
96	121·7	N·8		inscr. <b>ΟΑΝΙΝΔΟ</b> .
			<b>ΠΑΟΝΑΝΟΡΑΟΟ ΟΗΡΚΙΚΟΡΑΝΟ</b> Upper part of king I., emerging from clouds, diad.; flames rising from shoulders; wears rounded helmet; holds ear of corn and elephant-goad.	<b>ΟΚΡΟ</b> Siva l., nimbate; wears necklace, and has four arms and hands, in which are (1) vase and elephant-goad, (2) thunderbolt, (3) trident, (4) goat; to l.,  .
97	122·7	N·8		[Pl. XXVIII. 14.]
98	121·5	N·8		[I. O. C.]
99	120·1	N·8		
			inscr. barbarous. Similar	<b>ΟΚΡΟ</b> Siva l., with four arms and hands, in which are (1) wreath, (2)  , (3) trident, (4) goat; to l.,  .
100	123·	N·85		
			<b>ΠΑΟΝΑΝΟΡΑ ΟΟΗΡΚ</b> Upper part of king I., emerging from clouds, diad. and nimbate; wears rounded helmet; holds ear of corn and standard surmounted by bird.	<b>ΟΚΡΑ</b> Siva facing, three-headed; has four arms and hands, in which are vase, thunderbolt, trident, and club; to l.,  .
101	122·2	N·85		[Pl. XXVIII. 15.]





No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<b>ΠΑΟΝΑΝΟΡΑ</b> <b>ΟΟΘΗΡΚΙΚΟΡΑΝΟ</b> Upper part of the king L. emerging from clouds, diad. and nimbate; wears conical helmet; holds ear of corn and spear.	<b>ΟΚΡΟ</b> Siva facing, three-headed, nimbate; clad only in waistband, ithyphallic; has four arms and hands, in which are goat, wheel, trident, and thunderbolt; to r., 𐎧𐎡𐎴. 𐎧𐎡𐎴.
102	123.5	A '85	Similar.	[Pl. xxviii. 16.]  <b>ΠΑΟΡΗΟΡΟ</b> Ares standing r., in Greek helmet and armour; holds spear, and shield which rests on ground; to r., 𐎧𐎡𐎴.
103	123	A '8		[Pl. xxviii. 17.]
104	121.7	A '8	inscr. barbarous.	inscr. <b>VAOPHOO</b> . [L. O. C.]
105	122.5	A '85	(last letters of inscr. want- ing).	
			<b>ΠΑΟΝΑΝΟΡΑΟΟ</b> <b>ΟΗΡΚΟΚ</b> Similar type.	<b>ΠΑΟΡΗΟΑΡ</b> Similar.
106	123.8	A '85		
			<b>ΠΑΟΝΑΝΟΡΑΟΟΟ</b> <b>ΗΡΚΕΚΟΡΑΝΟ</b> Similar type.	<b>ΠΑΟΡΗΟΡΟ</b> Ares l., in Greek helmet and armour; holds shield in r. hand, spear in l.; to l., 𐎧𐎡𐎴.
107	122.5	A '85		[Pl. xxviii. 18.]
			Same inscr. Upper part of king, as above; holds ear of corn and sceptre.	<b>ΠΑΟΡΗΟΡΟ</b> Ares r., in Greek helmet and armour, nimbate; holds spear and sword; to l., 𐎧𐎡𐎴.
108	123	A '8		[Pl. xxviii. 19.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			Inscr. obscure. Upper part of king I., emerging from clouds, diad.; wears rounded helmet; holds ear of corn and elephant-goad.	<b>PIOM</b> Roma or Pallas standing r., wearing helmet and long chiton; holds spear and shield; to r.,  .
109	123.5	A 85		[Pl. xxviii. 20.]
			<b>ΡΑΟΝΑΝΟΡΑ ΟΟΥΟΗΡΚΙΚΟΡ</b> Similar.	<b>ΣΑΡΑΠΟ</b> Sarapis standing l., diad. and clad in himation; r. hand advanced; in l., sceptre; to l.,  .
110	123.1	A 85		[Pl. xxviii. 21.]
111	121.6	A 85		[I. O. C.]
			<b>ΡΑΟΝΑΝΟΡΑΟΟ ΟΗΡΚΙΚΟΡΑΝΟ</b> Upper part of king I., emerging from clouds, diad.; wears rounded helmet; holds ear of corn and elephant-goad.	<b>ΣΚΑΝΔΟΚΟ Μ ΒΙΖΑΓΟ</b> <b>ΑΡΟ</b> Skanda and Viṣākha * standing face to face, nimbate; each wearing chlamys and neck-lace, and sword at waist; but Skanda holds in r. hand, standard surmounted by bird; Viṣākha holds in l. hand, spear; between them,  .
112	123.	A 8		[Pl. xxviii. 22.]
113	121.3	A 8		
			Similar; last letter of inscr. wanting.	<b>ΣΚΑΝΔΟΚΟΜΑΡΟ Β ΙΖΑΓΟ</b> Skanda and Viṣākha standing face to face, nimbate; Skanda holds in r. hand, standard; Viṣākha holds in l. hand, spear; between them,  .
114	31.	A 5		[I. O. C. Pl. xxviii. 23.]

\* A son and impersonation of Skanda. See Introduction.





No.	Wt.	Metal. Size.	Obverse.	Reverse.
115	121·	N 8	<p>ΠΑΟΝΑΝΟΡΑΟΟ ΟΗΡΚΙΚΟΡΑΝΟ</p> <p>Upper part of king l., emerging from clouds, diad.; wears rounded helmet; holds ear of corn and elephant-goad.</p>	<p>ΣΚΑΝΔΟΚ ΟΜΑΡΟΜΑ ΑΣ Η ΝΟΒΙΖΑΓΟ Niche on basis, within which, Skanda and Viṣṇu- kha standing as above; between them, Mahāsena, horned (?), facing, nimbate, clad in chlamys; sword at waist; to l., 𐎧.</p> <p>[Pl. XXVIII. 24.]</p>
116	123·2	N 8	<p>ΠΑΟΝΑΝΠΑΟΟ ΟΗΚΙΚΟΡΑΝΟ</p> <p>Upper part of king l., emerging from clouds, diad. and nimbate; wears conical helmet; holds ear of corn and spear.</p>	<p>ΦΑΡΡΟ Male deity l., head winged; clad in coat; holds in r. hand, fire; l. grasps sword at waist; to l., 𐎧.</p> <p>— [L. O. C. Pl. XXVIII. 25.]</p>
117	122·4	N 85	<p>ΗΡΚΙΚΟΡΑΝΟ</p> <p>Upper part of king l., emerging from clouds, diad. and nimbate; flames rise from shoul- ders; wears conical hel- met; holds ear of corn and standard.</p>	<p>ΦΑΡΡΟ Male deity l., head winged, diad.; flames rising from shoul- ders; wears coat and chlamys; holds in r. hand, fire; l. grasps sword at waist; to l., 𐎧.</p>
118	121·6	N 8	<p>ΠΑΟΝΑΝΟΡΑΟ ΟΟΗΡΚΙΚΟΡΑΝΟ</p> <p>Upper part of king l., emerging from clouds, diad. and nimbate; wears conical helmet; holds ear of corn and standard surmounted by bird.</p>	<p>ΦΑΡΡΟ Similar; deity nimbate.</p>

No.	Wt.	Metal. Size.	Obverse,	Reverse
119	123.4	N 8	<p>ΠΑΟΝΑΝΟΡΑΟΟΟ ΗΡΚΙΚΟΡΑΝΟ King as last; holding ear of corn and spear.</p>	<p>ΦΑΡΟ Male deity l., head winged, nimbate; wears coat and chlamys; r. hand advanced; in l., long sceptre; sword at waist; to l., .</p> <p>[I. O. C.]</p>
120	121.2	N 8	<p>Same inser. King as last; holding ear of corn and sceptre.</p>	<p>ΦΑΡΡΟ Male deity l., nimbate; flames rising from shoulders; holds in extended r. hand, fire; in l., sceptre; to l., .</p> <p>[Pl. XXVIII. 26.]</p>
121	123.3	N 8	<p>Same inser. King as be- fore; holding ear of corn and spear.</p>	<p>ΦΑΡΡΟ Male deity r., head winged, nimbate; clad in coat; holds sceptre and fire; to r., .</p> <p>[Pl. XXVIII. 27.]</p>
122	122.4	N 8	<p>Same inser. King as be- fore; holding double ear of corn and spear.</p>	<p>ΦΑΡΡΟ Male deity l., head winged, nimbate; clad in coat and chlamys; holds purse and cal- ceus; to l., .</p> <p>[I. O. C.]</p>
123	123.5	N 8	<p>ΠΑΟΝΑΝΟΡΑ ΟΟΟΗΡΚΕΚΟΡΑ King as before; holding ear of corn and spear.</p>	<p>ΦΑΡΟ Similar figure; holds purse and long sceptre; to l., .</p> <p>[Pl. XXVIII. 28.]</p>
124	121.5	N 8	<p>ΠΑΟΝΑΝΟΡΑΟΟΟ ΗΡΚΙΚΟΡΑΝΟ Similar.</p>	<p>ΦΑΡΡΟ Male deity r., head winged, diad. and nimbate; clad in coat; holds sceptre and elephant-goad; to l., .</p> <p>[Pl. XXVIII. 29.]</p>

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<b>ΠΑΟΝΑΝΟΡΑΟ</b> <b>ΟΟΗΡΚΟΚΟΡ</b> Upper part of king l., emerging from clouds, diad. and nimbate; wears rounded helmet; holds ear of corn and standard.	Inscr. barbarous. Male deity l., nim- bate; in extended r. hand, fire; in l., sword; to l.,  .
125	124.1	N 85		
			<b>ΠΑΟΝΑΝΟΡΑΟ</b> <b>ΟΗΡΚΙΚΟΡΑΝΟ</b> Upper part of king l., emerging from clouds, diad.; wears rounded helmet; holds ear of corn and elephant-goad.	<b>ΦΑΡΟ</b> Male deity l., head winged, nimbate; holds in r. hand, wreath; in l., sceptre; to l.,  .
126	121.2	N 8		
			Similar.	<b>ΦΑΡΡΟ</b> Male deity r., head winged, nimbate; r. hand rests on hip; in l., sceptre; to r.,  .
127	122.5	N 75		
128	121.7	N 8		[I. O. C.]
129	122.2	N 9		inscr. <b>ΦΑΡΟ</b> .
130	33.3	N 5		
131	27	N 5		[I. O. C. Pl. XXVIII. 30.]
			Similar	<b>ΦΑΡΟ</b> Male deity l.; l. hand rests on hip; in r., sceptre; to l.,  .
132	123.3	N 75		
133	121.4	N 8		inscr. <b>ΦΑΡΡΟ</b> . [I. O. C.]
134	122.1	N 8		" <b>ΟΡΑΦ</b> . (sword at waist).

No.	Wt.	Metal. Size.	Obverse.	Reverse.
135	120·8	A·8	<p>ΠΑΝΑΝΟΡΑΟΟ ΟΗΡΚΙΚΟΡΑΝΟ Upper part of king l., emerging from clouds, diad.; wears rounded helmet; holds ear of corn and elephant-goad.</p>	<p>ΦΑΡΟ Male deity l., head winged, nimbate, standing on fire; holds in r. hand, fire; in l., sceptre; to l., ☸.</p>
136	120·	A·8	Similar.	<p>ΦΑΡΟ Male deity l., head winged, nimbate, standing on fire; r. hand extended; in l., caduceus; to l., ☸.</p>
137	122·4	A·8	Similar.	<p>[I. O. C. Pl. xxviii. 31.]</p> <p>ΩΡΟΝ Male deity l., bearded, wearing modius and himation; r. hand advanced; in l., long sceptre; to l., ☸.</p> <p>[Pl. xxviii. 32.]</p> <p>[I. O. C.]</p>
138	122·	A·8		
139	122·2	A·8		
(β) Bronze; type, King on elephant.				
140	Æ 1·		<p>ΠΑΝΑΝΟ ΠΑΟΟΟ· ΗΡΚΕΝΟΡΑΝΟ* The king r., diad. and nimbate, riding on ele- phant; holds spear and elephant-goad.</p>	<p>ΑΘΡΟ Male deity l., diad.; holds in r. hand, wreath; and in l., tongs; to l., ☸.</p>
141	Æ 1·15			
142	Æ 1·			

\* This inscription cannot be read entire on any single specimen; and many specimens are blundered or barbarous; but the formula in the text seems to be the normal and usual one.

No.	Wt.	Metal. Size.	Obverse.	Reverse.
143	Æ 1.		<b>PAONANO PAOOO- HPKENOPANO</b> The king r., diad. and nimbate, riding on ele- phant; holds spear and elephant-goad.	<b>APOOXP</b> Female deity r., diad. and nimbate; holds cornucopias, to r.,  .
144	Æ .95			[I. O. C.]
			Similar.	Inscr. obscure. Female deity * l., nimbate; holds in extended r. hand, wreath; in l., cornucopias; to l.,  .
145	Æ 1.			[I. O. C.]
			Similar.	<b>HPAKAOI</b> Heracles r.; holds in r. hand, club; l. raised to head; to r.,  .
146	Æ .95			[Pl. XXIX. 1.]
			Similar.	<b>MAO</b> Moon-god l., crescent behind shoulders; r. hand extended; with l. grasps sword; to l.,  .
147	Æ 1.05			[I. O. C. Pl. XXIX. 2.]
148	Æ 1.			
149	Æ 1.			
150	Æ 1.			
151	Æ .85			
152	Æ .8			(deity holds wreath and sword).



\* Cf. the deity accompanied by the inscription **ΔΟΧΡΟ** on gold of this king.




No.	Wt.	Metal Size.	Obverse.	Reverse.
153		Æ 1·05	<b>PAONANO PAOOO- HPKENOPANO</b> The king r., diad. and nimbate, riding on ele- phant; holds spear and elephant-goad.	<b>MAO</b> Female deity l., nimbate; holds in both hands, cornucopiae; to l., ☸.
			Similar.	<b>MIIOPO</b> Sun-god l., radiate; r. hand extended; with l. grasps sword; to l., ☸.
154		Æ 1·		[I. O. C.]
155		Æ 1·		(inser. <b>MIIOPO</b> ).
156		Æ·95		" "
			Barbarous inscr. King on elephant to l.	<b>MPPO!</b> Sun-god l., nimbate; r. hand extended; in l., sceptre; to l., ☸.
157		Æ 1·	<b>PAONANO PAOOO- HPKENOPANO</b> The king r., diad. and nimbate, riding on ele- phant; holds spear and elephant-goad.	<b>OKPO</b> Siva standing l., four armed; holds wreath, thunderbolt, trident, and goat; to l., ☸.
158		Æ 1·05		
159		Æ 1·	Similar.	(Siva holds in fourth hand, vase). [Pl. XXIX. 3.]
				<b>OKPO</b> Siva standing l., two armed; holds in r. hand, trident; in l., vase and lion's skin (l); to l., ☸; to r., ☸.
160		Æ 1·05		[I. O. C.]
161		Æ 1·		
162		Æ·9		
163		Æ·85		
164		Æ·95		
165		Æ·95		










No.	Wt.	Metal Size.	Obverse.	Reverse.
			(γ) <i>Bronze; type, King seated.</i>	
166	Æ 1.		<b>ΠΑΟΝΑΝΟΡΑΟ</b> <b>ΟΟΗΡΚΕΝΟΡΑΝΟ*</b> King facing, head r., seated cross-legged on cushions, body radiate; in l. hand, sceptre.	<b>ΑΘΡΟ</b> Male deity l.; holds wreath in extended r. hand; to l., ☸.
167	Æ 1.		Inscr. King, head and body radiate, seated facing on throne.	Similar.
168	Æ 1.			
169	Æ 8		Inscr. King nimbate, facing, head r., seated; holds in l. hand, sceptre.	<b>ΑΡΔΟΧΡ</b> Female deity l.; holds cornucopias; to l., ☸.
170	Æ 8		Inscr. King nimbate, r., reclining.	<b>ΑΡ]ΔΟΧΡ</b> Female deity l.; holds in r. hand, sceptre (†); to l., ☸.
171	Æ 1.		Inscr. King seated cross-legged on cushions, facing, head r., head and body radiate; l. hand raised.	<b>ΜΑΟ</b> Moon-god l., crescent behind shoulders; r. hand advanced; with l. grasps sword; to l., ☸.
172	Æ 1.		in l. sceptre.	[L. O. C. Pl. xxix. 4.]
173	Æ 1.		" "	
174	Æ 95		" "	
175	Æ 8		" "	



\* On coins of this class the inscription is even more debased than on those of the last; sometimes, however, it ends **ΟΟΗΡΚΕΚΟΡΑΝΟ**.

No.	Wt.	Metal. Size.	Obverse.	Reverse.
176	Æ 9		<b>PAONANOPAO</b> <b>OOHPKENOPANO</b> King seated cross-legged, facing, head r., nimbate; holds in each hand, staff or sword.	<b>MAO</b> Moon-god l., crescent behind shoulders; r. hand advanced; with l. grasps sword; to l., ☽.
177	Æ 1.		Inscr. King, head and body radiate, half reclining, facing, on throne.	Similar.
178	Æ 1.			
179	Æ 1.			(inscr. retrograde). [Pl. xxix. 5.]
180	Æ 9			[I. O. C.]
181	Æ 9			"
182	Æ 1.		Inscr. King, with head and body nimbate, seated cross-legged, facing, on cushions; in l. hand, sceptre.	<b>MIOPO</b> Sun-god l., radiate; r. hand advanced; with l. grasps sword; to l., ☼.
183	Æ 1.			[I. O. C.]
184	Æ 8		(king not nimbate).	(deity holds wreath in r.).
185	Æ 95			[Pl. xxix. 6.]
186	Æ 1.1		Inscr. King, with body radiate, half reclining, facing on throne, flames on shoulders.	Similar.
187	Æ 1.			(deity holds sceptre, not sword).
188	Æ 1.			(inscr. <b>MIIPO</b> ).
189	Æ 85			
190	Æ 85			(deity holds wreath in r.).

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			<b>ΠΑΝΑΝΟΡΑΟ</b> <b>ΟΟΗΡΚΕΚΟΡΑΝΟ</b> King, with head nim- bate and body radiate, seated facing, head r., cross-legged on cushions; holds in l. hand, sceptre.	<b>NANA</b> Nanaia r., nimbate; holds sceptre; to r.,  .
191		Æ 1·05		[L. O. C.]
			Similar	<b>ΟΚΡΟ</b> Siva facing, nimbate, head l.; has four arms and hands, in which he holds a wreath, a thun- derbolt, a trident and a vase; to l.,  .
192		Æ 1·05		
193		Æ 9		
			Inscr. King, with head and body radiate, half reclining, facing, on throne.	Similar.
194		Æ 1·		[L. O. C. Pl. XXIX. 7.]
195		Æ 1·		
196		Æ 1·		(Siva holds goat in fourth hand).
197		Æ 9		(Siva grasps sword in fourth hand).

No.	Wt.	Metal. Size.	Obverse.	Reverse.
BAZODEO (VASU DEVA).				
(a) <i>Gold.</i>				
			<b>ΠΑΟΝΑΝΟ ΠΑΟ ΒΑ ΖΟΛΗΟΚΟΡΑΝΟ</b> The king I., clad in conical helmet and suit of mail, diad. and nim- bate; holds r. hand over altar; in l., spear; wears sword.	<b>NANA</b> Nanaia r., nimbate, head surmounted by crescent; holds sceptre, ending in forepart of horse, and patera; to r.,  .
1	122.5	N 85		[Pl. XXIX. 8.]
2	122.2	N 8		[I. O. C.]
			<b>ΠΑΟΝΑΝΟΡΑ ΟΒΑΖΟΔΗΟΚ</b> Similar.	<b>ΟΚΡΟ</b> Siva facing, having three faces and two arms; holds wreath and trident; to l.,  .
3	120.8	N 8		
4	122.3	N 8		(inscr. <b>ΟΡΚΟ</b> ). [Pl. XXIX. 9.]
			<b>ΠΑΟΝΑΝΟΡΑΟΒΑ ΖΟΛΗΟΚΟΡΑΝΟ</b> The king I., clad in conical helmet and suit of mail, diad. and nim- bate; holds r. hand over altar; in l., spear; stan- dard behind head.	<b>ΟΚΡΟ</b> Siva facing, having three faces and two arms; holds wreath and trident; behind him, bull l.; to r.,  .
5	123.8	N 8		[Pl. XXIX. 10.]
6	124.9	N 8		
7	123.5	N 85		(Siva one-faced). [I. O. C.]
8	124.8	N 85		(bull feeding).
9	123.4	N 8		" (inscr. <b>ΟΡΚΟ</b> ). "
10	122.8	N 85	(inscr. barbarous).	(Siva one-faced); symbol to l.

No.	Wt.	Metal Size.	Obverse.	Reverse.
			<b>ΠΑΟΝΑΝΟΡΑΟΒΑ</b> <b>ΖΟΑΗΟΚΟΡΑΝΟ</b> The king standing as before at altar; beside which, trident fixed in the ground.	<b>ΟΚΡΟ</b> Siva, one-headed, facing; holds wreath and trident; behind him, bull l.; to l.,  .
11	126.	N 85		
12	124.7	N 85		
13	121.2	N 8		
14	123.	N 9	to r.,  .	(inser. <b>ΟΓΚΟ</b> ; to l.,  .
15	124.	N 85	"  .	" "
16	116.4	N 85	" "	" "
17	31.	N 5		" " [I. O. C. Pl. XXIX. 11.]
18	30.7	N 5		(Siva crosses his legs); to r.,  .
<i>Barbarous imitations.</i>				
19	122.7	N 9	to r.,  .	[Pl. XXIX. 12.]
20	122.5	N 9	" "	to l.,  .
21	123.7	N 1.	" " ; below,  .	
22	123.5	N 1.05	" " " "	
23	120.8	N 95	" "	to l.,  .
24	124.7	N 1.05	" " " "	[Pl. XXX. 13.]

No.	Wt.	Metal. Size.	Obverse.	Reverse.
			(β) Bronze.	
			<b>ΠΑΟΝΑΝΟΡΑΟ</b> <b>ΒΑΖΟΛΗΟΚΟΡΑΝΟ *</b> The king, standing as before, at altar; beside which, trident fixed in the ground.	<b>ΟΚΡΟ</b> Siva, one-headed, facing; holds wreath and trident; behind him, bull I.; to r.,  .
25	Æ 9			
26	Æ 9		to r.,  .	
27	Æ 95		" "	[Pl. xxix. 14.]
28	Æ 1.			
29	Æ 85			
30	Æ 95		(inscr. barbarous).	
31	Æ 95		" "	
32	Æ 1.		(trident absent).	(inscr. wanting). [L. O. C.]
			<b>ΠΑΟΒΑ ΖΟΔΗΟ</b> King, standing as above, at altar.	Similar (γ).
33	Æ 75			

\* These legends are not complete on any specimen.

No.	Wt.	Metal. Size.	Obverse.	Reverse.
INDO-SCYTHIC, UNCERTAIN.				
(a) <i>Gold ; without figure of King.</i>				
1	66.7	N 6	Indian legend (see plate xxix. 15; the inscription seems to run on one side . . . . : <i>didava-ta</i> ?). Greek city-goddess, clad in chiton and peplos, wearing mural crown, and holding a poppy-head.	<p><b>TAYPOC</b> Humped bull r.  <b>𐎧𐎠𐎫</b> (<i>vrishabha</i>).</p>
				[Pl. xxix. 15.]



No.	Obverse.	Reverse.
<b>PANTALEON.</b>		
1	Head of the king r., diad.  [Pl. xxx. 4.]	<div style="display: flex; justify-content: space-between;"> <div> <b>ΒΑΣΙΛΕΩΣ</b>  <b>ΠΑΝΤΑΛΕΟΝΤΟΣ</b> </div> <div>           Zeus seated            l.; holds            in l., sceptre, in r., a figure of            the three-headed Hekate.         </div> </div> <div style="text-align: right;">AR Wt. 232<sup>+</sup> (Gen. Cunningham).</div>
<b>AGATHOCLES.</b>		
<i>With name and type of Antiochus Nicator.</i>		
1	<div style="display: flex; justify-content: space-between;"> <div> <b>ΑΝΤΙΟΧΟΥ</b>  <b>ΝΙΚΑΤΟΡΟΣ</b> </div> <div>           Head of Antiochus            l. r., diad.         </div> </div> <div style="text-align: right;">[Pl. xxx. 5.]</div>	<div style="display: flex; justify-content: space-between;"> <div> <b>ΒΑΣΙΛΕΥΟΝΤΟΣ</b>  <b>ΑΓΑΘΟΚΛΕΟΥΣ</b>  <b>ΔΙΚΑΙΟΥ</b> </div> <div>           Zeus striding            to l., hurl-            ing thunderbolt;            eagle at his feet: to l., wreath.         </div> </div> <div style="text-align: right;">AR Wt. 255<sup>+</sup> (Gen. Cunningham).</div>
<b>ANTIMACHUS I.</b>		
<i>With name and type of Diodotus.</i>		
1	<div style="display: flex; justify-content: space-between;"> <div> <b>ΔΙΟΔΟΤΟΥ</b>  <b>ΣΩΤΗΡΟΣ</b> </div> <div>           Head of Diodotus            r., diad.         </div> </div> <div style="text-align: right;">[Pl. xxx. 6.]</div>	<div style="display: flex; justify-content: space-between;"> <div> <b>ΒΑΣΙΛΕΥΟΝΤΟΣ</b>  <b>ΑΝΤΙΜΑΧΟΥ</b>  <b>ΘΕΟΥ</b> </div> <div>           Zeus striding            to l., hurl-            ing thunderbolt;            eagle at his feet: to l., wreath.         </div> </div> <div style="text-align: right;">AR Tetradrachm (The late Sir E. C. Bayley).</div>
<i>With his own types.</i>		
2	Indian elephant r.  [Pl. xxx. 7.]	<div style="display: flex; justify-content: space-between;"> <div> <b>ΒΑΣΙΛΕΩΣ ΘΕΟΥ</b>  <b>ΑΝΤΙΜΑΧΟΥ</b> </div> <div>           Nike l.            holding            wreath and palm, standing on            prow of ship.         </div> </div> <div style="text-align: right;">Æ round, 9 (formerly Gen. Cunningham).</div>

## EUCRATIDES.

No.	Obverse.	Reverse.
1	Bust of the king r., helmeted.  [Rev. Numism., 1867, Pl. XII.]	<b>ΒΑΣΙΛΕΩΣ ΜΕΓΑΛΟΥ</b> The <b>ΕΥΚΡΑΤΙΔΟΥ</b> Dioscuri charging r., carrying palms.  <i>N</i> Wt. 2593·5 gr. (20 stater piece, Bibl. Nationale, Paris).
2		<i>N</i> Stater (Col. Strutt).
3	Bust of the king l., helmeted, but with shoulders bare; thrusting with spear.  [Pl. xxx. 8.]	As last.  <i>R</i> Wt. 233 (Gen. Cunningham).
4	<b>ΒΑΣΙΛΕΩΣ ΜΕΓΑΛΟΥ</b> Bust <b>ΕΥΚΡΑΤΙΔΟΥ</b> of the king r., helmeted.  [Pl. xxx. 9.]	<b>𐤀𐤁𐤁𐤁𐤁 𐤀𐤕𐤓𐤕𐤓𐤕</b> ( <i>Maha-</i> <b>𐤕𐤓𐤕𐤓𐤕𐤓𐤕</b> <i>rajasa maha-</i> <i>takasa Eukratidasa</i> ). The Dios- curi standing side by side; hold spears and swords.  <i>R</i> Wt. 34·5 gr. (formerly Gen. Abbott). On a coin of this class in Gen. Court's Collection, the inscription begins <b>𐤀𐤕𐤓</b> (Von Sallet in <i>Zeit. f. Num.</i> 10, p. 157).
5	Head of Apollo r., laur.  [Pl. xxx. 10.]	<b>ΒΑΣΙΛΕΩΣ</b> Horse l., standing. <b>ΕΥΚΡΑΤΙΔΟΥ</b>  <i>Æ</i> round, ·7 (Vienna).
6	<b>ΒΑΣΙΛΕΩΣ ΜΕΓΑΛΟΥ</b> Bust <b>ΕΥΚΡΑΤΙΔΟΥ</b> of the king r., diad.  [Pl. xxx. 11.]	Indian inser. as above. The pilei of the Dioscuri, surmounted by stars, and two palms.  <i>Æ</i> square, ·55 (Gen. Cunningham).

No.	Obverse.	Reverse.
7	<p>ΒΑΣΙΛΕΩΣ ΜΕΓΑΛΟΥ ΕΥ- ΚΡΑΤΙΔΟΥ Bust of the king r., diad. and helmeted.</p> <p>[Pl. xxx. 12.]</p>	<p>𐤁𐤕𐤕𐤕𐤕𐤕 𐤁𐤕𐤕𐤕𐤕𐤕 𐤁𐤕𐤕𐤕𐤕𐤕 (Māhārājasa rajadīrajasa Evkratidasa). Nike l.; holds wreath and palm.</p> <p>Æ square, 7 (Gen. Cunningham).</p>

## HELIOCLES.

1	Bust of the king r., helmeted.	<p>ΒΑΣΙΛΕΩΣ Zeus seated l.; ΗΛΙΟΚΛΕΟΥΣ holds Nike ΔΙΚΑΙΟΥ and long sceptre.</p> <p>AR Tetradrachm (formerly Major Hay).</p>
2	[Pl. xxxi. 1.]	AR Drachm (The late Sir E. C. Bayley).

## ANTIALCIDAS.

1	<p>ΒΑΣΙΛΕΩΣ ΝΙΚΗΦΟΡΟΥ ΑΝΤΙΑΛΚΙΔΟΥ Bust of the king r., diad.</p>	<p>𐤁𐤕𐤕𐤕𐤕𐤕 𐤁𐤕𐤕𐤕𐤕𐤕 (Maha- 𐤁𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕𐤕 rajasa jaya- dharasa Antialkidas). Elephant walking r.; wreath in raised trunk.</p> <p>Æ square, 75 (Major Landon: now presented to British Museum).</p>
---	--	--

## ANTIALCIDAS AND LYSIAS.

1	<p>ΒΑΣΙΛΕΩΣ ΑΝΙΚΗΤΟΥ ΛΥΣΙΟΥ Bust of bearded Herakles r.; club on shoulder.</p> <p>[Pl. xxxi. 2.]</p>	<p>Inscr. as last. The caps of the Dios- curi, and two palms.</p> <p>Æ square, 7 (Bodleian Library).</p>
---	--	--

No.

Obverse.

Reverse.

## THEOPHILUS.

- 1 ΒΑΣΙΛΕΥΣ ΔΙΚΑΙΟΥ ΒΕΟΦΙΛΟΥ Bust of the king r., diad. [Pl. xxxi. 3.]
- ΑΒΨΞ ΑΥΓ~ (Maharaja jasa dhramikasa Theophilus). Herakles, crowning himself; holds in l. hand, club and lion's skin.  
R Wt. 36 (Gen. Cunningham).
- 2 ΒΑΣΙΛΕΥΣ ΔΙΚΑΙΟΥ ΘΕΟΦΙΛΟΥ Head of bearded Herakles r.; club on shoulder. [Pl. xxxi. 4.]
- ΑΓΑΓΑ ΑΒΨΞ ΑΥΓ~ (Maharajasa dhramikasa Theophilus). Cornucopiae.  
Æ square, '8 (Gen. Cunningham).

## ARCHEBIUS.

- 1 ΒΑΣΙΛΕΥΣ ΔΙΚΑΙΟΥ ΝΙΚΗΦΟΡΟΥ ΑΡΧΕΒΙΟΥ Bust of Zeus r., diad.; sceptre on shoulder. [Pl. xxxi. 5.]
- ΑΓΓΑΛ ΑΒΨΞ ΑΥΓ~ ΑΛΛΑΓΑ (Maharajasa dhramikasa jayadharasa Arkhebius). The caps of the Dioscuri, and two palms.  
Æ square, '9 (Gen. Cunningham).

## APOLLODOTUS.

- 1 ΒΑΣΙΛΕΥΣ ΣΩΤΗΡΟΣ [ΑΠΟΛΛΟΔΟΤΟΥ] Apollo seated r. on throne, holding out bow. [Pl. xxxi. 5.]
- ΑΓΓΑΓΑ ΑΥΓ~ (Maharajasa tradatusa Apollodotus). Tripod.  
Æ square, '8 (Gen. Cunningham).

No.	Obverse.	Reverse.
<b>STRATO I.</b>		
1	<p><b>ΒΑΣΙΛΕΩΣ ΕΠΙΦΑΝΟΥΣ</b>  <b>ΣΩΤΗΡΟΣ ΣΤΡΑΤΩΝΟΣ</b>            Bust of the king r., diad.</p> <p>[Pl. xxxi. 6.]</p>	<p>𐤁𐤓𐤕𐤕 𐤁𐤓𐤕𐤕 𐤁𐤓𐤕𐤕.~𐤁            𐤁𐤓𐤕𐤕 (<i>Māhārajasa prati-</i>  <i>chhaya tradatasa Stratasā</i>). Pal-            las l.; holding aegis and hurling            thunderbolt.</p> <p>R Wt. 134. (Gen. Cunningham).</p>
<b>STRATO II.</b>		
1	<p><b>ΒΑΣΙΛΕΩΣ ΣΩΤΗΡΟΣ</b>  <b>ΣΤΡΑΤΩΝΟΣ ΥΙΟΥ</b>  <b>ΣΤΡΑΤΩΝΟΣ</b> Bust of the            king r., diad.</p> <p>[Pl. xxxi. 7.]</p>	<p>𐤁𐤓𐤕𐤕 𐤁𐤓𐤕𐤕 𐤁𐤓𐤕𐤕.~𐤁            𐤁𐤓𐤕𐤕 (<i>Maharaja rajarajasa Stratasā</i>  <i>putrasa cha sampriyapita Stra-</i>  <i>tasa</i>). Pallas l.; holding aegis            and thunderbolt.</p> <p>R Wt. 36. (Gen. Cunningham).</p>
This is Gen. Cunningham's reading of his specimen (engraved), and given on his authority.		
<b>MENANDER.</b>		
1	<p><b>ΒΑΣΙΛΕΩΣ ΣΩΤΗΡΟΣ</b>  <b>ΜΕΝΑΝΔΡΟΥ</b> Head of Pallas            r., helmeted.</p> <p>[Pl. xxxi. 8.]</p>	<p>𐤁.𐤓𐤕𐤕 𐤁𐤓𐤕𐤕 𐤁𐤓𐤕𐤕.~𐤁            (<i>Māhārajasa tradatasa Mena-</i>  <i>drāsa</i>). Owl r.</p> <p>R Wt. 28. (Gen. Cunningham).</p>
2	<p><b>ΒΑΣΙΛΕΩΣ ΣΩΤΗΡΟΣ</b>  <b>ΜΕΝΑΝΔΡΟΥ</b> Bust of the            king l., wearing aegis and thrust-            ing with spear.</p>	<p>𐤁𐤓𐤕𐤕 𐤁𐤓𐤕𐤕.~𐤁            𐤁.𐤓𐤕𐤕 (<i>Māhā-</i>  <i>rajasa tradatasa</i>  <i>Mendrāsa</i>). Pallas l.; holding            thunderbolt and aegis.</p> <p>R Didrachm (Published by Gen.            Cunningham from a sealing-wax            impression).</p>

No.	Obverse.	Reverse.
3	<b>ΒΑΣΙΛΕΩΣ ΣΩΤΗΡΟΣ</b> <b>ΜΕΝΑΝΔΡΟΥ</b> Young male head r., wearing wreath.  [Pl. XXXI. 9.]	<p>𐤁.𐤒𐤏𐤔 𐤔𐤕𐤕𐤕 𐤔𐤕𐤕.~𐤕</p> <p>(<i>Mohurajasa tradatasa Menadrasa</i>). Dolphin r.</p> <p>Æ square, 1.</p>
4	Same inscr. Two-humped camel l.  [Pl. XXXI. 10.]	Same inscr. Bull's head, facing.  Æ square, 1. (Museum As. Soc. Bengal).
5	Same inscr. Elephant l.  [Pl. XXXI. 11.]	Same inscr. Elephant-goad.  Æ square, 9 (Gen. Cunningham).
6	Same inscr. Boar's head r.  [Pl. XXXI. 12.]	Same inscr. Palm-branch.  Æ square, 8

Nos. 3 and 6 are said by Gen. Cunningham to be in the East India Museum. This is incorrect, as the coins of this Museum are now in the British Museum, and these types are wanting.

## EPANDER.

1	<b>ΒΑΣΙΛΕΩΣ ΝΙΚΗΦΟΡΟΥ</b> <b>ΕΠΑΝΔΡΟΥ</b> Bast of the king r., diad.  [Pl. XXXI. 13.]	<p>𐤁𐤕𐤕𐤕𐤕 [𐤔𐤕𐤕.~𐤕] (<i>Maha-</i>  𐤕𐤕𐤕𐤕𐤕 <i>rajasa jagatharasa</i>  <i>Epandrasa</i>). Pallas l.; holds aegis  and thunderbolt.</p> <p>AR Wt. 19. (broken), (Gen. Cun-  ningham).</p>
---	---	---

## DIONYSIUS.

1	Apollo r., clad in chlamys; holds arrow with both hands.  [Pl. XXXI. 14.]	<p>𐤁𐤕𐤕𐤕𐤕 𐤔𐤕𐤕𐤕 𐤔𐤕𐤕.~𐤕</p> <p>(<i>Maharajasa tradatasa Dionisi-</i>  <i>gasa</i>). Royal diadem.</p> <p>Æ square, 6 (Col. Bosh).</p>
---	--	--

No.	Obverse.	Reverse.
<b>ZOILUS.</b>		
1	<p><b>ΒΑΣΙΛΕΩΣ ΔΙΚΑΙΟΥ</b> Bust  <b>ΙΩΛΟΥ</b> of the king r., diad.</p> <p>[Pl. XXXII. 1.]</p>	<p>𐤆𐤇𐤑𐤏 𐤕𐤓𐤕.~𐤏 (Māhō-  𐤕𐤓𐤕𐤏 <i>rajasa dhramikasa</i>  <i>Jhoilasa</i>). Herakles, facing; holds  in r., wreath; in l., club and lion's  skin; on his shoulder, Nike hold-  ing wreath.</p> <p>AR Wt. 36.5 (Gen. Cunningham).</p>
2	<p><b>ΒΑΣΙΛΕΩΣ ΔΙΚΑΙΟΥ</b> Head  <b>ΙΩΛΟΥ</b> of bearded Herakles  r., in lion's skin.</p> <p>[Pl. XXXII. 2.]</p>	<p>𐤕𐤓𐤕𐤏 𐤕𐤓𐤑𐤏 𐤕𐤓𐤕.~𐤏  (Maharajasa dhramikasa Jhoi-  lasa). Club and bow-case, within  ivy-wreath.</p> <p>AE square, 1.1 (Lady Headfort).</p>

**ARTEMIDORUS.**

1	<p><b>ΒΑΣΙΛΕΩΣ ΑΝΙΚΗΤΟΥ</b>  <b>ΑΡΤΕΜΙΔΩΡΟΥ</b> Bust of the  king r., diad.</p> <p>[Pl. XXXII. 3.]</p>	<p>𐤕𐤓~𐤕/𐤕𐤕 𐤕𐤓𐤕.~𐤏  𐤕𐤓𐤕𐤑𐤏𐤕𐤕𐤏 (Māhārajasa  <i>apadihalasa Artemidorasa</i>). Ar-  temis, clad in short chiton and  chlamys, shooting l.</p> <p>AR Wt. 128 (Gen. Cunningham).  A specimen much injured (Wt.  117.3), recently acquired for  British Museum.</p>
2	<p>(king helmeted). [Pl. XXXII. 4.]</p>	<p>AR Wt. 36 (Gen. Cunningham).</p>
3	<p>Same inser. Bust of the king r.,  diad.</p> <p>[Pl. XXXII. 5.]</p>	<p>Same inser. Nike r.; holds wreath  and palm.</p> <p>AR Wt. 37 (Gen. Cunningham).</p>

No.

Obverse.

Reverse.

## PHILOXENUS.

- 1 The British Museum has recently acquired a didrachm (Wt. 140) of this king with the usual type and inscriptions (p. 36), but having on the obverse a helmeted bust of the king l., thrusting with spear.

## NICIAS.

- 1 **ΒΑΣΙΛΕΩΣ ΣΩΤΗΡΟΣ**  
**ΝΙΚΙΟΥ** Bust of the king r.,  
diad.  
[Pl. XXXII. 6.]
- Ἰνδρῖν Ἰνδρῖν (Mahā-  
Ἰνδρῖν *rajasa tradahina*  
*Nikiasa*). The king (or Pallas ?)  
helmeted, standing l.; holds palm  
over shoulder.  
R Wt. 36. (Gen. Cunningham).

## TELEPHUS.

- 1 **ΒΑΣΙΛΕΩΣ ΕΥΕΡΓΕΤΟΥ**  
**ΤΗΛΕΦΟΥ** Giant (Skythes?),  
his body ending in three serpents;  
holds in each hand, hammer!  
[Pl. XXXII. 7.]
- Ἰνδρῖν Ἰνδρῖν (Maharajasa  
Ἰνδρῖν *palanakrahasa Teliphasa*). Helios  
radiate facing, clad in tunic and  
chlamys, holds long sceptre; be-  
side him male figure wrapped in  
manile, wearing wreath or horned;  
in field, mon.  
R Wt. 37. (Bodleian Library).

Mr. Oman having kindly procured a cast of this coin, we are enabled to give a more accurate description of it than has hitherto appeared. Mr. Bendall suggests the reading *palanakrahasa* as a rendering of *εὐεργέτης*.

## AMYNTAS.

- 1 Gen. Cunningham possesses hemidrachms with the usual type of reverse, the seated Zeus; but having on the obverse respectively, (1) bust of the king in Macedonian causia; (2) bust of the king, bare-headed, thrusting with spear.

No.	Obverse.	Reverse.
<b>HERMAEUS.</b>		
1	Gen. Cunningham has a didrachm of the usual type (Wt. 153 grs.), with helmeted head of the king on the obverse.	
2	<b>ΒΑΣΙΛΕΩΣ ΣΩΤΗΡΟΣ</b> <b>ΕΡΜΑΙΟΥ</b> King on horseback r., galloping.	<p>𐤀𐤅𐤁𐤁 𐤀𐤕𐤁𐤁𐤁 (Maha-  𐤀𐤕𐤁𐤁𐤁 <i>rajasa mahatasa</i>  <i>Heramayasa</i>). Zeus seated l. on  throne.</p> <p>AR Wt. 31 (Gen. Cunningham).</p>
3	<b>ΒΑΣΙΛΕΩΣ ΣΤΗΡΟΣ ΣΥ</b> <b>ΕΡΜΑΙΟΥ</b> Bust of the king r., bare.	<p>𐤀𐤕𐤁𐤁𐤁 [𐤀𐤕𐤁𐤁𐤁𐤀𐤕𐤁𐤁𐤁𐤀𐤕𐤁𐤁𐤁  𐤀𐤕𐤁𐤁𐤁 (Maharajasa  <i>rajarajasa</i>)] <i>mahatasa Heramaya-</i>  <i>sa</i>). Nike l.; holding wreath.</p> <p>Æ round, 7 (Gen. Cunningham).</p>
	[Pl. xxxii. 8.]	
4	𐤀𐤕.....𐤀𐤕 𐤀𐤕𐤁𐤁𐤁𐤁 ( <i>Maharajasa raja</i> ..... [ <i>Herama?</i> ] <i>ajasa</i> ). Horse r.	<p>Uncertain device, surrounded by a  circle of unascertained Chinese  characters.</p> <p>Æ l. (Sir D. Forsyth), <i>Num. Chron.</i>,  1879, p. 276.</p>
<b>MAUES.</b>		
1	<b>ΒΑΣΙΛΕΩΣ ΒΑΣΙΛΕΩΝ</b> <b>ΜΕΓΑΛΟΥ ΜΑΥΟΥ</b> Biga r., in which radiate figure holding sceptre or spear, and charioteer.	<p>𐤀𐤕𐤁𐤁𐤁 𐤀𐤕𐤁𐤁𐤁𐤁𐤁 (Raja-  𐤀𐤕𐤁𐤁𐤁 <i>dirajasa mahatasa</i>  <i>Moasa</i>). Zeus seated l. on throne;  thunderbolt in extended r. hand.</p> <p>AR Didrachm (Bodleian Library),  Wt. 121.</p> <p>AR Hemidrachm (acquired for Brit.  Mus.), Wt. 27.6.</p>
2		

No.

Obverse.

Reverse.

## AZES AND AZILISES.

- 1 ΒΑΣΙΛΕΩΣ ΒΑΣΙΛΕΩΝ  
ΜΕΓΑΛΟΥ ΑΖΟΥ The king  
r., on horseback; lance couched.

[Pl. XXXII. 9.]

𐤁𐤆𐤌𐤍𐤏𐤕𐤁𐤆𐤌𐤍𐤏𐤕  
𐤁𐤆𐤌𐤍𐤏𐤕𐤁𐤆𐤌𐤍𐤏𐤕 (Maharajasa  
rajarajasa mahatasa Ayilishasa).  
A city? l., holds in r. hand an  
object resembling a brazier; in l.,  
palm bound with fillet.

AR Didrachm (R. Rochette, 1<sup>re</sup>  
Suppl., Pl. II., No. 16).

AR Hemidrachm (Grotefend).

2

## AZILISES.

- 1 'Standing figure to the r., with the  
r. arm extended horizontally, and  
holding a chaplet.'

'Figure in short tunic, with loose  
veil-like garments around the head,  
&c. Arian legend, imperfect, . . .  
jasa mahatasa Ayilishasa.'

Æ square (Thomas's Prinsep II., p.  
212, No. 9, Sir E. C. Bayley).

## VONONES AND SPALAHORES.

- 1 ΒΑΣΙΛΕΩΣ ΒΑΣΙΛΕΩΝ  
ΜΕΓΑΛΟΥ ΟΝΩΝΟΥ  
Hercules, with club and lion's  
skin; r. hand raised to the head.'

[Ariana Antiqua, Pl. VIII. 9.]

'Arian legend: — Spahora bhrata  
dhramikasa Spalahorasa. Minerva  
to the l., armed with shield and  
spear; r. arm extended.'

Æ square (Thomas's Prinsep II., p.  
204, No. 3, Mr. Brereton).

No.	Obverse.	Reverse.
<b>GONDOPHARES.</b>		
1	<p>Bust of the king l., wearing Arsacid tiara, diad.</p> <p>[Pl. XXXII. 10.]</p>	<p><b>ΒΑΣΙΛΕΩΣ ΒΑΣΙΛΕΩΝ ΜΕΓΣ ΥΝΔΟΦΕΡΗΣ ΑΥΤΟΚΡΑΤΟ</b> King seated l. on throne, holding sceptre; behind, Nike crowning him.</p> <p>AR Wt. 58<sup>+</sup> (Berlin, <i>Zeitschr. f. Num.</i> 1879, p. 358).</p>

## ZEIONISES.

1	<p>Barbarous inscr. The king r., on horseback; arm extended.</p> <p>[Pl. XXXII. 11.]</p>	<p>Inscription ending <b>ΖΕΙΟΝΙΣΕΩΣ</b> (<i>Jehūniasa</i>). The king facing; on one side, Nike; on the other, a wingless figure, crowning him.</p> <p>AR Didrachm (Thomas's Prinsep, Pl. XXVIII. 5).</p>
---	--	--

## ARSACES DIKAIOS.

1	<p><b>ΒΑΣΙΛΕΥΟΝΤΟΣ ΒΑΣΙΛΕΩΝ ΔΙΚΑΙΟΥ ΑΡΣΑΚΩΝ</b> The king, on horseback r.; r. hand raised.</p>	<p>Arim legend:—(<i>Māhārājasa rajarajasa mahatasa Ashshakasa tradatasa</i>). Type obliterated.* [On another specimen, Male figure to the left, holding a small figure in his right hand].</p> <p>AE round (Cunningham).</p>
---	--	--

\* A coin of this class has a type thus described by Rollin and Fournier, *Catalogue de Médailles*, No. 8296.—Figure militaire (?) diadémée debout, à g., tenant de la dr. une palme, la g. sur son épée (?).

No.	Obverse.	Reverse.
<b>ARSACES THEOS.</b>		
1	<b>ΒΑΣΙΛΕΥΣ ΘΕΟΥ . . . ΚΑΚΟΥ</b> Horse r.  [Pl. xxxii. 12.]	Bow in case: fillet-border.  Æ square, 7 (Berlin, <i>Zeitschr. f. Num.</i> , Pl. v. 2).
<b>KADPHISES II.</b>		
1	<b>ΒΑΣΙΛΕΥΣ ΟΟΗΜΟ ΚΑΔΦΙ- CHC</b> King r., holding club; seated in biga moving slowly to r.  [Pl. xxxii. 13.]	Usual reverse; type, Siva standing (see p. 124).  N Stater ( <i>Ariana Antiqua</i> , Pl. x. 9).
<b>KANERKES.</b>		
1	<b>ΡΑΟΝΑΝΟΡΑΟ Κ[ΑΝΗΡΚΙ] ΚΟΡΑΝΟ</b> Bust of the king r., helmeted, holding spear, above clouds.	<b>ΗΛΙΟΣ</b> Helios standing, radiate; one hand advanced, the other grasping sword.  N Wt. 30·8 (Rollin and Feuillant).
This coin, published by v. Sallet, is noteworthy as bilingual.		
2	<b>ΡΑΟ ΚΑ[ΝΗΡΚΙ]</b> The king standing, at altar.  [Pl. xxxii. 14.]	<b>ΓΟΒΟΥΔΟ</b> Buddha seated facing, cross-legged; arms in po- sure of benediction.  Æ 1 (Berlin, <i>Zeitschr. f. Num.</i> 1879, Pl. ix. 1).



# INDEX 1.

## TYPES.

### A

Abdagases, Head of.—Abdagases, 107.  
 Aegia.—Demetrius, 7; Antialcidas, 28; Menander, 49; Antimachus II., 55.  
 Agathocleia, Head of.—Agathocleia and Strato, 43.  
 Agathocles, Head of.—Agathocles, 10.  
 Alexander as Herakles, Head of.—Agathocles, 10.  
 Amyntas, Head of.—Amyntas, 61, 171.  
 Antialcidas, Head of.—Antialcidas, 25 *egg.*, 166.  
 Antimachus I., Head of.—Antimachus I., 12.  
 Antiochus, Head of.—Agathocles, 164.  
 Apollo, standing.—Eucratides, 13; Apollodotus I., 35 *sq.*; Apollodotus II., 38 *sq.*; Strato I., 41; Dionysius, 51, 169; Zoilus, 53; Hippostratus, 60; Maues, 72;  
 Apollo, standing, and elephant.—Zoilus, 53.  
 Apollo, seated.—Apollodotus I., 167.

Apollo, Head of.—Euthydemus II., 8; Strato I., 41; Eucratides 165.  
 Apollodotus II., Head of.—Apollodotus II., 37.  
 Apollophanes, Head of.—Apollophanes, 54.  
 Archebius, Head of.—Archebius, 32.  
 Artemidorus, Head of.—Artemidorus, 170.  
 Artemis, standing.—Artemidorus, 54.  
 Artemis, running with torch.—Diodotus I., 3.  
 Artemis, hunting.—Demetrius, 7; Hoerkes, 144; Artemidorus, 170.  
 Artemis, radiate.—Maues, 69.

### B

Biga, in which radiate figure.—Maues, 172.  
 Biga, in which king.—Kadphises II., 175.  
 Boar's head.—Menander, 169.  
 Bow and quiver.—Strato I., 41.  
 Bow and arrow.—Spalirises with Ares, 102.

Bow in case.—Maues, 72; Arsaces Theos, 175.

Bow-case and club.—Zoilus, 170.

Buddha, standing.—Kanerkas, 130, 133.

Buddha, seated.—Kanerkas, 175.

Bull, Indian.—Heliocles, 24; Diomedes, 31; Apollodotus I., 34, 36; Epander, 51; Artemidorus, 54; Philoxenus, 57; Maues, 69, 71; Azes, 85 *sqq.*; Azilises, 95 *sqq.*; Zeionises, 111 *sq.*; Uncertain, 162.

Bull's head.—Menander, 169.

### C.

Caduceus.—Demetrius, 7; Maues, 68.

Caduceus and cock.—Sophytes, 2.

Calliope and Hermaeus, Heads of.—Hermaeus and Calliope, 66.

Camel, Bactrian.—Uncert., 112; Menander, 169.

City, A.—Philoxenus, 57; Hippostratus, 59 *sq.*; Azes, 82, 90 *sq.*; Azes and Azilises, 173; Azilises, 94; Uncert., 162. (*See also Tyche*)

City, Head of a.—Andragoras, 1.

City and king.—Zeionises, 110.

Club.—Menander, 50.

Club and bow case.—Zoilus, 170.

Cock and Caduceus.—Sophytes, 2.

Cornucopise.—Theophilus, 167.

### D.

Dancing-girl.—Pantaleon, 9; Agathocles, 11.

Deity, wears modius.—Hoerkes, 153.

Deity, holds spear.—Hyrcodes, 117.

Deity, with horse.—Kanerkas, 130.

Deity, female, holds cornucopise.—Kanerkas, 130, 133; Hoerkes, 137, 154, 156.

Demeter, standing.—Azes, 85.

Demeter? seated.—Azes, 84.

Demetrius, Head of.—Demetrius, 6, 163.

Diadema.—Apollodotus II., 39; Dionysius, 169.

Diodotus, Head of.—Diodotus I., 3; Agathocles, 10; Antimachus I., 164.

Diomedes, Head of.—Diomedes, 31.

Dionysius, Head of.—Dionysius, 51.

Dionysus, Young, Head of.—Pantaleon, 9; Agathocles, 11.

Dioscuri, The, standing.—Diomedes, 31; Azilises, 93; Eucratides, 165.

Dioscuri, The, on horseback.—Eucratides, 13 *sqq.*, 165; Diomedes, 31.

Dioscuri, One of the.—Eucratides, 16; Azilises, 93.

Dolphin.—Menander, 169.

Dolphin, twined round anchor.—Nicias, 58.

### E.

Elephant.—Heliocles, 23 *sq.*; Lysias, 29 *sq.*; Archabius, 33; Apollodotus I., 34; Zoilus, 53; Maues, 68; Azes, 87, 90; Azilises, 95, 97; Antimachus I., 164; Antalcidas, 166; Menander, 169.

Elephant: holds wreath.—Maues, 71.

Elephant, Head of.—Demetrius 7; Menander, 50.

Enclosure, Sacred.—Agathocles, 12.  
 Epander, Head of.—Epander, 169.  
 Eucratides, Head of.—Eucratides,  
 13 *sq.*, 165 *sq.*  
 Euthydemus I., Head of.—Euthy-  
 demus, I., 4 *sq.*; Agathocles, 10.  
 Euthydemus II., Head of.—Euthy-  
 demus II., 8.

F.

Female figure, between stars.—Maues,  
 70.  
 Female figure: holds fillet.—Maues,  
 71; Azes, 89.  
 Fire-god.—Kauerkas, 130, 132 *sq.*;  
 Hoerkes, 136, 150 *sq.*, 156.

G.

Giant.—Telephus, 171.  
 Goad, Elephant.—Menander, 169.  
 Gondophares, Head of.—Gondo-  
 phares, 103 *sq.*, 174.  
 Gorgon-head on aegis. (*See* Aegia.)

H.

Hecate in hand of Zeus. (*See* Zeus.)  
 Heliocles, Head of.—Heliocles, 21  
*sq.*, 166.  
 Heliocles and Laodice, Heads of.—  
 Eucratides, 19.  
 Helios in quadriga.—Philo, 20.  
 Herakles, Young, standing.—Deme-  
 trius, 6; Euthydemus II., 8;  
 Lysias, 29 *sq.*; Zoilus, 52;  
 Maues, 69 *sq.*; Azes, 89; Azi-  
 lises, 96; Spalahores with Vo-

nonas, 98; Spalagadames with  
 Vonones, 99; Uncert., 119;  
 Hermaeus and Kadphises, 120  
*sq.*; Kadphises I., 122; Hoer-  
 kes, 138, 154; Theophilus, 167;  
 Vonones and Spalahores, 173.

Herakles, seated.—Euthydemus I.,  
 4 *sq.*; Agathocles, 10; Agatho-  
 cleia and Strato, 43; Azilises,  
 95; Spalagadames with Spaly-  
 ris, 100.

Herakles; Nike on shoulder.—Zoilus,  
 170.

Herakles, bearded, Head of.—Euthy-  
 demus I., 5; Demetrius, 7;  
 Euthydemus II., 8; Lysias, 29;  
 Strato I., 42; Antialcidas and  
 Lysias, 166; Theophilus, 167;  
 Zoilus, 170.

Herakles, Young, Head of.—Aga-  
 thocles, 10.

Heraüs, Head of.—Heraüs, 116.

Hermæus, Head of.—Hermæus, 62  
*sq.*, 172; Hermæus and Kad-  
 phises, 120 *sq.*; Kadphises I.,  
 122.

Hermæus and Calliope, Heads of.—  
 Hermæus and Calliope, 66.

Hermes, standing.—Maues, 71; Azes,  
 83 *sq.*

Hippostratus, Head of.—Hippo-  
 stratus, 59 *sq.*

Horse.—Euthydemus I., 5; Euthy-  
 demus II., 8; Heliocles, 22;  
 Menander, 48; Hippostratus,  
 60; Hermæus, 66, 172; Maues,  
 72; Azes, 89; Azilises, 96;  
 Eucratides, 165; Arsaces Theos,  
 175.

Horse, Forepart of.—Hyrcodes, 118.

Hyrcodes, Head of.—Hyrcodes, 117  
*sq.*

## K

- Kadaphes, Head of.—Kadaphes, 123.  
 Kadphises II., Head of.—Kadphises II., 126.  
 Kanerkes, Head of.—Kanerkes, 132.  
 King, standing.—Azilises, 96; Spalirises, 101; Spalirises with Azes, 102; Kadphises II., 126 *sq.*; Kanerkes, 129 *sqq.*, 175; Bazodo, 159 *sq.*; Nicias, 171.  
 King, seated.—Maues, 71; Azes, 83 *sq.*; Gondophares, 104; Sanabares, 113; Kadaphes, 123, Kadphises II., 124 *sqq.*; Hooerkes, 138, 145; Hooerkes, 156.  
 King on horseback.—Antimachus II., 55; Philoxenus, 56, 171; Nicias, 58; Hipposstratus, 59 *sq.*; Hermaeus, 172; Hermaeus and Calliope, 66; Maues, 68 *sq.*; Azes, 73 *sqq.*, 88 *sqq.*; Azes and Azilises, 92, 173; Azilises, 93 *sqq.*; Spalahores with Vonones, 98; Spalagadames with Vonones, 99; Spalagadames with Spalyria, 100; Spalirises, 100; Spalirises with Azes, 102; Gondophares, 103 *sqq.*; Abdagases, 107 *sq.*; Zeionises, 110; Uncert., 111; Soter, 114 *sqq.*; Zeionises, 174; Arsaces Dikaioes, 174.  
 King on elephant.—Hooerkes, 137; 153 *sq.*  
 King on camel.—Azes, 88.  
 King in biga.—Kadphises II., 175.  
 King crowned by Nike.—Gondophares, 174.  
 King on horseback, crowned by Nike.—Herañs, 116.  
 King and City.—Zeionisea, 110.

- King between Nike and another.—Zeionisea, 174.  
 King, half length.—Kadphises II., 124; Kanerkes, 132, 175; Hooerkes, 136 *sqq.*  
 King, Head of, helmeted.—Sophytes, 2; Eucratides, 14 *sqq.*, 165; Plato 20; Antialeidas, 26; Lysias, 29; Diomedes, 31; Archebius, 32; Strato I., 40; Agathocleia, 43; Menander, 44 *sq.*; Apolliphaneas, 54; Philoxenus, 56; Amyntas, 61; Hermaeus, 63; Soter, 116; Kadphises II., 124 *sqq.*; Kanerkes, 132; Hooerkes, 136 *sqq.*; Heliocles, 166.  
 King, Head of, in causia.—Antimachus I., 12; Antialeidas, 25 *sq.*; Amyntas, 171.  
 King, Head of, in elephant's skin.—Demetrius, 6, 163; Lysias, 29.  
 King, Head of, in tiara.—Sanabares, 113; Gondophares, 174.  
 King, Bust of, thrusting with spear.—Eucratides, 18, 165; Archebius, 32; Menander, 46 *sq.*, 168; Philoxenus, 171; Amyntas, 171.

## L

- Lakshmi, beside lion.—Azes, 85.  
 Laodice, Head of. (*See Heliocles and Laodice.*)  
 Lion.—Azes, 85 *sqq.*; Azilises, 97; Zeionises, 111; Uncert., 111, 119.  
 Lion, Maneless.—Pantaleon, 9; Agathocles, 11; Menander, 50; Maues, 69.  
 Lysias, Head of.—Lysias, 29.

## M

Maenad, between vines.—Maues, 70; Azez, 89.

Mahāsēnā.—Hooerkes, 138, 150.

Mahāsēnā Skanda and Viśākha.—Hooerkes, 150.

Male figure: holds sceptre.—Azilises, 97.

Male figure: holds club and trident.—Maues, 71; Azez, 89.

Male head in Phrygian cap.—Amyntas, 61; Hermaeus, 66.

Menander, Head of.—Menander, 44 *egg.*, 168.

Moon-god.—Kanerkes, 129, 131, 133 *sq.*; Hooerkes, 139, 154, 156.

Moon-god and sun-god.—Hooerkes, 141.

## N

Nannia.—Kanerkes, 129, 131, 134 *sq.*; Hooerkes, 144 *egg.*, 158; Bazodeo, 159.

Nicias, Head of.—Nicias, 58, 171.

Nike.—Eucratides, 18, 166; Archebius, 32; Strato I., 42; Menander, 48; Epander, 51; Antimachus II., 55; Philoxenus, 57; Hermaeus, 65, 172; Maues, 68 *egg.*; Azez, 83; Gondophares, 104 *sq.*; Abdagasea, 107; Orthagnes, 109; Pacores, 110; Sanabares, 113; Hooerkes, 147; Antemidorus, 170.

Nike on prow.—Antimachus I., 164.

Nike in quadriga.—Andragoras, 1.

Nike, wingless.—Azilises, 96.

## O

Orthagnes, 109.

Owl.—Archebius, 32 *sq.*; Menander, 49, 168.

Ox, Head of.—Menander, 49.

## P

Pacores, Head of.—Pacores, 110.

Pallas, standing.—Andragoras, 1; Menander, 50; Amyntas, 61; Maues, 69; Azez, 78 *egg.*, 91; Spalahores with Vonones, 98; Spalagadames with Vonones, 99; Gondophares, 103; Hooerkes, 149; Demetrius, 163; Nicias, 171; Vonones and Spalahores, 173.

Pallas, thundering.—Apollodotus II., 37; Strato I., 40 *sq.*; 168; Strato II., 168; Menander, 44 *egg.*, 168; Dionysius, 51; Zoilus, 52; Apollophanes, 54; Amyntas, 61; Kanjalala, 67; Azez, 78; Gondophares, 103; Epander, 169.

Pallas, seated.—Hippostratus, 60; Demetrius, 163.

Pallas, Head of.—Menander, 48 *sq.*, 168.

Palm.—Menander, 50, 169.

Palm and wreath.—Antialcidas, 28; Antimachus II., 55.

Palms and pilei. (*See* Pilei.)

Pantaleon, Head of.—Pantaleon, 164.

Panther.—Pantaleon, 9; Agathoclea, 11.

Philoxenus, Head of.—Philoxenus, 56, 171.

Pilei of Dioscouri and palma.—Eucratides, 15, 18, 165; Antialeidas, 27 *sq.*; Antialeidas and Lysias, 166; Archebius, 167.

Plato, Head of.—Plato, 20.

Poseidon, standing.—Antimachus I., 12; Azes, 77.

Poseidon and River-god.—Maues, 70 *sq.*; Azes, 89.

## Q.

Quadriga of Helios.—Plato, 20.

Quadriga driven by Nike.—Andragoras, I.

Quiver and bow.—Strato I., 41.

## R.

Ranjabala, Head of.—Ranjabala, 67.

River-god under foot of Poseidon.  
(*See* Poseidon.)

## S.

Sanabares, Head of.—Sanabares, 113.

Sarapis.—Hooerkes, 149.

Siva, two armed.—Gondophares, 104; Kadphises II., 125; Kanerkes, 135; Hooerkes, 153; Bazoleo, 159.

Siva, two armed, with bull.—Kadphises II., 124, 126 *sq.*, 175; Bazoleo, 159 *sqq.*

Siva, four armed.—Kanerkes, 132, 135; Hooerkes, 147, 155, 158.

Skanda.—Hooerkes, 138.

Skanda and Viśākha.—Hooerkes, 142.

Skanda Viśākha and Mahāsena.—Hooerkes, 150.

Sophytes, Head of.—Sophytes, 2.

Soter, Head of.—Soter, 114 *sqq.*

Strato I., Head of.—Strato I., 40 *sq.*, 168.

Strato II., Head of.—Strato II., 168.

Stupa, Buddhist.—Agathocles, 12.

Sun-god, standing.—Philoxenus, 57;

Kanerkes, 129, 131, 134, 175;

Hooerkes, 136, 141, 155, 157.

Sun-god and moon-god.—Hooerkes, 141.

Sun-god and another figure.—Telephus, 171.

Symbol ☪.—Gondophares, 105.

## T.

Theophilus, Head of.—Theophilus, 167.

Thunderbolt, winged.—Demetrius, 163.

Trident.—Demetrius, 7.

Trident and battle-axe in one.—Kadphises II., 126.

Tripod-lebes.—Euthydenus II., 8;

Apollodotus I., 35 *sq.*, 167;

Apollodotus II., 38 *sq.*; Strato I.,

41; Menander, 49; Dionysius,

51; Zoilus, 53; Hippostratus,

60; Maues, 72.

Triton.—Hippostratus, 60.

Tyche.—Maues, 68, 70 *sq.*

## V.

Viśākha and Skanda.—Hooerkes, 149.

Viśākha Skanda and Mahāsena.—Hooerkes, 150.

W.

- War-god.—Kanerkes, 132; Hoerkes, 138, 148.  
 Warrior, standing.—Arsaces Dikaioa, 174.  
 Wheel.—Menander, 50.  
 Wind-god.—Kanerkes, 135.  
 Wreath and palm.—Antialeidas, 28; Antinuchus II., 55.

Z.

- Zeus, standing.—Heliocles, 21 *sqq.*; Maues, 68; Azes, 73 *sqq.*, 83; Azes and Azilises, 92; Azilises, 93; Spalahores with Vonones, 98; Spalagadames with Vonones, 99; Spalirises, 100; Gondophares, 103, 106; Abdagases, 107 *sq.*; Soter, 114, 116.  
 Zeus, thundering.—Diodotus I., 3;

- Agathocles, 10, 164; Antimachus I., 164; Archebius, 32.  
 Zeus, standing: holding Hecate.—Agathocles, 10.  
 Zeus, seated.—Agathocles, 10; Amyntas, 61, 171; Hermaeus, 62 *sqq.*, 172; Spalirises, 101; Heliocles, 166.  
 Zeus, seated, with Thunderbolt.—Maues, 70, 172.  
 Zeus, seated, and elephant.—Encratides, 19; Antialeidas, 25 *sq.*; Maues, 70.  
 Zeus, seated; holds Hecate.—Pantaleon, 164.  
 Zeus, Head of, diad.—Andragoras, 1; Archebius, 167.  
 Zeus, Head of, laur.—Diodotus I., 3; Euthydemus I., 5.  
 Zeus, Head of thundering.—Antialeidas, 27 *sq.*  
 Zoilus, Head of.—Zoilus, 52, 170.

# INDEX II.

## KINGS, TYRANTS, &c.

### A.

Abdagases, 107.  
 Agathocles, 10, 164.  
 Agathocleia with Strato, 43.  
 Amyntas, 61, 171.  
 Andragoras, 1.  
 Antialcidas, 25, 166.  
 Antialcidas and Lysias, 166.  
 Antimachus I., 12, 164.  
 Antimachus II., 55.  
 Apollodotus I., 34, 167.  
 Apollodotus II., 37.  
 Apollophanes, 54.  
 Archobius, 32, 167.  
 Arsaces Dikaïos, 174.  
 Arsaces Theos, 175.  
 Artemidorus, 54, 170.  
 Azes, 73.  
 Azes and Azilises, 92, 173.  
 Azes and Spalirises, 102.  
 Azilises, 93, 173.

### B.

Bazoteco (Vasu Deva), 159.

### C.

Calliope and Hermaeus, 66.

### D.

Demetrius, 6, 163.  
 Diodotus I., 3.  
 Diomedes, 31.  
 Dionysius, 51, 169.

### E.

Epander, 51, 169.  
 Eucratides, 13, 165.  
 Eucratides with Heliocles and Laodice, 19.  
 Euthydemus I., 4.  
 Euthydemus II., 8.

### G.

Gondophares, 103, 174.

### H.

Heliocles, 21, 166.  
 Heliocles and Laodice with Eucratides, 19.  
 Heraüs, 116.  
 Hermaeus, 62, 172.  
 Hermaeus and Calliope, 66.  
 Hermaeus and Kadphises I., 120.  
 Hippostratus, 59.

Hooerkes, 136.

Hyreodes, 117.

## K.

Kadaphes, 123.

Kadphises I., 122.

Kadphises I. and Hermæus, 120.

Kadphises II., 124, 175.

Kamerkes, 129, 175.

## L.

Laodice with Heliocles and Eucratides, 19.

Lysias, 29.

Lysias and Antialcidas, 166.

## M.

Manes, 68, 172.

Menander, 44, 168.

## N.

Nicias, 58, 171.

## O.

Orthagnes, 109.

## P.

Pacores, 110.

Pantaleon, 9, 164.

Philoxenus, 56, 171.

Plato, 20.

## R.

Ranjabala, 67.

## S.

Sanabares, 113.

Sophytes, 2.

Sofer Megas, 114.

Spalagadames with Spalyris, 100.

Spalagadames with Vonones, 99.

Spalahores with Vonones, 98, 173.

Spalirises, 100.

Spalirises with Azes, 102.

Strato I., 40, 168.

Strato I. and Agathocleia, 43.

Strato II., 168.

## T.

Telephus, 171.

Theophilus, 167.

## V.

Vasu Deva (Bazosleo), 159.

Vonones and Spalagadames, 99.

Vonones and Spalahores, 98, 173.

## Z.

Zeionises, 110, 174.

Zoilus, 52, 170.

# INDEX III.

## TITLES OF KINGS.

### A. GREEK.

**ΑΔΕΛΦΙΔΕΩΣ** Abdagases, 108.

**ΑΔΕΛΦΟΥ ΤΟΥ ΒΑΣΙΛΕΩΣ** Spalyris, 100.

**ΑΝΙΚΗΤΟΥ** Lysias, 29, 166; Artemidorus, 54, 170; Philoxenus, 56; Demetrius, 163.

**ΑΥΤΟΚΡΑΤΟ[** Gondophares, 174.

**ΒΑΣΙΛΕΥΟΝΤΟΣ** Agathocles, 10; Soter, 114.

**ΒΑΣΙΛΕΥΟΝΤΟΣ ΒΑΣΙΛΕΩΝ** Abdagases, 107; Arsaces Dikaios, 174.

**ΒΑΣΙΛΕΩΣ ΑΔΕΛΦΟΥ** Spalirises, 100.

**ΒΑΣΙΛΕΩΣ ΒΑΣΙΛΕΩΝ** Gondophares, 104; Kanerkes, 129.

**ΒΑΣΙΛΕΩΣ ΒΑΣΙΛΕΩΝ ΜΕΓΑΛΟΥ** Maues, 68, 172; Azos, 73, 173; Azilises, 92; Vonones, 98, 173; Spalirises, 101; Gondophares, 103, 174; Orthagnes, 109; Pacoros, 110; Soter, 114; Kalphises II., 126.

**ΒΑΣΙΛΕΩΣ ΜΕΓΑΛΟΥ** Eucratides, 14, 165; Apollodotus II., 37; Hippostratus, 59; Azos, 90; Spalirises, 102; Gondophares, 105; Sanabares, 113.

**ΔΙΚΑΙΟΥ** Agathocles, 10, 164; Heliocles, 21, 166; Archebius, 32, 167; Strato I., 41; Menander, 50; Zoilus, 52, 170; Spalyris, 100; Theophilus, 167; Arsaces, 174.

**ΕΠΙΦΑΝΟΥΣ** Plato, 20; Strato I., 40, 168.

**ΕΥΕΡΓΕΤΟΥ** Telephus, 171.

**ΘΕΟΤΡΟΠΟΥ** Agathocleia, 43.

**ΘΕΟΥ** Euthydemus I., 10; Antimachus I., 12, 164; Gondophares, 103; Arsaces, 175.

**ΝΙΚΑΤΟΡΟΣ** Amyntas, 61; Antiochus of Syria, 164.

**ΝΙΚΗΦΟΡΟΥ** Antialeidas, 25, 166; Archebius, 32, 167; Epander, 51, 169; Antimachus II., 55.

**ΣΑΚΑ ΚΟΙΡΑΝΟΥ (ΚΟΡΡΑΝΟΥ)** Hemus, 116.

**ΣΑΤΡΑΠΟΥ** Zeionises, 110.

**ΣΩΤΗΡΟΣ** Diodotus, 10, 164; Diomedes, 31; Apollodotus I., 34, 167; Apollodotus II., 37; Strato I., 40, 168; Menander, 44, 168; Dionysius, 51; Zoilus, 52; Apollophanes, 54; Nicias, 58, 171; Hippostratus, 59; Hermaeus, 62, 172; Kanjalsala, 67; Gondophares, 105; Abdagases, 107; Soter, 114; Kadphises II., 126; Strato II., 168.

**ΤΥΡΑΝΝΟΥΝΤΟΣ** Hemus, 116.

**ΥΙΟΥ** Zeionises, 111; Strato II., 168.

**ΦΙΛΟΠΑΤΟΡΟΣ** Apollodotus II., 37.

## B. SCYTHIC, IN GREEK LETTERS.

**ΖΑΘΟΥ** Kadaphes, 123.

**ΚΟΡΑΝΟ** Kanerkes, 130; Hooerkes, 136.

**ΡΑΘ** Kanerkes, 130, 175; Hooerkes, 136.

**ΡΑΘΑΝΑΘ** Kanerkes, 130, 175; Hooerkes, 136.

**ΣΥ** Hermaeus, 120, 172; Kadaphes, 123.

**ΧΟΡΑΝ (ΚΟΡΟΝ, &c.)** Kadphises I., 122; Kadaphes, 123.

## C. INDIAN TITLES AND WORDS.

Apudihataa, Lycias, 29; Artemidorus, 51, 170; Philoxenus, 56.

Aparajitasa, Demetrius, 163.

Apudihataa, Gondophares, 105.

Apudihatachakasa, Kanjalsala, 67.

Bhrudaputrasa, Abdagases, 107.

Bhrata, Spalahores, 173.

Chia, Strato II., 168.

Chhatrapasa, Ranjabala, 67; Zeionises, 110.

Devatratatasa (Devaladasa), Gondophares, 103.

Dhramathidasa, Kadphises I., 120.

Dhramikasa (Dhraminasa), Heliocles, 23; Archebius, 32, 167; Strato I., 41; Menander, 50; Zeilus, 52, 170; Azes, 90; Spalahores, 98, 173; Spalagadanes, 99; Spalirises, 100; Gondophares, 105; Theophilus, 167.

Hiduja Same, Agathocles, 12.

Jayadharasa, Antialeidas, 25, 166; Archebius, 32, 167; Epander, 51, 169; Antimachus II., 55; Amyntas, 61.

Jayantasa (Jayatasa), Hippostratus, 59; Aspvarma, 91.

Kariṣṭyo nagara devata, Eueratides, 19.

Kujula (Kuyula), Kadphises I., 120; Kadaphes, 123.

Kushana (Khushana), Kadphises I., 120; Kadaphes, 123.

Mahachhatrapasa, Ranjabala, 67.

Maharajasa, *Passim* after Eueratides.

Maharajabhrata (Maharajabhrata), Spalahores, 98; Spalirises, 100.

Mahatasa (Mahatakasa), Hippostratus, 59; Maues, 68, 172; Azes, 73, 102, 173; Azilises, 93, 173; Spalirises, 101; Gondophares, 103; Orthagnes, 109; Pacores, 110; Soter, 114; Eueratides, 165; Hormaeus, 172; Arsaces, 174.

Mahisvarasa, Kadphises II., 124.

Palanakramasa, Telephus, 171.

Pratichhasa, Strato I., 40, 168.

Putrasa, Aspvarma, 91; Spalagadanes, 99; Zeionises, 110; Strato II., 168.

Rajadirajasa, Maues, 68, 172; Azes, 77; Azilises, 93; Gondophares, 103; Orthagnes, 109; Pacores, 110; Soter, 114; Kadphises II., 124; Eueratides, 165.

Rajarajasa, Azes, 73, 173; Azilises, 94, 173; Gondophares, 101; Strato II., 168; Arsaces Dikaios, 174.

Rajine, Pantaleon, 9; Agathocles, 11.

Sachhadramaphidasa, Kadaphes, 123.

Sagaba, Orthagnes, 109.

Sampriyapita, Strato II., 168.

Sarvaloga isvarasa, Kadphises II., 124.

Sasasa, Gondophares, 106.

Strategasa, Aspavarma, 91.

Tradatasa, Diomedes, 31; Apollodotus I., 34, 167; Strato I., 40, 168; Strato II., 37; Menander, 44, 168; Dionysius, 51, 162; Zailas, 52; Apollopheanes, 54; Nicus, 58, 171; Hippostratus, 59; Hermeneus, 62; Gondophares, 103; Abdagastes, 107; Soter, 114; Kadphises II., 124; Arsaces Dikaios, 174.

Virshabha, Uncert., 162.

Yavugasa (Yauasa), Kadphises I., 120; Kadaphes, 123.

## INDEX IV.

### REMARKABLE INSCRIPTIONS AND LEGENDS.

- ΑΘΡΟ, ΑΘΟΡΟ** Kanerkes, 130, 132; Hooerkes, 136, 153, 156.  
**ΑΛΕΞΑΝΔΡΟΥ ΤΟΥ ΦΙΛΙΠ-ΠΟΥ** Agathocles, 10.  
**ΑΝΤΙΟΧΟΥ ΝΙΚΑΤΟΡΟΣ** Agathocles, 164.  
**ΑΡΑΕΙΧΡΟ** Hooerkes, 136.  
**ΑΡΔΗΘΟΥ** Pyreosles, 117.  
**ΑΡΔΟΧΡΟ** Kanerkes, 130, 133; Hooerkes, 137, 154, 156.  
**ΒΙΖΑΓΟ** Hooerkes, 149.  
**ΒΟΔΔΟ, ΒΟΥΔΟ** Kanerkes, 130, 175.  
**ΔΙΟΔΟΤΟΥ ΣΩΤΗΡΟΣ** Agathocles, 10; Antimachus I., 164.  
**ΔΟΧΡΟ** Hooerkes, 138.  
**ΕΥΘΥΔΗΜΟΥ ΘΕΟΥ** Agathocles, 10.  
**ΗΛΙΟΣ** Kanerkes, 129, 175.  
**ΗΡΑΚΙΛΟ, ΗΡΑΚΛΟ** Hooerkes, 138, 154.  
**ΑΡΟΟΑΣΠΟ** Kanerkes, 130.  
**ΜΑΑΣΗΝΟ** Hooerkes, 138, 150.  
**ΜΑΚΑΡΟΥ** Pyrkodes, 117.  
**ΜΑΝΔΟΒΑΓΟ** Hooerkes, 139.  
**ΜΛΟ** Kanerkes, 131, 133; Hooerkes, 139, 154, 156.  
**ΜΕΙΡΟ, ΜΙΗΡΟ, ΜΙΟΡΟ** Kanerkes, 131, 134; Hooerkes, 138, 141, 144, 155, 157.  
**ΝΑΝΑ, ΝΑΝΑΡΟ** Kanerkes, 131, 134; Hooerkes, 144, 158; Bazodeo, 159.  
**ΝΑΝΑΙΑ** Uncert. king, 119; Kanerkes, 129.  
**ΟΑΔΟ** Kanerkes, 135.  
**ΟΑΝΙΝΔΑ** Hooerkes, 147.  
**ΟΔΥΟ ΒΟΥ ΣΑΚΑΜΑ** Kanerkes, 133.  
**ΟΚΡΟ, ΟΚΡΑ** Kanerkes, 132, 135; Hooerkes, 147, 155, 158; Bazodeo, 159.  
**ΟΝΙΑ?** Hooerkes, 144.  
**ΟΡΛΑΓΝΟ** Kanerkes, 132.  
**ΡΑΟΡΗΘΟΡΟ** Hooerkes, 148.  
**ΡΙΟΜ?** Hooerkes, 149.  
**ΣΑΛΗΝΗ** Kanerkes, 129.  
**ΣΑΡΑΠΟ** Hooerkes, 149.  
**ΣΚΑΝΔΟ ΚΟΜΑΡΟ** Hooerkes, 149.  
**ΤΑΥΡΟΣ** Uncert., 162.  
**ΦΑΡΡΟ, ΦΑΡΟ** Kanerkes, 132; Hooerkes, 150.  
**ΩΡΟΝ** Hooerkes, 153.

TABLE  
FOR  
CONVERTING ENGLISH INCHES INTO MILLIMÈTRES  
AND THE  
MEASURES OF MIONNET'S SCALE.

ENGLISH INCHES		FRENCH MILLIMÈTRES
4		100
3.5		95
3		90
2.5		85
2		80
1.5		75
1		70
.9		65
.8		60
.7		55
.6		50
.5		45
.4		40
.3		35
.2		30
.1		25
		20
		15
		10
		5
		0

ENGLISH INCHES	MIONNET'S SCALE	FRENCH MILLIMÈTRES
4	39	100
3.5	38	95
3	37	90
2.5	36	85
2	35	80
1.5	34	75
1	33	70
.9	32	65
.8	31	60
.7	30	55
.6	29	50
.5	28	45
.4	27	40
.3	26	35
.2	25	30
.1	24	25
	23	20
	22	15
	21	10
	20	5
	19	0

## T A B L E

OF




THE RELATIVE WEIGHTS OF ENGLISH GRAINS AND FRENCH GRAMMES.

Grains.	Grammes.	Grains.	Grammes.	Grains.	Grammes.	Grains.	Grammes.
1	064	41	2-656	81	5-248	121	7-840
2	129	42	2-720	82	5-312	122	7-905
3	194	43	2-785	83	5-378	123	7-970
4	259	44	2-850	84	5-442	124	8-035
5	324	45	2-915	85	5-508	125	8-100
6	388	46	2-980	86	5-572	126	8-164
7	453	47	3-045	87	5-637	127	8-229
8	518	48	3-110	88	5-702	128	8-294
9	583	49	3-175	89	5-767	129	8-359
10	648	50	3-240	90	5-832	130	8-424
11	712	51	3-304	91	5-896	131	8-488
12	777	52	3-368	92	5-961	132	8-553
13	842	53	3-434	93	6-026	133	8-618
14	907	54	3-498	94	6-091	134	8-682
15	972	55	3-564	95	6-156	135	8-747
16	1-036	56	3-628	96	6-220	136	8-812
17	1-101	57	3-693	97	6-285	137	8-877
18	1-166	58	3-758	98	6-350	138	8-942
19	1-231	59	3-823	99	6-415	139	9-007
20	1-296	60	3-888	100	6-480	140	9-072
21	1-360	61	3-952	101	6-544	141	9-136
22	1-425	62	4-017	102	6-609	142	9-200
23	1-490	63	4-082	103	6-674	143	9-265
24	1-555	64	4-146	104	6-739	144	9-330
25	1-620	65	4-211	105	6-804	145	9-395
26	1-684	66	4-276	106	6-868	146	9-460
27	1-749	67	4-341	107	6-933	147	9-525
28	1-814	68	4-406	108	6-998	148	9-590
29	1-879	69	4-471	109	7-063	149	9-655
30	1-944	70	4-536	110	7-128	150	9-720
31	2-008	71	4-600	111	7-192	151	9-784
32	2-073	72	4-665	112	7-257	152	9-848
33	2-138	73	4-729	113	7-322	153	9-914
34	2-202	74	4-794	114	7-387	154	9-978
35	2-267	75	4-859	115	7-452	155	10-044
36	2-332	76	4-924	116	7-516	156	10-108
37	2-397	77	4-989	117	7-581	157	10-173
38	2-462	78	5-054	118	7-646	158	10-238
39	2-527	79	5-119	119	7-711	159	10-303
40	2-592	80	5-184	120	7-776	160	10-368

T A B L E  
OF  
THE RELATIVE WEIGHTS OF ENGLISH GRAINS AND FRENCH GRAMMES.

Grains.	Grammes.	Grains.	Grammes.	Grains.	Grammes.	Grains.	Grammes.
161	10.432	201	13.024	241	15.616	290	18.79
162	10.497	202	13.089	242	15.680	300	19.44
163	10.562	203	13.154	243	15.745	310	20.08
164	10.626	204	13.219	244	15.810	320	20.73
165	10.691	205	13.284	245	15.875	330	21.38
166	10.756	206	13.348	246	15.940	340	22.02
167	10.821	207	13.413	247	16.005	350	22.67
168	10.886	208	13.478	248	16.070	360	23.32
169	10.951	209	13.543	249	16.135	370	23.97
170	11.016	210	13.608	250	16.200	380	24.62
171	11.080	211	13.672	251	16.264	390	25.27
172	11.145	212	13.737	252	16.328	400	25.92
173	11.209	213	13.802	253	16.394	410	26.56
174	11.274	214	13.867	254	16.458	420	27.20
175	11.339	215	13.932	255	16.524	430	27.85
176	11.404	216	13.996	256	16.588	440	28.50
177	11.469	217	14.061	257	16.653	450	29.15
178	11.534	218	14.126	258	16.718	460	29.80
179	11.599	219	14.191	259	16.783	470	30.45
180	11.664	220	14.256	260	16.848	480	31.10
181	11.728	221	14.320	261	16.912	490	31.75
182	11.792	222	14.385	262	16.977	500	32.40
183	11.858	223	14.450	263	17.042	510	33.04
184	11.922	224	14.515	264	17.106	520	33.68
185	11.988	225	14.580	265	17.171	530	34.34
186	12.052	226	14.644	266	17.236	540	34.98
187	12.117	227	14.709	267	17.301	550	35.64
188	12.182	228	14.774	268	17.366	560	36.28
189	12.247	229	14.839	269	17.431	570	36.93
190	12.312	230	14.904	270	17.496	580	37.58
191	12.376	231	14.968	271	17.560	590	38.23
192	12.441	232	15.033	272	17.625	600	38.88
193	12.506	233	15.098	273	17.689	700	45.36
194	12.571	234	15.162	274	17.754	800	51.84
195	12.636	235	15.227	275	17.819	900	58.32
196	12.700	236	15.292	276	17.884	1000	64.80
197	12.765	237	15.357	277	17.949	2000	129.60
198	12.830	238	15.422	278	18.014	3000	194.40
199	12.895	239	15.487	279	18.079	4000	259.20
200	12.960	240	15.552	280	18.144	5000	324.00










A



2 A



3 A




4



A




A




A




A




A



A



A




A



A




A



10 A




A




A




A




A








Æ




Æ



Æ




Æ




NI




Æ



Æ



Æ



Æ







1

AR



2

AR



3

AR



4

AR




5

AR



7

N1



6

N1





8

AR




9

AR



10

AR








1

AR



2

AR



3

AR



4

AR



5

AR



6

AR




7

AR



8

AR



9

AR



10

AR








11

AR











1 R




2



R



3



R



4



R




5



R



6



R



7



R



8



R




9



R



10



R




11



R




12



R




13



R




14



R





























Æ




Æ




Æ





Æ



Æ



Æ




Æ



Æ



Æ




Æ



Æ









Æ



Æ









Α



2

Α



3

Α



4

Α




5

Α





6

Α



7

Α



8

Α





9

Α




10

Α



11

Α







A



A



A



A




A



A




A




A




A




A



A



A







1



2



3



4



5




6





7





8




9




10




11



12









1

2



3


4




5



6



7



8




9



10



11




12



13



14




15




16



17



18



19






1

AR



2

AR




3

AR




4

AR



5

AR




6

AR



7

AR




8

AR



9

AR





10

AR




11

AR




12

AR








1

Æ



2

Æ



3

Æ



4

Æ



5

Æ



6

Æ





7

Æ





8

Æ





9

Æ



10

Æ



11

Æ




12


Æ












Æ



Æ




Æ



Æ



Æ




Æ



Æ



Æ



Æ



Æ





Æ




Æ






























1 A



2



A



3 A



4 A



5 A



6 A



7 A



8 A



9



A



10 A



11



A



12



A



13 A



14 A



15 A



16



A



17 A



18 A



19 A



20 A



21 A



22 A



23 A



24 A





1 N



2 N



3 N



4 N



5 N



6 N



7 N



8 N



9 N



10 N



11 N



12 N



13 N



14 N



15 N



16 N



17 N



18 N




19 N




20 N



21 N



22 N



23 N



24 N



25 N



26 N



27 N



28 N



29 N



30 N



31 N



32 N





1 A



2

A



3 A





4

A



5

A




6

A




7

A



8

A



9

A




10

A



11

A



12

A



13

A



14

A



15

A




















AR




AE




AR



AR




AR




AE



AR




AR




AR




AR




AR



AE



AE



AR

Vol- 11.5  
21/11/75

*"A book that is shut is but a block"*

CENTRAL ARCHAEOLOGICAL LIBRARY

GOVT. OF INDIA  
Department of Archaeology  
NEW DELHI.

Please help us to keep the book  
clean and moving.